Dear Senators LODGE, Broadsword & Werk, and Representatives RAYBOULD, Harwood & Elaine Smith:

The Legislative Services Office, Research and Legislation, has received the enclosed rules of the Department of Environmental Quality: IDAPA 58.01.08 - Idaho Rules for Public Drinking Water Systems (Docket #58-0108-0801).

Pursuant to Section 67-454, Idaho Code, a meeting on the enclosed rules may be called by the cochairmen or by two (2) or more members of the subcommittee giving oral or written notice to Research and Legislation no later than fourteen (14) days after receipt of the rules' analysis from Legislative Services. The final date to call a meeting on the enclosed rules is no later than 8-19-08. If a meeting is called, the subcommittee must hold the meeting within forty-two (42) days of receipt of the rules' analysis from Legislative Services. The final date to hold a meeting on the enclosed rules is 9-17-08.

\_\_\_\_\_The germane joint subcommittee may request a statement of economic impact with respect to a proposed rule by notifying Research and Legislation. There is no time limit on requesting this statement, and it may be requested whether or not a meeting on the proposed rule is called or after a meeting has been held.

To notify Research and Legislation, call 334-2475, or send a written request to the address or FAX number indicated on the memorandum enclosed.

# **MEMORANDUM**

TO: Rules Review Subcommittee of the Senate Health and Welfare Committee and

the House Environment, Energy and Technology Committee

FROM: Principal Legislative Research Analyst - Katharine Gerrity

DATE: July 31, 2008

SUBJECT: Department of Environmental Quality

IDAPA 58.01.08 - Idaho Rules For Public Drinking Water Systems

The Department of Environmental Quality submits notice of proposed rulemaking at IDAPA 58.01.08 - Idaho Rules For Public Drinking Water Systems. According to the Department, under the current rules a water main extension, whether approved for construction by the Department or by a qualified licensed professional engineer, is a material modification to the public water system. In addition, the Department notes that the current rules also specify that all portions of an existing system that are affected by a water main extension must be in compliance with the rules in effect at the time the project is reviewed and approved. According to the Department, this requirement could "in some cases require upgrades to existing parts of the water system to meet criteria for pumping redundancy, standby power, fire flow, and other applicable rule requirements such as completion of a facility plan." The Department states that the rules are being modified so that the engineering community can approve simple water main extensions as provided in Section 39-118, Idaho Code. The term "simple water main extension" is defined in the changes to the rules.

The Department also delineates in its Notice of Rulemaking additional changes that are being proposed. The Department notes that drinking water system owners and operators, developers, consultants, engineers, cities, counties, industry, drinking water professional organizations, and the public at large may be interested in commenting on the proposed rules. Negotiated rulemaking was conducted.

The Department states that there is no federal law or regulation that is comparable to plan and specification review and facility standard provisions. The Department also states that the engineering standards for design, construction, and operation of public drinking water systems

regulates activities that are not regulated by the federal government. The Department adds that the rules include facility and design standards which are intended to protect human health and the environment, but that the standards are for the design and construction of public drinking water facilities. The Department notes that these rules are not based upon any express estimate or analysis of risk to public health or the environment, but instead, "the facility and design standards are based upon guidelines set forth in documents, such as the 'Recommended Standards for Water Works' and the 'American Water Works Association Standards,' that are generally accepted and used throughout the United States by engineers and state regulators."

We have no specific comments relating to the proposed rulemaking. We did contact the Department and confirmed that the rule changes are in large part prompted by statutory changes that have been made, as well as user concerns and suggestions relating to different problem areas that were pinpointed and addressed during negotiated rulemaking. The rule appears to be authorized pursuant to Chapter 1, Title 39, and Chapter 21, Title 37, Idaho Code.

cc: Department of Environmental Quality
Paula J. Wilson
Michael Stambulis

# **IDAPA 58 - DEPARTMENT OF ENVIRONMENTAL QUALITY**

#### 58.01.08 - IDAHO RULES FOR PUBLIC DRINKING WATER SYSTEMS

#### **DOCKET NO. 58-0108-0801**

#### **NOTICE OF RULEMAKING - PROPOSED RULE**

**AUTHORITY:** In compliance with Section 67-5221(1), Idaho Code, notice is hereby given that this agency has initiated proposed rulemaking procedures. The action is authorized by Chapter 1, Title 39, Idaho Code, and Chapter 21, Title 37, Idaho Code.

PUBLIC HEARING SCHEDULE: No hearings have been scheduled. Pursuant to Section 67-5222(2), Idaho Code, a public hearing will be held if requested in writing by twenty-five (25) persons, a political subdivision, or an agency. Written requests for a hearing must be received by the undersigned on or before August 20, 2008. If no such written request is received, a public hearing will not be held.

**DESCRIPTIVE SUMMARY:** The following is a nontechnical explanation of the substance and purpose of the proposed rulemaking:

Under the provisions of IDAPA 58.01.08, Idaho Rules for Public Drinking Water Systems, a water main extension, whether approved for construction by the Department of Environmental Quality (DEQ) or by a qualified licensed professional engineer (QLPE), is a material modification to the public water system. The current rules also specify that all portions of the existing system that are affected by the water main extension must be in compliance with the rules in effect at the time the project is reviewed and approved. This requirement could in some cases require upgrades to existing parts of the water system to meet criteria for pumping redundancy, standby power, fire flow, and other applicable rule requirements such as completion of a facility plan.

The objective of this rulemaking is to modify the recently updated Idaho Rules for Public Drinking Water Systems so that the engineering community can approve simple water main extensions as intended by 2005 Senate Bill 1220 and as codified at Section 39-118, Idaho Code. The proposed rules define a simple water main extension as a new or replacement water main(s) that is connected to existing water main facilities and does not require the addition of system components designed to control quantity or pressure, including, but not limited to, booster stations, new sources, pressure reducing stations, or reservoirs; and continues to provide the required pressure and quantity for the system.

The following list sets out the major issues included in the proposed rules:

- 1. Add and/or revise definitions (Section 003) and revise rule sections as necessary;
- Clarify Section 500, Demonstration of Technical, Financial, and Managerial Capacity;
- 3. Revise Section 501, General Design Requirements for Public Drinking Water Systems;
- 4. Modify the content of facility plans and preliminary engineering reports contained in Sections 502 and 503, respectively;
- Revise Section 504, Review of Plans and Specifications;
- 6. Clarify separation requirements for sources of contamination from public drinking water wells (Sections 510-512, and 900);
- Modify sections regarding spring sources and ground water sources (Sections 513 and 514); Clarify Section 531, Design Standards for Chemical Application;
- Add and clarify design requirements for drinking water distribution systems (Section 542);
- 10. Further define storage structures and facilities (Section 544); and
- 11. Clarify several operating criteria for public drinking water systems (Section 552).

This proposed rule also includes any necessary corrections that are typographical and nonsubstantive in nature (e.g., making corrections for consistency with other sections in this rule chapter, IDAPA 58.01.16, Wastewater Rules, and other DEQ rules). These changes were made based on feedback from the regulated community and DEQ staff who routinely use the rules.

Drinking water system owners and operators, developers, consultants, engineers, cities, counties, industry, drinking water professional organizations, and the public at large may be interested in commenting on this proposed rule. The proposed rule text is in legislative format. Language the agency proposes to add is underlined. Language the agency proposes to delete is struck out. It is these additions and deletions to which public comment should be addressed.

After consideration of public comments, DEQ intends to present the final proposal to the Board of Environmental Quality at the October 2008 Board meeting for adoption as a pending rule. The rule is expected to be final and effective upon the conclusion of the 2009 legislative session if adopted by the Board and approved by the Legislature.

**NEGOTIATED RULEMAKING:** The text of the proposed rule has been drafted based on discussions held and concerns raised during negotiations conducted pursuant to Idaho Code Section 67-5220 and IDAPA 04.11.01.810-815. On April 2, 2008, the Notice of Negotiated Rulemaking was published in the Idaho Administrative Bulletin, Vol. 08-4, pages 35 and 36, and a preliminary draft rule was made available for public review. Meetings were held on April 22, May 6, and May 20, 2008. Several members of the public participated in this negotiated rulemaking process by attending the meetings and by submitting written comments.

**IDAHO CODE SECTION 39-107D STATEMENT:** Section 39-107D, Idaho Code, provides that DEQ must meet certain requirements when it formulates and recommends rules which are broader in scope or more stringent than federal law or regulations, or which propose to regulate an activity not regulated by the federal government. There is no federal law or regulation that is comparable to plan and specification review and facility standard provisions set forth in these rules. Therefore, the changes to the rules are not broader in scope or more stringent than federal law or regulations.

Section 39-107D, Idaho Code, also applies to a rule which "proposes to regulate an activity not regulated by the federal government." The engineering standards for design, construction, and operation of public drinking water systems regulate activities that are not regulated by the federal government. These rules address the review and approval of plans and specifications for public drinking water systems and the standard by which the agency does the review and approval. This is not an activity regulated by the federal government. Therefore, Section 39-107D, Idaho Code, applies.

Section 39-107D(3), Idaho Code, provides that any rule subject to 39-107D that proposes a standard necessary to protect human health and the environment must also include in the rulemaking record and in the notice of rulemaking additional information. This additional information includes any estimates of risk accomplished, identification of populations or receptors addressed by any estimates, and other information related to an estimation of risk. These rules include facility and design standards which are intended to protect human health and the environment. The standards, however, are for the design and construction of public drinking water facilities. The rules are not based upon any express estimate or analysis of risk to public health or the environment. Instead, the facility and design standards are based upon guidelines set forth in documents, such as the "Recommended Standards for Water Works" and the "American Water Works Association Standards," that are generally accepted and used throughout the United States by engineers and state regulators.

**FISCAL IMPACT STATEMENT:** The following is a specific description, if applicable, of any negative fiscal impact on the state general fund greater than ten thousand dollars (\$10,000) during the fiscal year: Not applicable.

ASSISTANCE ON TECHNICAL QUESTIONS, SUBMISSION OF WRITTEN COMMENTS: For assistance on questions concerning the proposed rulemaking, contact Michael Stambulis at michael.stambulis@deq.idaho.gov, (208)373-0123.

Anyone can submit written comments by mail, fax or e-mail at the address below regarding this proposed rule. The Department will consider all written comments received by the undersigned on or before September 3, 2008.

Dated this 3rd day of July, 2008.

Paula J. Wilson Hearing Coordinator Department of Environmental Quality 1410 N. Hilton/Boise, Idaho 83706-1255 (208)373-0418/Fax No. (208)373-0481 paula.wilson@deq.idaho.gov

#### THE FOLLOWING IS THE TEXT OF DOCKET NO. 58-0108-0801

### 003. **DEFINITIONS.**

The definitions set forth in 40 CFR 141.2, revised as of July 1, 2006, are herein incorporated by reference except for the definition of the terms "action level," "disinfection," "noncommunity water system," and "person." (4-2-08)

- **01. Action Level.** The concentration of lead or copper in water that determines, in some cases, whether a water system must install corrosion control treatment, monitor source water, replace lead service lines, or undertake a public education program. (12-10-92)
  - **O2. Administrator.** The Administrator of the United States Environmental Protection Agency. (4-5-00)
  - **03. Annual Samples.** Samples that are required once per calendar year. (12-10-92)
- **04. Annular Opening**. As used in well construction, this term refers to the nominal inside diameter of the borehole minus the outside diameter of the casing divided by two (2). (3-30-07)
- **05. Aquifer.** A geological formation of permeable saturated material, such as rock, sand, gravel, etc., capable of yielding an economic quantity of water to wells and springs. (5-3-03)
- **06. Available.** Based on system size, complexity, and source water quality, a properly licensed operator must be on site or able to be contacted as needed to initiate the appropriate action in a timely manner. (4-6-05)
- **O7. Average Day Demand**. The volume of water used by a system on an average day based on a one (1) year period. See also the definition of Water Demand in these rules. (3-30-07)(\_\_\_\_\_)
- **08. Backflow**. The reverse from normal flow direction in a plumbing system or water system caused by back pressure or back siphonage. (12-10-92)
- **09. Bag Filters.** Pressure-driven separation devices that remove particulate matter larger than one (1) micrometer using an engineered porous filtration media. They are typically constructed of a non-rigid, fabric filtration media housed in a pressure vessel in which the direction of flow is from the inside of the bag to the outside.

  (4-2-08)
- **10. Bank Filtration**. A water treatment process that uses a well to recover surface water that has naturally infiltrated into ground water through a river bed or bank(s). Infiltration is typically enhanced by the hydraulic gradient imposed by a nearby pumping water supply or other well(s). (4-2-08)
  - **11. Board**. The Idaho Board of Environmental Quality.
- 12. Capacity. The capabilities required of a public drinking water system in order to achieve and maintain compliance with these rules and the requirements of the federal Safe Drinking Water Act. It is divided into three (3) main elements:

  (4-5-00)
- **a.** Technical capacity means the system has the physical infrastructure to consistently meet drinking water quality standards and treatment requirements and is able to meet the requirements of routine and emergency operations. It further means the ability of system personnel to adequately operate and maintain the system and to otherwise implement technical knowledge. Training of operator(s) is required, as appropriate, for the system size and complexity. (4-6-05)
- **b.** Financial capacity means the financial resources of the water system, including an appropriate budget; rate structure; cash reserves sufficient for <u>current operation and maintenance</u>, future needs and emergency situations; and adequate fiscal controls.

  (4-5-00)(\_\_\_\_)
  - c. Managerial capacity means that the management structure of the water system embodies the

(5-3-03)

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

# Docket No. 58-0108-0801 Proposed Rulemaking

aspects of water	treatment system operations, including, but not limited to;	<del>(4-5-00)</del> ()
i.	Short and long range planning;	(4-5-00)
ii.	Personnel management;	(4-5-00)
iii.	Fiduciary responsibility;	(4-5-00)
iv.	Emergency response;	(4-5-00)
v.	Customer responsiveness;	(4-5-00)
vi.	Source water protection;	(4-5-00)
vii.	Administrative functions such as billing and consumer awareness; and	(4-5-00)
viii.	Ability to meet the intent of the federal Safe Drinking Water Act.	(4-5-00)

- 13. Cartridge Filters. Pressure-driven separation devices that remove particulate matter larger than one (1) micrometer using an engineered porous filtration media. They are typically constructed as rigid or semi-rigid, self-supporting filter elements housed in pressure vessels in which flow is from the outside of the cartridge to the inside.

  (4-2-08)
- **14. Combined Distribution System.** The interconnected distribution system consisting of the distribution systems of wholesale systems and of the consecutive systems that receive finished water. (4-2-08)
- **15. Community Water System.** A public water system which serves at least fifteen (15) service connections used by year-round residents or regularly serves at least twenty-five (25) year-round residents. See also the definition of a Public Drinking Water System in these rules.
- 16. Components of Finished Water Storage. Storage is available to serve the system if the storage structure or facility is elevated sufficiently or is equipped with sufficient booster pumping capability to pressurize the system. Components of finished water storage are further defined as:

  (3-30-07)(\_\_\_\_\_)
- **a.** Dead Storage. Storage that is either not available for use in the system or can provide only substandard flows and pressures. (3-30-07)
- **b.** Effective Storage. Effective storage is all storage other than dead storage and is made up of the additive components described in  $p\underline{P}$  aragraphs  $\frac{003.12}{12}$ .c. through  $\frac{003.12}{12}$ .f. of this Subsection.
- **c.** Operational Storage. Operational storage supplies water when, under normal conditions, the sources are off. This component is the larger of; (3-30-07)
- i. The volume required to prevent excess pump cycling and ensure that the following volume components are full and ready for use when needed; or (3-30-07)
  - ii. The volume needed to compensate for the sensitivity of the water level sensors. (3-30-07)
- **d.** Equalization Storage. Storage of finished water in sufficient quantity to compensate for the difference between a water system's maximum pumping capacity and peak hour demand. (3-30-07)
  - **e.** Fire Suppression Storage. The water needed to support fire flow in those systems that provide it. (3-30-07)
- **f.** Standby Storage. Standby storage provides a measure of reliability or safety factor should sources fail or when unusual conditions impose higher than anticipated demands. <u>Normally used for emergency operation, if standby power is not provided, to provide water for eight (8) hours of operation at average day demand.</u>

<del>(3-30-07)</del>(\_\_\_\_)

- 17. Composite Correction Program (CCP). A systematic approach to identifying opportunities for improving the performance of water treatment and implementing changes that will capitalize on these opportunities. The CCP consists of two (2) elements: (4-5-00)
- a. Comprehensive Performance Evaluation (CPE). A thorough review and analysis of a treatment plant's performance-based capabilities and associated administrative, operation, and maintenance practices. It is conducted to identify factors that may be adversely impacting a plant's capability to achieve compliance and emphasizes approaches that can be implemented without significant capital improvements. The CPE must consist of at least the following components: assessment of plant performance; evaluation of major unit processes; identification and prioritization of performance limiting factors; assessment of the applicability of comprehensive technical assistance; and preparation of a CPE report. (4-5-00)
- **b.** Comprehensive Technical Assistance (CTA). The implementation phase that is carried out if the CPE results indicate improved performance potential. During the CTA phase, the system must identify and systematically address plant-specific factors. The CTA consists of follow-up to the CPE results, implementation of process control priority setting techniques, and maintaining long term involvement to systematically train staff and administrators. (4-5-00)
  - **18.** Compositing of Samples. The mixing of up to five (5) samples by the laboratory. (4-5-00)
- **19. Confining Layer.** A nearly impermeable subsurface stratum which is located adjacent to one (1) or more aquifers and does not yield a significant quantity of water to a well. (5-3-03)
- **20. Confirmation Sample.** A sample of water taken from the same point in the system as the original sample and at a time as soon as possible after the original sample was taken. (12-10-92)
- 21. Connection. Each structure, facility, or single family residence which is connected to a water system, and which is or could be used for domestic purposes, is considered a single connection. Multi-family dwellings and apartment, condominium, and office complexes are considered single connections unless individual units are billed separately for water by the water system, in which case each such unit shall be considered a single connection.

  (10-1-93)
- **22. Consecutive System.** A public water system that receives some or all of its finished water from one (1) or more wholesale systems. Delivery may be through a direct connection or through the distribution system of one (1) or more consecutive systems. (4-2-08)
  - **23. Consumer**. Any person served by a public water system. (12-10-92)
- **24. Consumer Confidence Report (CCR)**. An annual report that community water systems must deliver to their customers. The reports must contain information on the quality of the water delivered by the systems and characterize the risks (if any) from exposure to contaminants detected in the drinking water in an accurate and understandable manner. (4-5-00)
  - **25. Contaminant.** Any physical, chemical, biological, or radiological substance or matter in water. (12-10-92)
- **26. Cross Connection**. Any actual or potential connection or piping arrangement between a public or a consumer's potable water system and any other source or system through which it is possible to introduce into any part of the potable water system used water, water from any source other than an approved public water system, industrial fluid, gas or substance other than the intended potable water with which the system is supplied. Cross connections include bypass arrangements, jumper connections, removable sections, swivel or change-over devices and other temporary or permanent devices which, or because of which "backflow" can or may occur. (10-1-93)
- **27. Dead End Main**. A distribution main of any diameter and length that does not loop back into the distribution system. (3-30-07)

- 28. Dead Storage. Storage that is either not available for use in the system or can provide only substandard flows and pressures. See also the definition of Components of Finished Water Storage in these rules.
  - **282. Department.** The Idaho Department of Environmental Quality. (12-10-92)
  - **2930. Director**. The Director of the Department of Environmental Quality or his designee. (12-10-92)
- **301. Disinfection.** Introduction of chlorine or other agent or process approved by the Department, in sufficient concentration or dosage, and for the time required to kill or inactivate pathogenic and indicator organisms. (3-30-07)
- **342. Disinfection Profile**. A summary of daily Giardia lamblia inactivation through the drinking water treatment plant. The procedure for developing a disinfection profile is contained in 40 CFR 141.172 and 40 CFR 141.530-141.536. (5-3-03)
- **323. Distribution System.** Any combination of pipes, tanks, pumps, and other equipment which delivers water from the source(s), *and/or* treatment facility(ies), or a combination of source(s) and treatment facility(ies) to the consumer. Chlorination may be considered as a function of a distribution system. (3-16-04)(\_\_\_\_\_)
  - 334. **Drinking Water**. Means "water for human consumption." (3-30-07)
- **345. Drinking Water System**. All mains, pipes, and structures through which water is obtained and distributed, including wells and well structures, intakes and cribs, pumping stations, treatment plants, reservoirs, storage tanks and appurtenances, collectively or severally, actually used or intended for use for the purpose of furnishing water for drinking or general domestic use. (12-10-92)
- 356. **Dual Sample Set.** A set of two (2) samples collected at the same time and same location, with one (1) sample analyzed for TTHM and the other sample analyzed for HAA5. Dual sample sets are collected for the purposes of conducting an Initial Distribution System Evaluation (40 CFR Part 141, Subpart U) and for determining compliance with the TTHM and HAA5 MCLs under the Stage 2 Disinfection Byproducts Requirements (40 CFR Part 141, Subpart V). (4-2-08)
- **367. DWIMS**. Idaho Department of Environmental Quality Drinking Water Information Management System. Replaced by SDWISS April 2001. (3-15-02)
- 38. Effective Storage. Effective storage is all storage other than dead storage and is made up of the additive components described in Paragraphs c. through f. of the definition Components of Finished Water Storage in these rules.
- **379. Enhanced Coagulation**. The addition of sufficient coagulant for improved removal of disinfection byproduct precursors by conventional filtration treatment. Conventional filtration treatment is defined in 40 CFR 141.2. (5-3-03)
- **3840. Enhanced Softening**. The improved removal of disinfection byproduct precursors by precipitative softening. (4-5-00)
- 41. Equalization Storage. Storage of finished water in sufficient quantity to compensate for the difference between a water system's maximum pumping capacity and peak hour demand. See also the definition of Components of Finished Water Storage in these rules.
- **42.** Equivalent Dwelling Unit (EDU). A unit of measure that standardizes all land use types (housing, retail, office, etc.) to the level of demand created by a single-family detached housing unit within a water system. The demand for one (1) equivalent dwelling unit is equivalent to the amount of water provided to the average single-family detached housing unit within a water system. For example, a business designed to use three (3) times as much water as an average single-family detached housing unit would have a demand of three (3) equivalent dwelling units.

	<del>\</del>	_
3943. treatment technic Department that unreasonable risk	<b>Exemption</b> . A temporary deferment of compliance with a maximum contaminant level que requirement which may be granted only if the system demonstrates to the satisfaction of the system cannot comply due to compelling factors and the deferment does not cause a to public health. (12-10-9)	he an
water storage, and the future of the anticipated or una sometimes referre	<b>Facility Plan</b> . The facility plan for a public drinking water system describes the overall system of water, treatment processes and facilities, pumping stations and distribution piping, finished waste disposal. It is a comprehensive planning document for infrastructure and includes a plan of system/facility, including upgrades and additions. It is usually updated on a regular basis due anticipated growth patterns, regulatory requirements, or other infrastructure needs. A facility planed to as a master plan or facilities planning study. In general, a facility plan is an overall system-wice a project specific plan.  (3-30-0)	ed for to is de
4 <u>45</u> . in Sections 500 the rules must be follows:	<b>Facility Standards and Design Standards</b> . Facility standards and design standards are described hrough 552 of these rules. Facility and design standards found in Sections 500 through 552 of the lowed in the planning, design, construction, and review of public drinking water facilities. (3-30-0)	ese
<b>42<u>6</u>.</b> calculated by sys	<b>Fee Assessment</b> . A charge assessed on public drinking water systems based on a rate structu tem size. (10-1-9	
	<b>Filter Profile</b> . A graphical representation of individual filter performance, based on continuous ements or total particle counts versus time for an entire filter run, from startup to backwancludes an assessment of filter performance while another filter is being backwashed. (4-5-0)	sh
	<b>Finished Water</b> . Water that is introduced into the distribution system of a public water system as stribution and consumption without further treatment, except as necessary to maintain water quality system (e.g., booster disinfection, addition of corrosion control chemicals). (4-2-0)	ity
49. are defined as:	Finished Water Storage Structures or Facilities. Finished water storage structures or facilities.	<u>es</u>
<b>a.</b> bottom elevation	Above-ground storage structure or facility. A finished water storage structure or facility with above normal ground surface.	<u>a</u>
<u><b>b.</b></u> bottom elevation	Ground-level storage structure or facility. A finished water storage structure or facility with at normal ground surface.	_a )
bottom elevation surface.	Partially buried storage structure or facility. A finished water storage structure or facility with below normal ground surface and any portion of the structure or facility above normal ground.	<u>a</u> nd )
<u>d.</u> bottom elevation	Below-ground storage structure or facility. A finished water storage structure or facility with and top elevation below normal ground surface.	<u>a</u>
	<b>Fire Flow Capacity</b> . The water system capacity, in addition to maximum day demand, that fighting purposes within the water system or distribution system pressure zone. Adequacy of the flow capacity is determined by the local fire authority. (3-30-0)	he
51. See also the defin	Fire Suppression Storage. The water needed to support fire flow in those systems that provide nition of Components of Finished Water Storage in these rules.	<u>it.</u> )
52. one (1) or more c	Fixture Protection. The practice of installing backflow prevention assemblies or devices to isolaross connections within a customer's facility.	<u>ite</u> )

46<u>53</u>.

Flowing Stream. As used in the Long Term 2 Enhanced Surface Water Treatment Rule (40 CFR

Part 141, Subpart W), this term means a course of running water flowing in a definite channel.

(4-2-08)

- 4754. GAC10. Granular activated carbon filter beds with an empty bed contact time of ten (10) minutes based on average daily flow day demand and a carbon reactivation frequency of every one hundred eighty (180) days, except that the reactivation frequency for GAC10 used as a best available technology for compliance with MCLs established in the Stage 2 Disinfection Byproducts Requirements (40 CFR Part 141, Subpart V) shall be one hundred twenty (120) days.
- **4855. GAC20.** Granular activated carbon filter beds with an empty-bed contact time of twenty (20) minutes based on average daily flow and a carbon reactivation frequency of every two hundred forty (240) days. (4-2-08)
- **4956. Groundwater System**. A public water system which is supplied exclusively by a groundwater source or sources. (12-10-92)
- 507. Groundwater Under the Direct Influence of Surface Water. Any water beneath the surface of the ground with significant occurrence of insects or other macroorganisms, algae, or large diameter pathogens such as Giardia lamblia or Cryptosporidium, or significant and relatively rapid shifts in water characteristics such as turbidity, temperature, conductivity, or pH which closely correlate to climatological or surface water conditions. Direct influence must be determined for individual sources in accordance with criteria established by the State. The State determination of direct influence may be based on site-specific measurements of water quality, and/or documentation of well construction characteristics and geology with field evaluation, or a combination of water quality and documentation.
- **548. Haloacetic Acids (Five) (HAA5).** The sum of the concentrations in milligrams per liter of the haloacetic acid compounds (monochloroacetic acid, dichloroacetic acid, trichloroacetic acid, monobromoacetic acid, and dibromoacetic acid) rounded to two (2) significant figures after addition. (4-5-00)
- **529. Health Hazards**. Any condition which creates, or may create, a danger to the consumer's health. Health hazards may consist of, but are not limited to, design, construction, operational, structural, collection, storage, distribution, monitoring, treatment or water quality elements of a public water system. See also the definition of Significant Deficiency, which refers to a health hazard identified during a sanitary survey. (5-3-03)
  - **5360. Inorganic.** Generally refers to compounds that do not contain carbon and hydrogen. (12-10-92)
- 61. Internal or In-Plant Isolation. The practice of installing backflow prevention assemblies to protect an area within a water customer's facility from contaminating another part of the facility.
- **5462. Laboratory Certification Reciprocity**. Acceptance of a laboratory certification made by another state. Laboratory reciprocity may be granted to laboratories outside of Idaho after application, proof of home state certification, and EPA performance evaluation results are submitted and reviewed. Reciprocity must be renewed after a time specified by the Idaho Laboratory Certification Officer to remain valid. (4-5-00)
- **5563. Lake/Reservoir.** As used in the Long Term 2 Enhanced Surface Water Treatment Rule (40 CFR Part 141, Subpart W), this term means a natural or man-made basin or hollow on the Earth's surface in which water collects or is stored that may or may not have a current or single direction of flow. (4-2-08)
- **564. License.** A physical document issued by the Idaho Bureau of Occupational Licenses certifying that an individual has met the appropriate qualifications and has been granted the authority to practice in Idaho under the provisions of Chapter 24, Title 54, Idaho Code. (4-6-05)
- **5765. Locational Running Annual Average (LRAA)**. The average of sample analytical results for samples taken at a particular monitoring location during the previous four (4) calendar quarters, as set forth in the Stage 2 Disinfection Byproducts Requirements (40 CFR Part 141, Subpart V). (4-2-08)
  - **5866.** Log. Logarithm to the base ten (10).

(12-10-92)

- **5967. Material Deviation**. A change from the design plans that significantly alters the type or location of facilities, requires engineering judgment to design, or impacts the public safety or welfare. (4-11-06)
- **649. Maximum Contaminant Level (MCL)**. The maximum permissible level of a contaminant in water which is delivered to any user of a public water system. (3-30-07)
- **6270. Maximum Day Demand-***Rate*. The average rate of consumption for the twenty-four (24) hour period in which total consumption is the largest for the design year. See also the definition of Water Demand in these rules.
- <u>71.</u> <u>Maximum Pumping Capacity. The pumping capacity with the largest source or pump out of service.</u>
- 6372. Maximum Residual Disinfectant Level (MRDL). A level of a disinfectant added for water treatment that may not be exceeded at the consumer's tap without an unacceptable possibility of adverse health effects. For chlorine and chloramines, a public water system is in compliance with the MRDL, when the running annual average of monthly averages of samples taken in the distribution system, computed quarterly, is less than or equal to the MRDL. For chlorine dioxide, a public water system is in compliance with the MRDL when daily samples are taken at the entrance to the distribution system and no two (2) consecutive daily samples exceed the MRDL. MRDLs are enforceable in the same manner as maximum contaminant levels under Section 1412 of the Safe Drinking Water Act. There is convincing evidence that addition of a disinfectant is necessary for control of waterborne microbial contaminants. Notwithstanding the MRDLs listed in 40 CFR 141.65, operators may increase residual disinfectant levels of chlorine or chloramines (but not chlorine dioxide) in the distribution system to a level and for a time necessary to protect public health to address specific microbiological contamination problems caused circumstances such as distribution line breaks, storm runoff events, source water contamination, or cross-connections.
- 6473. Maximum Residual Disinfectant Level Goal (MRDLG). The maximum level of a disinfectant added for water treatment at which no known or anticipated adverse effect on the health of persons would occur, and which allows an adequate margin of safety. MRDLGs are nonenforceable health goals and do not reflect the benefit of the addition of the chemical for control of waterborne microbial contaminants. (4-5-00)
- 6574. Membrane Filtration. A pressure or vacuum driven separation process in which particulate matter larger than one (1) micrometer is rejected by an engineered barrier, primarily through a size-exclusion mechanism, and which has a measurable removal efficiency of a target organism that can be verified through the application of a direct integrity test. This definition includes the common membrane technologies of microfiltration, ultrafiltration, nanofiltration, and reverse osmosis. (4-2-08)
- **6675. Method Detection Limit (MDL)**. The lowest concentration which can be determined to be greater than zero with ninety-nine percent (99%) confidence, for a particular analytical method. (12-10-92)
- **676. New System.** Any water system that meets, for the first time, the definition of a public water system provided in Section 1401 of the federal Safe Drinking Water Act (42 U.S.C. Section 300f). This includes systems that are entirely new construction and previously unregulated systems that are expanding. (4-5-00)
- 6877. Noncommunity Water System. A public water system that is not a community water system. A non-community water system is either a transient noncommunity water system or a non-transient noncommunity water system. See also the definition of a Public Drinking Water System in these rules.

- **6978. Non-Potable Mains**. The pipelines that collect and convey non-potable discharges from or to multiple service connections. (4-11-06)
- **769. Non-Potable Services**. The pipelines that convey non-potable discharges from individual facilities to a connection with the non-potable main. This term also refers to pipelines that convey non-potable water from a pressurized irrigation system, reclaimed wastewater system, and other non-potable systems to individual consumers. (4-11-06)
- **7480. Nontransient Noncommunity Water System.** A public water system that is not a community water system and that regularly serves at least twenty-five (25) of the same persons over six (6) months per year. See also the definition of a Public Drinking Water System in these rules.
- **7281. Nuclear Facility.** Factories, processing plants or other installations in which fissionable material is processed, nuclear reactors are operated, or spent (used) fuel material is processed, or stored. (12-10-92)
- **7382. Operating Shift**. That period of time during which water system operator decisions that affect public health are necessary for proper operation of the system. (4-5-00)
- 83. Operational Storage. Operational storage supplies water when, under normal conditions, the sources are off. This component is the larger of the volume required to prevent excess pump cycling and ensure that the following volume components are full and ready for use when needed or the volume needed to compensate for the sensitivity of the water level sensors. See also the definition of Components of Finished Water Storage in these rules.
- **784. Owner/Purveyor of Water/Supplier of Water**. The person, company, corporation, association, or other organizational entity which holds legal title to the public water system, who provides, or intends to provide, drinking water to the customers, and/or and who is ultimately responsible for the public water system operation.

  (4 6 05)
- **785. Peak Hour Demand.** The highest hourly flow, excluding fire flow, that a water system or distribution system pressure zone is likely to experience in the design year. See also the definition of Water Demand in these rules.
- **726. Person.** A human being, municipality, or other governmental or political subdivision or other public agency, or public or private corporation, any partnership, firm, association, or other organization, any receiver, trustee, assignee, agent or other legal representative of the foregoing or other legal entity. (12-10-92)
- **727. Pesticides.** Substances which meet the criteria for regulation pursuant to the Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA), as amended, and any regulations adopted pursuant to FIFRA. For example, pesticides include, but are not limited to insecticides, fungicides, rodenticides, herbicides, and algaecides. (12-10-92)
  - **788. Plant.** A physical facility where drinking water or wastewater is treated or processed. (3-30-07)
- **789. Plant Intake**. The works or structures at the head of a conduit through which water is diverted from a source (e.g., river or lake) into the treatment plant. (4-2-08)
- **890. Point of Use (POU) Treatment Device.** A treatment device applied to a single tap used for the purpose of reducing contaminants in drinking water at that one tap. (3-30-07)
  - **891. Point of Use (POU) Treatment System**. A collection of POU treatment devices. (3-30-07)
  - **892. Potable Mains.** Pipelines that deliver potable water to multiple service connections. (3-30-07)
- **823. Potable Services.** Pipelines that convey potable water from a connection to the potable water main to individual consumers. (3-30-07)

- **894. Preliminary Engineering Report.** The preliminary engineering report for a public drinking water system facility is a report that addresses specific portions of the system or facility for which modifications are being designed. Modifications may include, but are not limited to, significant changes to existing processes or facilities, system expansion, addition of treatment, or installation of other processes and facilities. This report addresses specific purpose and scope, design requirements, alternative solutions, costs, operation and maintenance requirements, and other requirements as described in Section 503. Preliminary engineering reports are generally project specific as opposed to an overall system-wide plan, such as a facility plan. However, the preliminary engineering report shall describe modifications to the facility plan that may be required as a result of the proposed project. (3-30-07)
- 95. Premise Isolation or Containment. The practice of separating the customer's premise from the purveyor's system by means of a backflow prevention assembly installed on the service line before any distribution takes place.
- **8596. Presedimentation.** A preliminary treatment process used to remove gravel, sand, and other particulate material from the source water through settling before the water enters the primary clarification and filtration processes in a treatment plant. (4-2-08)
- **8697. Public Notice**. The notification of public water system consumers of information pertaining to that water system including information regarding water quality or compliance status of the water system. (12-10-92)
- 8798. Public Drinking Water System. A system for the provision to the public of water for human consumption through pipes or, after August 5, 1998, other constructed conveyances, if such system has at least fifteen (15) service connections, regardless of the number of water sources or configuration of the distribution system, or regularly serves an average of at least twenty-five (25) individuals daily at least sixty (60) days out of the year. Such term includes: any collection, treatment, storage, and distribution facilities under the control of the operator of such system and used primarily in connection with such system; and any collection or pretreatment storage facilities not under such control which are used primarily in connection with such system. Such term does not include any "special irrigation district." A public water system is either a "community water system" or a "noncommunity water system-"as further defined as:
- **a.** Community water system. A public water system which serves at least fifteen (15) service connections used by year-round residents or regularly serves at least twenty-five (25) year-round residents.
- <u>b.</u> Noncommunity water system. A public water system that is not a community water system. A non-community water system is either a transient noncommunity water system or a non-transient noncommunity water system.
- <u>c.</u> <u>Nontransient noncommunity water system. A public water system that is not a community water system and that regularly serves at least twenty-five (25) of the same persons over six (6) months per year. ( )</u>
- **d.** Transient noncommunity public water system. A noncommunity water system which does not regularly serve at least twenty-five (25) of the same persons over six (6) months per year.
  - **8892. Public Water System/Water System.** Means "public drinking water system." (4-5-00)
- **89100. Pump House**. An above-grade structure containing important water system components, such as a well, hydropneumatic tank, booster pump, pump controls, flow meter, well discharge line, or a treatment unit. Pump houses are often called well houses in common usage, even though in modern construction these structures may not contain either a well or a pump. These terms are used interchangeably in national standards and trade publications.

  (3-30-07)
- 101. Qualified Licensed Professional Engineer (QLPE). A professional engineer licensed by the state of Idaho; qualified by education or experience in the specific technical fields involved in these rules; and retained or employed by a city, county, quasi-municipal corporation, or regulated public utility for the purposes of plan and specification review.

- Quasi-Municipal Corporation. A public entity, other than community government, created or authorized by the legislature to aid the state in, or to take charge of, some public or state work for the general welfare. For the purpose of these rules, this term refers to drinking water districts.
- Regulated Public Utility. For the purpose of these rules, any public water system that falls under the jurisdiction of the Idaho Public Utilities Commission and is subject to the rules thereof.
- 92104. Repeat Compliance Period. Any subsequent compliance period after the initial compliance period. (12-10-92)
- 93105. Responsible Charge (RC). Responsible Charge means, active, daily on-site and/or on-call responsibility for the performance of operations or active, on-going, on-site, and or on-call direction of employees and assistants.
- 94106. Responsible Charge Operator. An operator of a public drinking water system, designated by the system owner, who holds a valid license at a class equal to or greater than the drinking water system classification, who is in responsible charge of the public drinking water system.
- 95107. Reviewing Authority. For those projects requiring preconstruction approval by the Department, the Department is the reviewing authority. For those projects allowing for preconstruction approval by others, pursuant to Subsection 504.03.b. of these rules, the qualified Idaho licensed professional engineer (QLPE) is also the reviewing authority. (3-30-07)(
  - 96108. Sampling Point. The location in a public water system from which a sample is drawn. (12-10-92)
- 97.109 Sanitary Defects. Any faulty structural condition which may allow the water supply to become contaminated. (12-10-92)
- 98110. Sanitary Survey. An onsite review of the water source, facilities, equipment, operation and maintenance of a public water system for the purpose of evaluating the adequacy of such source, facilities, equipment, operation and maintenance for producing and distributing safe drinking water. The sanitary survey will include, but is not limited to the following elements: (4-5-00)

a.	Source;	(4-5-00)
b.	Treatment;	(4-5-00)
c.	Distribution system;	(4-5-00)
d.	Finished water storage;	(4-5-00)
e.	Pumps, pump facilities, and controls;	(4-5-00)
f.	Monitoring and reporting and data verification;	(4-5-00)
g.	System management and operation; and	(4-5-00)

- Operator compliance with state requirements. h. (4-5-00)
- 99111. SDWIS-State. An acronym that stands for "Safe Drinking Water Information System-State Version." It is a software package developed under contract to the U.S. Environmental Protection Agency and used by a majority of U.S. states to collect, maintain, and report data about regulated public water systems. See also the definition of DWIMS. (5-3-03)
- 10012. Sewage. The water-carried human or animal waste from residences, buildings, industrial establishments or other places, together with such ground water infiltration and surface water as may be present. (3-30-07)

- **1013. Significant Deficiency.** As identified during a sanitary survey, any defect in a system's design, operation, maintenance, or administration, as well as any failure or malfunction of any system component, that the Department or its agent determines to cause, or have potential to cause, risk to health or safety, or that could affect the reliable delivery of safe drinking water. See also the definition of Health Hazards. (5-3-03)
- 114. Simple Water Main Extension. New or replacement water main(s) that require plan and specification review per these rules and that is connected to existing water main facilities and does not require the addition of system components designed to control quantity or pressure, including, but not limited to, booster stations, new sources, pressure reducing stations, or reservoirs; and continues to provide the pressure and quantity requirements of Subsection 552.01.
- 10215. Special Irrigation District. An irrigation district in existence prior to May 18, 1994 that provides primarily agricultural service through a piped water system with only incidental residential or similar use where the system or the residential or similar users of the system comply with the exclusion provisions in Section 1401(4)(B)(i)(II) or (III) of the Safe Drinking Water Act. (4-6-05)
- **10316. Spring.** A source of water which flows from a laterally percolating water table's intersection with the surface or from a geological fault that allows the flow of water from an artesian aquifer. (12-10-92)
- 117. Standby Storage. Standby storage provides a measure of reliability or safety factor should sources fail or when unusual conditions impose higher than anticipated demands. See also the definition of Components of Finished Water Storage in these rules.
- 118. Substantially Modified. The Department shall consider a public water system to be substantially modified when, as the result of one (1) or more projects, there is a combined increase of twenty-five percent (25%) or more above the system's existing configuration in the population served or number of service connections, the total length of transmission and distribution water mains, and the peak or average water demand.
- 10419. Substitute Responsible Charge Operator. An operator of a public drinking water system who holds a valid license at a class equal to or greater than the drinking water system classification, designated by the system owner to replace and to perform the duties of the responsible charge operator when the responsible charge operator is not available or accessible. (4-6-05)
- **10520. Surface Water System**. A public water system which is supplied by one (1) or more surface water sources or groundwater sources under the direct influence of surface water. Also called subpart H systems in applicable sections of 40 CFR Part 141. (4-5-00)
- **10621. SUVA** (**Specific Ultraviolet Absorption**). SUVA means Specific Ultraviolet Absorption at two hundred fifty-four (254) nanometers (nm), an indicator of the humic content of water. It is a calculated parameter obtained by dividing a sample's ultraviolet absorption at a wave length of two hundred fifty-four (254) nm (UV254) (in m=1) by its concentration of dissolved organic carbon (DOC) (in mg/l). (3-30-07)
- 10722. Total Organic Carbon (TOC). Total organic carbon in mg/l measured using heat, oxygen, ultraviolet irradiation, chemical oxidants, or combinations of these oxidants that convert organic carbon to carbon dioxide, rounded to two (2) significant figures. (4-5-00)
- **10823. Total Trihalomethanes (TTHM).** The sum of the concentration in milligrams per liter of the trihalomethane compounds (trichloromethane [chloroform], dibromochloromethane, bromodichloromethane and tribromomethane [bromoform]), rounded to two (2) significant figures. (4-2-08)
- 16924. Transient Noncommunity Public Water System. A noncommunity water system which does not regularly serve at least twenty-five (25) of the same persons over six (6) months per year. See also the definition of a Public Drinking Water System in these rules.
- 14025. Treatment Facility. Any place(s) where a public drinking water system or nontransient noncommunity water system alters the physical or chemical characteristics of the drinking water. Chlorination may

be considered as a function of a distribution system.

(4-5-00)

- **1#26. Turbidity.** A measure of the interference of light passage through water, or visual depth restriction due to the presence of suspended matter such as clay, silt, nonliving organic particulates, plankton and other microscopic organisms. Operationally, turbidity measurements are expressions of certain light scattering and absorbing properties of a water sample. Turbidity is measured by the Nephelometric method. (12-10-92)
- **1427. Two-Stage Lime Softening.** A process in which chemical addition and hardness precipitation occur in each of two (2) distinct unit clarification processes in series prior to filtration. (4-2-08)
- **1#328.** Uncovered Finished Water Storage Facility. A tank, reservoir, or other facility that is directly open to the atmosphere and used to store water that will undergo no further treatment to reduce microbial pathogens except residual disinfection. (4-2-08)
- **11429. Unregulated Contaminant**. Any substance that may affect the quality of water but for which a maximum contaminant level or treatment technique has not been established. (12-10-92)
- 130. Use Assessment. For the purpose of obtaining a waiver from certain monitoring requirements, a use assessment is an evaluation as to whether synthetic organic contaminants are being or have been used, manufactured, transported, stored, or disposed of in the watershed for surface water or the zone of influence for ground water.
- 14531. Variance. A temporary deferment of compliance with a maximum contaminant level or treatment technique requirement which may be granted only when the system demonstrates to the satisfaction of the Department that the raw water characteristics prevent compliance with the MCL or requirement after installation of the best available technology or treatment technique and the determent does not cause an unreasonable risk to public health. (12-10-92)
- 14632. Very Small Public Drinking Water System. A Community or Nontransient Noncommunity Public Water System that serves five hundred (500) persons or less and has no treatment other than disinfection or has only treatment which does not require any chemical treatment, process adjustment, backwashing or media regeneration by an operator (e.g. calcium carbonate filters, granular activated carbon filters, cartridge filters, ion exchangers). (4-5-00)
- 14733. Volatile Organic Chemicals (VOCs). VOCs are lightweight organic compounds that vaporize or evaporate easily. (10-1-93)
- 1<del>18</del>34. **Vulnerability Assessment**. A determination of the risk of future contamination of a public drinking water supply. (12-10-92)

14935. Waiver. (12-10-92)

- **a.** For the purposes of these rules, except Sections 500 through 552, "waiver" means the Department approval of a temporary reduction in sampling requirements for a particular contaminant. (3-30-07)
- **b.** For purposes of Sections 500 through 552, "waiver" means a dismissal of any requirement of compliance. (3-30-07)
- ${f c.}$  For the purposes of Section 010, "waiver" means the deferral of a fee assessment for a public drinking water system. (10-1-93)
- **12036. Wastewater.** Unless otherwise specified, sewage, industrial waste, agricultural waste, and associated solids or combinations of these, whether treated or untreated, together with such water as is present.

  (3-30-07)
- 12437. Water for Human Consumption. Water that is used by humans for drinking, bathing for purposes of personal hygiene (including hand-washing), showering, cooking, dishwashing, and maintaining oral hygiene. In

### DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

Docket No. 58-0108-0801 Proposed Rulemaking

common usage, the terms "culinary water," "drinking water," and "potable water" are frequently used as synonyms.

- (5-3-03)Water Demand. The volume of water requested by system users to satisfy their needs. Water 138. demand can be further categorized as: Average day demand. The volume of water used by a system on an average day based on a one (1) year period. Maximum day demand. The average rate of consumption for the twenty-four (24) hour period in b. consumption is the largest for the design year. Peak hour demand. The highest hourly flow, excluding fire flow, that a water system or distribution system pressure zone is likely to experience in the design year. 12239. Water Main. A pipe within a public water system which is under the control of the system operator and conveys water to two (2) or more service connections or conveys water to a fire hydrant. The collection of water mains within a given water supply is called the distribution system. Water Main Extension. As used in Subsection 504.03, an extension of the distribution system of an existing public water system that does not require a booster pumping station and is intended to increase the service area of the water system. Watershed. The land area from which water flows into a stream or other body of water which 1240.
- 12541. Wholesale System. A public water system that treats source water as necessary to produce finished water and then delivers some or all of that finished water to another public water system. Delivery may be through a direct connection or through the distribution system of one (1) or more consecutive systems. (4-2-08)

# (BREAK IN CONTINUITY OF SECTIONS)

#### 007. DISAPPROVAL DESIGNATION.

drains the area.

The Department or its agent may assign a disapproved designation to a public water system when:

(5-3-03)

(3-30-07)

- Defects. There are design and/or construction defects; or some combination of design and construction defects; or <del>(12-10-92)</del>(
  - 02. Operating Procedures. Operating procedures constitute a health hazard; or (12-10-92)
- Quality. Physical, chemical, microbiological or radiological quality does not meet the requirements of these rules; or (10-1-93)
  - 04. **Monitoring.** The required monitoring as specified in these rules has not been conducted; or (10-1-93)
- Unapproved Source. An unapproved source of drinking water is used or the system is interconnected with a disapproved water system. (12-10-92)
- 06. Non-Payment of Annual Fee Assessment. The annual drinking water system fee assessment is not paid as set forth in Section 010.
- **Public Notification.** The Department may require the owner of a water system that has been given a disapproval designation to notify the public. The manner, content, and timing of this notification will be determined

by the Department. This requirement is in addition to any public notification requirements set forth in Section 150 that may also apply to the disapproved system. (5-3-03)

## (BREAK IN CONTINUITY OF SECTIONS)

### 010. FEE SCHEDULE FOR PUBLIC DRINKING WATER SYSTEMS.

All regulated public drinking water systems shall pay an annual drinking water system fee. The fee shall be assessed to regulated public drinking water systems as provided in this section. (10-1-93)

**01. Effective Date**. Annual fees shall be paid for each fee year beginning October 1, 1993, and continuing for each succeeding year. (10-1-93)

**02.** Fee Schedule. (10-1-93)

**a.** Community and Nontransient noncommunity public drinking water systems shall pay an annual fee according to the following fee schedule:

Number of Connections	Fee
1 to 20	\$100
21 to 184	\$5 per connection, not to exceed a total of \$735 per system
185 to 3,663	\$4 per connection, not to exceed a total of \$10,988 per system
3,664 or more	\$3 per connection

(7-1-97)

- **b.** The annual fee for transient public drinking water systems is twenty-five dollars (\$25). (10-1-93)
- **c.** New public drinking water systems formed after October 1 will not pay a fee until the following October. (10-1-93)

- **a.** An annual fee assessment will be generated for each community and nontransient noncommunity public drinking water system listed in the Department's Safe Drinking Water Information System (SDWISS). (3-15-02)
- **b.** Community and nontransient noncommunity public drinking water systems will be notified each year of the official number of connections listed in SDWISS. Systems will have at least one (1) month to notify the Department if the number of connections listed in SDWISS is not in agreement with the system's records. (3-15-02)
- **c.** The official number of connections listed in SDWISS following each yearly update, as required in Subsection 010.03.b., will be used to calculate the annual fee for community and nontransient noncommunity public drinking water systems for the next fee year of October 1 through September 30. (3-15-02)
- **04. Billing**. An annual fee shall be assessed and a statement will be mailed to all community, nontransient noncommunity, and transient public drinking water systems listed in SDWISS by the Department on or before September 1 of each year. (3-15-02)

a. Payment of the annual fee shall be due on October 1, unless it is a Saturday, a Sunday, or a legal

holiday, in which event the payment shall be due on the successive business day. Fees paid by check or money order shall be made payable to the Idaho Department of Environmental Quality and sent to 1410 North Hilton Street, Boise, ID 83706-1255. (10-1-93)

- **b.** If a public water system consists of two hundred fifty (250) connections or more, the system may request to divide its annual fee payment into equal monthly or quarterly installments by submitting a request to the Department on the proper request form provided with the initial billing statement. (10-1-93)
- **c.** The Department will notify applicable systems, in writing, of approval or denial of a requested monthly or quarterly installment plan within ten (10) business days of the Department receiving such a request.
- **d.** If a public water system has been approved to pay monthly installments then each installment shall be due by the first day of each month, unless it is a Saturday, a Sunday, or a legal holiday, in which event the installment shall be due on the successive business day. (10-1-93)
- **e.** If a public water system has been approved to pay quarterly installments then each installment shall be due by the first day of the month of each quarter (October 1, January 1, April 1, and July 1), unless it is a Saturday, a Sunday, or a legal holiday, in which event the installment shall be due on the first successive business day.

  (10-1-93)
- **06. Delinquent Unpaid Fees**. A public water system will be delinquent in payment if its annual fee assessment has not been received by the Department by November 1; or if having first opted to pay monthly or quarterly installments, its monthly or quarterly installment has not been received by the Department by the last day of the month in which the monthly or quarterly payment is due. (10-1-93)

# 07. Suspension of Services and Disapproval Designation.

(7-1-97)

- **a.** For any system delinquent in payment of fee assessed under Subsections 010.02 and 010.06, in excess of ninety (90) days, technical services provided by the Department may be suspended except for the following:

  (7-1-97)
  - i. Issuance of monitoring waivers; (7-1-97)
  - ii. Review and processing of engineering reports; and (7-1-97)
- iii. Review of plans and specifications for design and construction as set forth in Sections 501 through 552. (3-30-07)
- **b.** For any system delinquent in payment of fee assessed under Subsections 010.02 and 010.06, in excess of one hundred and eighty (180) days, the Department may suspend all technical services provided by the Department including any of the following: (7-1-97)
  - i. Review and processing of engineering reports; (7-1-97)
- ii. Review of plans and specifications for design and construction as set forth in Sections 501 through 552; (3-30-07)
  - iii. Renewal of monitoring waivers; or (7-1-97)
  - iv. Granting of new monitoring waivers. (7-1-97)
- **c.** For any system delinquent in payment of fee assessed under Subsections 010.02 and 010.06, in excess of one hundred and eighty (180) days, the Department may disapprove the public water system pursuant to Subsection 007.06. (7-1-97)
  - 08. Reinstatement of Suspended Services and Approval Status. For any public water system for

which delinquency of fee payment, pursuant to Subsection 010.07, has resulted in *T*the suspension of technical services, *and/or* the disapproval of a public water system, or both, *pursuant to Subsection 010.07 may be reinstated* continuation of technical services, reinstatement of public water system approval, or both, will occur upon payment of delinquent annual fee assessments.

(7.1-97)(\_\_\_\_\_)

- **09. Enforcement Action**. Nothing in Section 010 waives the Department's right to undertake an enforcement action at any time, including seeking penalties, as provided in Section 39-108, Idaho Code. (7-1-97)
- **10. Responsibility to Comply.** Subsection 010.07 shall in no way relieve any system from its obligation to comply with all applicable state and federal drinking water statutes, rules, regulations, or orders.

# (BREAK IN CONTINUITY OF SECTIONS)

#### 013. USE OF GUIDANCE.

Guidance documents referenced in these rules are to be used to assist both designers and reviewers in determining a reasonable way to achieve compliance with the rules. Nothing in these rules makes the use of a particular guidance or guidance document mandatory. If the plans and specifications comply with applicable facility and design standards as set out in these rules, Section 39-118, Idaho Code, requires that the *reviewing authority* Department not substitute *his or her* its judgment for that of the design engineer concerning the manner of compliance. If the design engineer needs assistance as to how to comply with a particular rule, the design engineer may use the referenced guidance documents for that assistance. However, the design engineer may also use other guidance or provide documentation to substantiate his or her own professional judgment.

#### (BREAK IN CONTINUITY OF SECTIONS)

# 100. MONITORING AND ANALYTICAL REQUIREMENTS.

- 01. Microbiological Contaminant Sampling and Analytical Requirements. (10-1-93)
- **a.** 40 CFR 141.21, revised as of July 1, 2001, is herein incorporated by reference. (3-15-02)
- **b.** The Department may reduce the total coliform monitoring frequency for community water systems serving twenty-five (25) to one thousand (1000) persons, as specified in 40 CFR 141.21(a)(2) and Subsection 100.01. The Department may allow community water systems serving twenty-five (25) to one thousand (1000) persons to reduce the total coliform monitoring frequency to once per quarter when; (12-10-92)
  - i. The system submits a written request to the Department in advance of the requirement; and (12-10-92)
  - ii. There has been no history of total coliform contamination in it's current configuration; and (10-1-93)
- iii. The system has been in compliance with the total coliform monitoring requirements for the last three (3) years; and (12-10-92)
- iv. A sanitary survey has been conducted within the past five (5) years which indicates to the Department that there are no deficiencies which could affect microbial quality; and (12-10-92)
  - v. The system uses only a groundwater source that is protected. (12-10-92)
  - c. The Department may reduce the total coliform monitoring frequency for noncommunity water

systems serving less than one thousand (1000) persons as specified in 40 CFR 141.21(a)(3)(i) and Subsection 100.01. The Department may allow noncommunity water systems serving less than one thousand (1000) persons to reduce the total coliform monitoring frequency to once per year when; (12-10-92)

- i. The system submits a written request to the Department in advance of the requirement; and (12-10-92)
- ii. No coliforms have been detected in the last three (3) years of monitoring; and (12-10-92)
- iii. The system has been in compliance with the total coliform monitoring requirements for the last three (3) years; and (12-10-92)
- iv. A sanitary survey has been conducted within the past five (5) years which indicates to the Department that there are no deficiencies which could affect microbial quality; and (12-10-92)
  - v. The system uses only a groundwater source that is protected. (12-10-92)
- d. The Department may reduce the total coliform monitoring frequency for noncommunity water systems serving more than one thousand (1000) persons during any month the system serves one thousand (1000) persons or fewer as specified in 40 CFR 141.21(a)(3)(ii) and Subsection 100.01. The Department will allow noncommunity water systems serving more than one thousand (1000) persons to reduce the total coliform monitoring frequency for any month the system serves one thousand (1000) persons or fewer, down to a minimum of one (1) sample per year, provided; (10-1-93)
  - i. The system submits a written request to the Department in advance of the requirement; and (12-10-92)
  - ii. No coliforms have been detected in the last three (3) years of monitoring; and (12-10-92)
- iii. The system has been in compliance with the total coliform monitoring requirements for the last three (3) years; and (12-10-92)
- iv. A sanitary survey has been conducted within the past five (5) years which indicates that there are no deficiencies which could effect microbial quality; and (12-10-92)
  - v. The system uses only a groundwater source that is protected. (12-10-92)
- **e.** A system must collect repeat samples within twenty-four (24) hours of notification of positive results as specified in 40 CFR 141.21(b) and Subsection 100.01. The Department may allow a system to delay collection of repeat samples if the system; (12-10-92)
  - i. Identifies the cause of the contamination; (12-10-92)
  - ii. Is making progress towards correcting the problem; (12-10-92)
- iii. Submits a written request to delay collecting repeat samples and a written statement admitting an acute MCL violation; (12-10-92)
- iv. Follows public notification requirements specified under 40 CFR Part 141, Subpart Q, revised as of July 1, 2006, for Tier 1 MCL violations including notice for consumers to boil their water; (4-2-08)
  - v. Continues to collect the regularly scheduled number of routine samples; (12-10-92)
  - vi. Collects all repeat samples immediately following correction of the problem; and (12-10-92)
- vii. Collects five (5) routine samples during the month following the end of the violation as required under 40 CFR 141.21 (b)(5), unless waived as allowed under that paragraph. (12-10-92)

- **02. Turbidity Sampling and Analytical Requirements**. 40 CFR 141.22, revised as of July 1, 2001, is herein incorporated by reference. (3-15-02)
- **03. Inorganic Chemical Sampling and Analytical Requirements**. 40 CFR 141.23, revised as of July 1, 2004, is herein incorporated by reference. (4-6-05)
- **04.** Organic Chemicals Other Than Total Trihalometranes, Sampling and Analytical Requirements. 40 CFR 141.24, revised as of July 1, 2004, is herein incorporated by reference. (4-6-05)
- **05. Analytical Methods for Radioactivity**. 40 CFR 141.25, revised as of July 1, 2001, is herein incorporated by reference. (3-15-02)
- **Monitoring Frequency and Compliance Requirements for Radioactivity in Community Water Systems**. 40CFR 141.26, revised as of July 1, 2001, is herein incorporated by reference. (3-15-02)
  - **07.** Waivers and Vulnerability Assessments. (10-1-93)
- **a.** Waivers from sampling requirements in Subsections 100.03, 100.04, 200.01, <u>551.01.h.</u> <u>503.11</u> and <u>551.01.i.</u> <u>503.12</u> may be available to all systems for all contaminants except nitrate, nitrite, arsenic and trihalomethanes, and are based upon a vulnerability assessment, use assessment, <u>and/or</u> the analytical results of previous sampling, or some combination of vulnerability assessment, use assessment, and analytical results.

<del>(10 1 93)</del>( )

- **b.** There are two (2) general types of monitoring waivers: (12-10-92)
- i. Waivers based exclusively upon previous analytical data (12-10-92)
- ii. Waivers based on a use or vulnerability assessment. (12-10-92)
- **c.** Waivers are to be made by the Department on a contaminant specific basis and must be in writing.
- **d.** Vulnerability assessments may be conducted by the Department, the water system, or a third party organization. The Department shall approve or disapprove all vulnerability assessments in writing. (12-10-92)
- **e.** Water systems which do not receive waivers shall sample at the required initial and repeat monitoring frequencies. (12-10-92)
- **f.** If a system elects to request a waiver from monitoring, it shall do so in writing at least sixty (60) days prior to the required monitoring deadline date. (10-1-93)
- **08. Initial Monitoring Schedule**. In addition to the requirements specified in 40 CFR 141.23, revised as of July 1, 2004, 40 CFR 141.24, revised as of July 1, 2004, and 40 CFR 141.40, revised as of July 1, 2001, initial monitoring must be completed according to the following schedule unless otherwise specified by the Department:

  (4-6-05)
- **a.** Public water systems serving more than one hundred (100) people must conduct initial monitoring before January 1, 1995 except that: (10-1-93)
- i. Initial monitoring for nitrate and nitrite must be completed before January 1, 1994 for all surface water sources serving transient noncommunity public water systems and for all ground water sources serving any public water system. (10-1-93)
- ii. Initial monitoring for nitrate and nitrite must be completed before April 1, 1993 for all surface water sources serving community or nontransient noncommunity public water systems. (10-1-93)

- iii. Initial monitoring required under 40 CFR 141.23(c) must be completed before January 1, 1994 for all surface water sources serving community or nontransient noncommunity public water systems. (10-1-93)
- **b.** Public water systems serving one hundred (100) or less people must conduct initial monitoring before January 1, 1996 except that: (10-1-93)
- i. Initial monitoring for nitrate and nitrite must be completed before January 1, 1994 for all surface water sources serving transient noncommunity public water systems and for all ground water sources serving a public water system. (10-1-93)
- ii. Initial monitoring for nitrate and nitrite must be completed before April 1, 1993 for all surface water sources serving community or nontransient noncommunity public water systems. (10-1-93)
- iii. Initial monitoring required under 40 CFR 141.23(c) must be completed before January 1, 1994 for all surface water sources serving community or nontransient noncommunity public water systems. (10-1-93)
  - **O9. Alternate Analytical Techniques.** 40 CFR 141.27 is herein incorporated by reference. (10-1-93)
- 10. Approved Laboratories. All analyses conducted pursuant to this chapter, except those listed below, shall be performed in laboratories certified or granted reciprocity by the Department. The following analyses shall be conducted by the public water system in accordance with the procedures approved in Idaho Department of Health and Welfare Rules, IDAPA 16.02.13, Subsection 008.02, "Rules Governing Certification of Idaho Water Quality Laboratories."

**a.** pH; (12-10-92)

**b.** Turbidity (Nephelometric method only); (12-10-92)

c. Daily analysis for fluoride; (12-10-92)

**d.** Temperature; and (12-10-92)

- **e.** Disinfectant residuals, except ozone, which shall be analyzed using the Indigo Method or an acceptable automated method pursuant to Subsection 300.05.c. (12-10-92)
  - 11. Consecutive Water System. 40 CFR 141.29 is herein incorporated by reference. (10-1-93)
- 12. Total Trihalomethane Sampling, Analytical and Other Requirements. 40 CFR 141.30, revised as of July 1, 2001, is herein incorporated by reference.

#### (BREAK IN CONTINUITY OF SECTIONS)

### 300. FILTRATION AND DISINFECTION.

- **01. General Requirements.** 40 CFR 141.70, revised as of July 1, 2002, is herein incorporated by reference. Each public water system using a surface water source or ground water source directly influenced by surface water shall be operated by personnel, as specified in Sections 553 and 554, who have met state requirements for licensing of water system operators. (4-6-05)
- **O2.** Criteria for Avoiding Filtration. 40 CFR 141.71, revised as of July 1, 2002, is herein incorporated by reference. (5-3-03)
  - **O3. Disinfection.** 40 CFR 141.72 is herein incorporated by reference. (10-1-93)

- a. In addition to the disinfection requirements in 40 CFR 141.72, each system with a surface water source or groundwater source directly influenced by surface water shall maintain a minimum of at least two-tenths (0.2) parts per million of chlorine in the treated water after an actual contact time of at least thirty (30) minutes at maximum peak hourly demand before delivery to the first customer.

  (12-10-92)(\_\_\_\_)
- **b.** The Department may allow a system to utilize automatic shut-off of water to the distribution system whenever total disinfectant residual is less than two-tenths (0.2) mg/l rather than provide redundant disinfection components and auxiliary power as required in 40 CFR 141.72(a)(2). An automatic water shut-off may be used if the system demonstrates to the satisfaction of the Department that, at all times, a minimum of twenty (20) psi pressure and adequate fire flow can be maintained in the distribution system when water delivery is shut-off to the distribution system and, at all times, minimum Giardia lamblia and virus inactivation removal rates can be achieved prior to the first customer. (12-10-92)
- **c.** Each system which provides filtration treatment must provide disinfection treatment such that filtration plus disinfection provide at least ninety-nine and nine tenths percent (99.9%) inactivation <u>/-and/or</u> removal of Giardia lamblia cysts and ninety-nine and ninety-nine one hundredths percent (99.99%) inactivation <u>/-and/or</u> removal of viruses as specified in 40 CFR 141.72 and Section 300. However, in all cases the disinfection portion of the treatment train shall be designed to provide not less than five tenths (0.5) log Giardia inactivation, irrespective of the Giardia removal credit awarded to the filtration portion of the treatment train. (5-3-03)(\_\_\_\_\_)
- i. Each system which provides filtration treatment shall submit engineering evaluations, *and/or* other documentation, or some combination of engineering evaluations and other documentation as required by the Department to demonstrate ongoing compliance with Subsection 300.03.c. (7 1 97)( )
- ii. The Department will establish filtration removal credit on a system-by-system basis. Unless otherwise demonstrated to the satisfaction of the Department, the maximum log removal *and/or inactivation* credit allowed for filtration is as follows:

Maximum Log Removal		
Filtration Type	Giardia	Viruses
Conventional	2.5	2.0
Direct	2.0	1.0
Slow sand	2.0	2.0
Diatomaceous earth	2.0	1.0
Membrane	3.0	1.0
Alternate technology	2.0	0

<del>(5-3-03)</del>(

- iii. Filtration removal credit shall be granted for filtration treatment provided the system is; (12-10-92)
- (1) Operated in accordance with the Operations Plan specified in Subsection 552.03.a.; and (12-10-92)
- (2) The system is in compliance with the turbidity performance criteria specified under 40 CFR 141.73; and (12-10-92)
- (3) Coagulant chemicals must be added and coagulation and flocculation unit process must be used at all times during which conventional and direct filtration treatment plants are in operation; and (12-10-92)
- (4) Slow sand filters are operated at a rate not to exceed one-tenth (0.1) gallons per minute per square foot; and (12-10-92)

- (5) Diatomaceous earth filters are operated at a rate not to exceed one and one-half (1.5) gallons per minute per square foot. (12-10-92)
  - **64. Filtration.** 40 CFR 141.73, revised as of July 1, 2002, is herein incorporated by reference. (5-3-03)
- **05. Analytical and Monitoring Requirements**. 40 CFR 141.74, revised as of July 1, 1999, is herein incorporated by reference. (4-5-00)
  - **a.** Each public water system which provides filtration treatment shall monitor as follows: (12-10-92)
- i. Each day the system is in operation, the purveyor shall determine the total level of inactivation of Giardia lamblia cysts and viruses achieved through disinfection based on CT99.9 values provided in 40 CFR 141.74(b)(3) (Tables 1.1 through 1.6, 2.1 and 3.1). (12-10-92)
- ii. At least once per day, the system shall monitor the following parameters to determine the total inactivation ratio achieved through disinfection: (12-10-92)
- (1) Temperature of the disinfected water at each residual disinfectant concentration sampling point; and (12-10-92)
  - (2) If using chlorine, the pH of the disinfected water at each chlorine residual sampling point. (12-10-92)
- (3) The disinfectant contact time, "T," must be determined each day during peak hour by demand. Disinfectant contact time, "T," in pipelines used for Giardia lamblia and virus inactivation shall be calculated by dividing the internal volume of the pipe by the peak hour by flow rate through that pipe. Disinfectant contact time, "T," for all other system components used for Giardia lamblia and virus inactivation shall be determined by tracer studies or equivalent methods.

  (12-10-92)(\_\_\_\_\_)
- (4) The residual disinfectant concentrations at each residual disinfectant sampling point at or before the first customer, must be determined each day during peak hour ly flow demand, or at other times approved by the Department.

  (12 10 92)(\_\_\_\_)
- iii. The purveyor may demonstrate to the Department, based on a Department approved on-site disinfection challenge study protocol, that the system is achieving disinfection requirements specified in Subsection 300.03 utilizing CT99.9 values other than those specified in 40 CFR 141.74(b)(3) (Tables 2.1 and 3.1) for ozone, chlorine dioxide, and chloramine. (10-1-93)
  - iv. The total inactivation ratio shall be calculated as follows: (12-10-92)
- (1) If the system applies disinfectant at only one (1) point, the system shall determine the total inactivation ratio by either of the two (2) following methods: (12-10-92)
- (a) One inactivation ratio (CTcalc/CT99.9) is determined at/or before the first customer during peak hour ly flow demand; or (12-10-92)(\_\_\_\_)
- (b) Sequential inactivation ratios are calculated between the point of disinfectant application and a point at or before the first customer during peak hour ly flow demand. The following method must be used to calculate the total inactivation ratio: (12-10-92)(\_\_\_\_\_)
  - (i) Step 1: Determine (CTcalc/CT99.9) for each sequence. (12-10-92)
  - (ii) Step 2: Add the (CTcalc/CT99.9) values for all sequences. The result is the total inactivation ratio. (12-10-92)
- (2) If the system uses more than one point of disinfectant application at or before the first customer, the system must determine the CT value of each disinfection sequence immediately prior to the next point of disinfectant

application during peak hour ly flow demand. The sum of the (CTcalc/CT99.9) values from all sequences is the total inactivation ratio. (CTcalc/CT99.9) must be determined by the methods described in 40 CFR 141.74(b)(4)(i)(B).

<del>(12-10-92)</del>(

- v. Log removal credit for disinfection shall be determined by multiplying the total inactivation ratio by three (3). (12-10-92)
- vi. The Department may reduce the CT monitoring requirements specified under Section 300, for any system which demonstrates that the required inactivation levels are consistently exceeded. Reduced CT monitoring shall be allowed only where the reduction in monitoring will not endanger the health of consumers served by the water system.

  (12-10-92)
- **b.** Residual disinfectant concentrations for ozone must be measured using the Indigo Method, or automated methods may be used if approved as provided for in 40 CFR 141.74(a)(5) and Subsection 300.05. Automated methods for ozone measurement must be approved by the Department. (4-6-05)
- c. As provided for in 40 CFR 141.74(b), the Department may specify interim monitoring requirements for systems notified by the Department or U.S. Environmental Protection Agency that filtration treatment must be installed. Until filtration is installed, systems shall conduct monitoring for turbidity and disinfectant residuals as follows unless otherwise specified by the Departments; (12-10-92)
- i. Disinfectant residual concentrations entering the distribution system shall be measured at the following minimum frequencies, and samples must be taken at evenly spaced intervals throughout the workday.

Minimum Frequencies		
Population	Samples/day	
Less than 500	1	
501 - 1000	2	
1,001 - 2,500	3	
Greater than 2501	4	

(12-10-92)

- ii. Turbidity shall be measured at least once per day at the entry point to the distribution system. (12-10-92)
- iii. The Department may, at its discretion, reduce the turbidity monitoring frequency for any noncommunity system which demonstrates to the satisfaction of the Department: (12-10-92)
- (1) A free chlorine residual of two-tenths (0.2) part per million is maintained throughout the distribution system; (12-10-92)
  - (2) The water source is well protected; (12-10-92)
  - (3) The total coliform MCL is not exceeded; and (12-10-92)
  - (4) No significant health risk is present. (12-10-92)
- d. The Department may allow systems with surface water sources or groundwater sources under the direct influence of surface water, to substitute continuous turbidity monitoring for grab sample monitoring as specified in 40 CFR 141.74(b)(2) and 40 CFR 141.74(c)(1) and Subsection 300.05. The Department may allow continuous turbidity monitoring provided the continuous turbidimeter is operated, maintained, standardized and calibrated per the manufacturers recommendations. For purposes of determining compliance with turbidity

performance criteria, discrete values must be recorded every four (4) hours water is supplied to the distribution system. (10-1-93)

e. The Department may allow systems using both a surface water source(s), or groundwater source(s) under the direct influence of surface water, and one (1) or more groundwater sources, to measure disinfectant residual at points other than the total coliform sampling points, as specified in 40 CFR 141.74(b)(6)(i) and 40 CFR 141.74(c)(3)(i) and Subsection 300.05. The Department may allow alternate sampling points provided the system submits an acceptable alternate monitoring plan to the Department in advance of the monitoring requirement.

(10-1-93)

- f. The Department may allow a reduced turbidity monitoring frequency for systems using slow sand filtration or technology other than conventional, direct, or diatomaceous earth filtration, as specified in 40 CFR 141.74(c)(1) and Subsection 300.05. To be considered for a reduced turbidity monitoring frequency, a system must submit a written request to the Department in advance of the monitoring requirement. (12-10-92)
- **06. Reporting and Recordkeeping**. 40 CFR 141.75, revised as of July 1, 2001, is herein incorporated by reference. (3-15-02)
- a. As provided in 40 CFR 141.75(a), revised as of July 1, 2001, and Section 300, the Department may establish interim reporting requirements for systems notified by the Department or U.S. Environmental Protection Agency that filtration treatment must be installed as specified in 40 CFR 141.75(a), revised as of July 1, 2001, and as referred to in Subsection 300.06. Until filtration treatment is installed, systems required to install filtration treatment shall report as follows:

  (3-15-02)
- i. The purveyor shall immediately report to the Department via telephone or other equally rapid means, but no later than the end of the next business day, the following information: (12-10-92)
  - (1) The occurrence of a waterborne disease outbreak potentially attributable to that water system; (12-10-92)
  - (2) Any turbidity measurement which exceeds five (5) NTU; and (12-10-92)
- (3) Any result indicating that the disinfectant residual concentration entering the distribution system is below two-tenths (0.2) mg/l free chlorine. (12-10-92)
- ii. The purveyor shall report to the Department within ten (10) days after the end of each month the system serves water to the public the following monitoring information using a Department-approved form:

(12-10-92)

(1) Turbidity monitoring information; and

- (12-10-92)
- (2) Disinfectant residual concentrations entering the distribution system.
- (12-10-92)
- iii. Personnel qualified under Subsection 300.01 shall complete and sign the monthly report forms submitted to the Department as required in Subsection 300.06. (12-10-92)
- **b.** In addition to the reporting requirements in 40 CFR 141.75(b), revised as of July 1, 2001, pertaining to systems with filtration treatment, each public water system which provides filtration treatment must report the level of Giardia lamblia and virus inactivation/-and/or-removal achieved each day by filtration and disinfection.

  (3-15-02)(\_\_\_\_\_)
- **07. Recycle Provisions**. 40 CFR 141.76, revised as of July 1, 2002, is herein incorporated by reference. (5-3-03)
- **a.** The Department shall evaluate recycling records kept by water systems pursuant to 40 CFR 141.76 during sanitary surveys, comprehensive performance evaluations, or other inspections. (5-3-03)

**b.** The Department may require a system to modify recycling practices if it can be shown that these practices adversely affect the ability of the system to meet surface water treatment requirements. (5-3-03)

# (BREAK IN CONTINUITY OF SECTIONS)

### 450. USE OF NON-CENTRALIZED TREATMENT DEVICES.

**01. Point of Entry Devices**. 40 CFR 141.100, revised as of July 1, 1999, is herein incorporated by reference. (4-5-00)

# 02. Point of Use (POU) Treatment Devices.

(3-30-07)

- **a.** A public water system may use point of use (POU) treatment in order to achieve compliance with certain maximum contaminant levels (MCL) or treatment techniques, in accordance with Subsection 450.02.b., when the following conditions are met: (3-30-07)
- i. A program for long-term operation, maintenance, and monitoring of the POU treatment system is approved by the Department, pursuant to Section 450.02.d. (3-30-07)
- ii. The public water system or a vendor of POU treatment devices under contract with the public water system shall own, control, and maintain the POU treatment system to ensure proper operation and maintenance and compliance with the MCL or treatment technique. (3-30-07)
- iii. Each POU treatment device is equipped with a mechanical warning mechanism to ensure that customers are automatically notified of operational problems. (3-30-07)
- iv. The POU treatment device must be certified by an accredited American National Standards Institute (ANSI) certification body to meet applicable ANSI/National Sanitation Foundation (NSF) Standards.

(3-30-07)

- **b.** POU treatment devices shall not be used to achieve compliance with a MCL or treatment technique requirement for a microbial contaminant or an indicator of a microbial contaminant. Community water systems may not use POU treatment devices to achieve compliance with a nitrate MCL. (3-30-07)
- c. The Department will waive the <u>Subsection 551.04</u> plan and specification requirements as described in <u>Subsection 551.04</u> relating to material modifications for the following systems only to that the material modification proposed is limited to the installation and/or use of a POU treatment device(s):

<del>(3 30 07)</del>( )

- i. Community water systems serving two hundred (200) or fewer service connections. (3-30-07)
- ii. Non-transient non-community water systems. (3-30-07)
- iii. Transient non-community water systems. (3-30-07)
- iv. Community water systems serving more than two hundred (200) service connections if approved by the Department through the waiver process outlined in Subsection 005.01.a. (3-30-07)
- **d.** A public water system must obtain written approval by the Department before installation of a POU treatment device for the purpose of achieving compliance with a MCL or treatment technique. The public water system shall submit the following documentation for approval to the Department: (3-30-07)
- i. Information identifying the public water system name and number, total number of service connections, contaminant(s) to be treated, type of POU treatment device to be installed, manufacturer and model

number of the POU treatment device, type and function of the mechanical warning mechanism (performance indicator) on the POU treatment device, certification verification for ANSI/NSF, installer qualifications, and a proposed date for installation of the POU treatment device(s). (3-30-07)

- ii. The manufacturer's specifications for the POU treatment device including demonstration that the POU treatment device is suited for the water chemistry of the public water system and contaminant(s) of concern and is of sufficient design and capacity for the particular application. (3-30-07)
- iii. Information relating to how other drinking water dispensing units, such as instant hot water dispensers and refrigerator water and ice dispensers, whose primary function is to provide drinking water, will be provided with treated water. If water is transported from a POU treatment device to another drinking water dispensing unit, the conducting tube shall be of non-reactive material. (3-30-07)
- iv. For non-transient non-community water systems and transient non-community water systems, demonstration that the drinking water dispensing units are located in areas adequate to protect public health.

  (3-30-07)
- v. Demonstration that all POU treatment devices are owned, controlled, and maintained by the public water system or by a vendor of POU treatment devices under contract with the public water system. (3-30-07)
- vi. A sampling plan identifying the location of all service connections and demonstrating how the system will ensure that all POU treatment devices are sampled for compliance with the contaminant(s) being treated during every compliance period or at a frequency designated by the state. (3-30-07)
- vii. Documentation that a customer at each service connection has agreed to installation and use of a POU treatment device and has granted access for installation, maintenance, and sampling. (3-30-07)
- viii. A plan that describes how the public water system will address any non-compliance with Subsection 450.02.d.vii. (3-30-07)
- ix. A maintenance plan that demonstrates how on-going maintenance activities will be performed and on what frequency, including: frequency of treatment media replacements, frequency of POU treatment device replacements, periodic verification that the mechanical warning device is functional, schedule of planned maintenance activities, plan of how the system will address unscheduled maintenance problems, and a plan and method of waste disposal.

  (3-30-07)
- x. Documentation that the system meets the current requirements for a certified operator pursuant to Section 554. (3-30-07)
- xi. A plan for on-going education and outreach to the customers of the public water system, including rental customers, on POU treatment and health effects of the contaminant(s) of concern. (3-30-07)
  - xii. A plan for how the system will ensure real estate disclosures for the POU treatment system. (3-30-07)
- xiii. A statement of recognition that failure to maintain compliance with the MCL, or the failure to operate and maintain compliance with a POU treatment system as approved by the Department, may necessitate installation of centralized treatment. (3-30-07)
- **e.** Within thirty (30) days of installing the approved POU treatment system, the public water system shall notify the Department in writing that the POU treatment system was installed as approved by the Department. (3-30-07)
- **f.** Within thirty (30) days of installing the approved POU treatment system, the public water system shall submit samples from each POU treatment device to a certified laboratory for the contaminant(s) being treated by the POU treatment device. The samples shall be used to demonstrate initial compliance with the MCL. (3-30-07)

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

Docket No. 58-0108-0801 Proposed Rulemaking

g.	The water system owner or operator must maintain records for a POU treatment system. Record	ls
shall be submitte	ed to the Department at a frequency and in a format specified by the Department. Records to maintain	in
shall include:	(3-30-0'	7)

	D '	(2, 20, 07)
1	Requirements of Subsection 450.02.d.:	(3-30-07)
1.	requirements of Subsection 430.02.d.,	(3 30 01)

- ii. All sampling performed on the POU treatment devices; (3-30-07)
- iii. Maintenance logs and schedules; (3-30-07)
- iv. Log of installed units; and (3-30-07)
- v. Contracts, lease agreements, or other legal documents with vendors and consumers. (3-30-07)
- **03.** Use of Bottled Water. 40 CFR 141.101, revised as of July 1, 1999, is herein incorporated by reference. (4-5-00)

### (BREAK IN CONTINUITY OF SECTIONS)

# 500. FACILITY AND DESIGN STANDARDS: DEMONSTRATION OF TECHNICAL, FINANCIAL, AND MANAGERIAL CAPACITY OF PUBLIC DRINKING WATER SYSTEMS.

No person shall proceed, or cause to proceed, with construction of a new community or nontransient, noncommunity drinking water system until it has been demonstrated to the Department that the water system will have adequate technical, financial, and managerial capacity, as defined in Section 003 of these rules. With the exception of water sources, Pdemonstration of capacity shall be submitted to the Department prior to or concurrent with the submittal of plans and specifications, as required in Section 39-118, Idaho Code, and Subsection 504.03 of these rules. Plans and specifications for water sources may be submitted to the Department prior to demonstration of capacity for the water system. The Department shall issue its approval of the new system capacity demonstration in writing.

<del>(3-30-07)</del>(

- **01. Technical Capacity**. In order to meet this requirement, the public water system shall submit documentation to demonstrate the following: (4-5-00)
- **a.** The system meets the relevant design, construction, and operating requirements of Sections 501 through 552 of these rules; (3 30 07)(\_\_\_\_\_)
  - **b.** The system has an adequate and consistent source of water; (4-5-00)
  - **c.** A plan is in place to protect the water source and deal with emergencies; (4-5-00)
  - **d.** A plan exists for replacement or improvement of infrastructure as necessary; and (4-5-00)
- **e.** The system has trained personnel with an understanding of the technical and operational characteristics of the system. (5-3-03)
- **02. Financial Capacity**. A demonstration of financial capacity must include but is not limited to the following information: (4-5-00)
- **a.** Documentation that organizational and financial arrangements are adequate to construct and operate the public water system in accordance with these rules (see Sections 501 through 552). This information can be provided by submitting estimated construction, operation, and maintenance costs, letters of credit, or other access to financial capital through public or private sources and, if available, a certified financial statement;

<del>(3-30-07)</del>( )

- **b.** Demonstration of revenue sufficiency, that includes but is not limited to billing and collection procedures; a proposed rate structure which *is affordable and ensures* demonstrates the availability of operating funds, revenues for depreciation and reserves, and the ability to accrue a capital replacement fund. A preliminary operating budget shall be provided; and (4-5-00)(\_\_\_\_\_)
  - **c.** Adequate fiscal controls must be demonstrated.

(4-5-00)

**03. Managerial Capacity**. In order to demonstrate adequate managerial capacity, the owner *and/*or operator of a new drinking water system shall submit at least the following information to the Department:

<del>(4-5-00)</del>(

- a. Clear documentation of legal ownership and any plans that may exist for transfer of that ownership  $\frac{\partial n}{\partial t}$  upon completion of construction or after a period of operation;  $\frac{(4-5-00)(}{}$
- **b.** The name, address, and telephone number of the person who will be accountable for ensuring that the water system is in compliance with these rules; (4-5-00)
  - **c.** The name, address, and telephone number of the *system* responsible charge operator;

<del>(4-5-00)</del>( )

- **d.** A description of the manner in which the water system will be managed. <u>Information such as</u>  $B_{\text{Dy}}$  laws, restrictive covenants, articles of incorporation, or procedures and policy manuals which describe the management organizational structure <u>are a means of</u> shall be provid<del>inged this information; (4-5-00)</del>()
- **e.** A <u>description</u> recommendation of staffing <u>should be provided</u> <u>qualifications</u>, including training, experience, certification or licensing, and continuing education-<u>completed by the water system staff</u>; (4.5.00)(
- f. An explanation of how the water system will establish and maintain effective communications and relationships between the water system management, its customers, professional service providers, and any applicable regulatory agencies; and (4-5-00)
- **g.** Evidence of planning for future growth, equipment repair and maintenance, and long term replacement of system components. (4-5-00)
- **05. Expanding Systems.** A public water system which comes into existence as a result of growth in population or number of service connections within a previously unregulated system will be considered a new system under these rules and is subject to all design, construction and operating requirements herein. (4-5-00)
- **06. Consolidation.** In demonstrating new system capacity, the owner of the proposed new system must investigate the feasibility of obtaining water service from an established public water system. If such service is available, but the owner elects to proceed with an independent system, the owner must explain why this choice is in the public interest in terms of environmental protection, affordability to water users, and protection of public health.

  (4-5-00)
- **O7. Exclusion**. New public water systems which are public utilities as defined in Sections 61-104 (Corporation), 61-124 (Water System), 61-125 (Water Corporation), and 61-129 (Public Utility), Idaho Code, must meet the regulatory requirements of the Idaho Public Utilities Commission (IPUC) in Chapter 1, Title 61, Idaho Code, Public Utilities Law, and IDAPA 31.01.01, "Rules of Procedure of the Idaho Public Utilities Commission." Such water systems will not be required to meet any requirements of this Section which are in conflict with the provisions and requirements of the IPUC. (4-5-00)

# 501. FACILITY AND DESIGN STANDARDS: GENERAL DESIGN REQUIREMENTS FOR PUBLIC DRINKING WATER SYSTEMS.

Unless otherwise specified by the Department, the design of new drinking water systems, or modifications to existing, public drinking water systems, shall be in conformance with the facility and design standards set forth in Sections 006 and 500 through 552 of these rules. The following general design requirements shall apply as applicable for the type of water system and the treatment or other processes employed. (3-30-07)

- **O1.** Materials Used in Construction. Unless otherwise authorized by the Department on a site-specific basis, materials Products that are used to construct public drinking water systems and have water contact surfaces shall conform to applicable AWWA standards and/or be certified by an accredited ANSI certification body to meet applicable ANSI/NSF Sstandards 53 and 61, referenced in Subsection 002.02, where products meeting such AWWA and ANSI/NSF standards exist. In the absence of such products, products meeting applicable product standards and acceptable to the reviewing authority may be selected. Corrosion control shall be taken into account during all aspects of public water system design.
- **O2.** Additives Used in Operation. No chemical or other substance shall be added to drinking water, nor shall any process be utilized to treat drinking water, unless specifically approved by the Department. All chemicals shall conform to applicable AWWA standards and be certified by an accredited ANSI certification body to meet ANSI/NSF Standard 60, referenced in Subsection 002.02. (3-30-07)
- **O3. Design Basis.** The system, including the water source and treatment facilities, shall be designed to provide either peak hour demand of the system or *peak daily pumping* maximum day demand plus equalization storage at the design year.

  (3.30-07)(\_\_\_\_\_)

04.	Design of Treatment Facilities D	esign of treatment facilities shall address:	(3-30-07)
V4.	Design of Treatment Facilities. D	esign of treatment facilities shall address:	(3-30-07)

- **a.** Functional aspects of facility layout and provisions for future facility expansion; (3-30-07)
- **b.** Provision for expansion of waste treatment and disposal facilities; (3-30-07)
- **c.** Roads constructed to provide year-round access by vehicles and equipment needed for repair and maintenance; (3-30-07)
  - **d.** Site grading and drainage; and (3-30-07)
  - e. Chemical delivery. (3-30-07)
- **05. Design of Buildings**. The design of buildings that are a part of public drinking water systems shall provide for: (3-30-07)
  - **a.** Adequate ventilation, lighting, heating, and air conditioning; (3-30-07)
  - **b.** Adequate drainage; (3-30-07)
  - **c.** Dehumidification equipment, if necessary; (3-30-07)
  - **d.** Accessibility of equipment for operation, servicing, and removal; (3-30-07)
  - e. Flexibility and convenience of operation and safety of operators; and (3-30-07)
- f. Separate room(s) for chemical storage and feed equipment to reduce that may be required based on type of chemicals and associated hazards and dust problems.

- **Reliability and Emergency Operation**. New community water systems constructed after April 15, 2007 are required to have sufficient dedicated on-site standby power, with automatic switch-over capability, and/or standby storage so that water may be treated and supplied to pressurize the entire distribution system during power outages. During a power outage, the water system shall be able to meet the operating pressure requirements of Subsection 552.01.b. for a minimum of eight (8) hours at average day demand plus fire flow where provided. A minimum of eight (8) hours of fuel storage shall be located on site unless an equivalent plan is authorized by the Department. Standby power provided in a public drinking water system shall be coordinated with the standby power that is provided in the wastewater collection and treatment system.
- **a.** The Department may require the installation of standby power or storage facilities in existing systems if the frequency and duration of power outages a system experiences constitute a health hazard. (3-30-07)
- **b.** Existing community public water systems that are substantially modified after April 15, 2007 shall meet the requirements of Subsection 501.07. in those portions of the system affected by the modifications. (3-30-07)
- i. For the purposes of Subsection 501.07., the Department shall consider a system to be substantially modified when there is a combined increase of twenty-five percent (25%) or more above the system's existing configuration in the following factors:

  (3-30-07)
  - (1) Population served or number of service connections. (3-30-07)
  - (2) Total length of transmission and distribution water mains. (3 30 07)
  - (3) Peak or average water demand per connection. (3-30-07)
- **#<u>c</u>.** New sources and booster pumps intended to increase system capacity shall be provided with standby power or equivalent. (3-30-07)
- **ed.** For both new and existing public water systems, the Department may reduce the requirements of Subsection 501.07 if the system can demonstrate the capacity to adequately protect public health during a power outage. Any decision by the Department will be based on, but not limited to, the following considerations: (3-30-07)
  - i. An adequate emergency response and operation plan and the capacity to implement that plan. (3-30-07)
- ii. The adequacy of the system's cross connection control program and the capacity to protect public health in the event of a system wide depressurization. (3-30-07)
- iii. Demonstration of historical and projected reliability of the electrical power supplied to the water system. (3-30-07)
- iv. A strategy for providing information to the public during power outages, including instructions to stop irrigation, boil water, etc., until notified otherwise. (3-30-07)
- v. The level of reliability acceptable to consumers. This can be accomplished with either a vote of the majority of consumers for privately owned and operated systems or a decision by the governing body for publicly governed systems. (3-30-07)
- vi. Other considerations that may be pertinent, including connections to other public water systems, agreements to provide water in emergency situations, and the availability of dedicated portable auxiliary power.

  (3-30-07)
- **08. On-Site Analysis and Testing Capabilities**. Each public water system shall have equipment and facilities for routine testing necessary to ensure proper operation. Equipment selection shall be based on the characteristics of the raw water source and the complexity of the treatment process involved. (3-30-07)

- **O9. Sample Taps.** Sample taps shall be provided so that water samples can be obtained from each water source and from appropriate locations in each unit operation of treatment, and from the finished water. Taps shall be consistent with sampling needs and shall not be of the petcock type. Taps owned by the water system and used for obtaining samples for bacteriological analysis shall be of the smooth-nosed type without interior or exterior threads, shall not be of the mixing type, and shall not have a screen, aerator, or other such appurtenance. (3-30-07)
- 10. Facility Potable Water Supply. The facility water supply service line and the plant finished water sample tap shall be supplied from a source of finished water at a point where all chemicals have been thoroughly mixed, and the required disinfectant contact time, if applicable, has been achieved. There shall be no cross connections between the facility water supply service line and any piping, troughs, tanks, or other treatment units containing wastewater, treatment chemicals, raw or partially treated water. (3-30-07)
- **11. Meters**. All water supplies shall have an acceptable means of measuring the flow from each source, the wash water, the recycled water, any blended water of different quality, and the finished water. (3-30-07)
- 12. Operation and Maintenance Manual. An operation and maintenance manual or manuals shall be provided for all public water systems. The manual shall include, but is not limited to, the following contents: daily operating instructions, operator safety procedures, location of valves and other key system features, parts list and parts order form, and information for contacting the water system operator. An operational trouble-shooting section shall be supplied to the water works as part of any proprietary unit installed in system facilities. (3-30-07)
- **13. Start-Up Training**. Provisions shall be made for operator instruction at the start-up of a new plant or pumping station. (3-30-07)
- 14. Safety. Consideration shall be given to the protection of maintenance personnel and visitors from typical and foreseeable hazards in accordance with the engineering standards of care. The design shall comply with all applicable safety codes and regulations that may include the Uniform Building Code, Uniform Fire Code, National Fire Protection Association Standards, and state and federal OSHA standards. Items to be considered include, but are not limited to, noise arresters, noise protection, confined space entry, protective equipment and clothing, gas masks, safety showers and eye washes, handrails and guards, warning signs, smoke detectors, toxic gas detectors and fire extinguishers.

  (3-30-07)
- **15. Security.** Appropriate design measures to help ensure the security of water system facilities shall be incorporated. Such measures, at a minimum, shall include means to lock all exterior doorways, windows, gates and other entrances to source, treatment, pumping stations, and water storage facilities. (3-30-07)
- **16. Other Regulations**. Consideration must be given to the design requirements of other federal, state, and local regulatory agencies for items such as safety requirements, special designs for the handicapped, plumbing and electrical codes, and construction in the flood plain. (3-30-07)
- 17. Ground Water Source Redundancy. New community water systems served by ground water shall have a minimum of two (2) sources if they are intended to serve more than twenty-five (25) connections or equivalent dwelling units (EDUs). Under normal operating conditions, with any source out of service, the remaining source(s) shall be capable of providing either the peak hour demand of the system or a minimum of the maximum day demand plus equalization storage. See Subsection 501.18 for general design and redundancy requirements concerning fire flow capacity.

# 178. Redundant Fire Flow Capacity.

(3-30-07)

**a.** Public water systems that provide fire flow shall be designed to provide maximum day demand plus fire flow instead of peak hour demand plus fire flow. This allowance is made because distribution pressures can be expected to fall during a fire event and overall demand would be less than peak hour. Pumping systems supporting fire flow capacity must be designed so that fire flow may be provided with the largest any pump out of service.

<del>(3-30-07)</del>(

**b.** The requirement for redundant pumping capacity specified in Subsection 501.178.a. may be reduced to the extent that <u>fire suppression</u> storage is provided in sufficient quantity to meet some or all of fire flow

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

Docket No. 58-0108-0801 Proposed Rulemaking

demands. Where <u>fire suppression</u> storage is not provided, the requirement for fire flow pumping redundancy may be reduced or eliminated if the following conditions are met: (3 30 07)(\_\_\_\_)

- i. The local fire authority states in writing that the fire flow capacity of the system is acceptable and is compatible with the water demand of existing and planned fire fighting equipment and fire fighting practices in the area served by the system. (3-30-07)
- ii. In a manner appropriate to the system type and situation, positive notification is provided to customers that describes the design of the system's fire fighting capability and explains how it differs from the requirements of Subsection 501.178.a. The notice shall indicate that the local fire authority has provided written acceptance of the system's fire flow capacity.

  (3 30 07)(\_\_\_\_)

#### 502. FACILITY AND DESIGN STANDARDS: FACILITY PLANS.

See the definition of Facility Plan in Section 003.

(3-30-07)

- <u>a.</u> <u>Department-reviewed simple water main extension projects. A facility plan is not required if the Department is provided documentation supporting the ability of the purveyor to provide service for the simple water main extension without adding system components designed to control quantity or pressure to the system and while continuing to provide the pressure and quantity requirements of Subsection 552.01. Documentation may be in the form of:</u>

<u>i.</u>	Hydraulic modeling;	( )
	•	

- <u>ii.</u> <u>Usage data and flow calculations;</u>
- iii. Declining balance reports that demonstrate the system has the capacity to supply the service area of the system served by the extension; or (\_\_\_\_\_)
  - <u>iv.</u> Other documentation acceptable to the Department.
- **b.** Qualified Licensed Professional Engineer (QLPE)-reviewed Simple Water Main Extension Projects. A Department-approved facility plan is not required to be in place prior to the QLPE approving a simple water main extension pursuant to Subsection 504.03.b., provided that the service area of the system served by the extension is in compliance with the facility and design standards in Sections 500 through 552 of these rules. If the Department has not approved a facility plan for the system which includes the proposed simple water main extension, then the system purveyor or the QLPE shall provide with the transmittal letter documentation supporting the ability of the purveyor to provide service for the simple water main extension without adding system components designed to control quantity or pressure to the system and while continuing to provide the pressure and quantity requirements of Subsection 552.01. The purveyor shall provide this documentation to the QLPE as necessary. Documentation may be in the form of:

<u>i.</u>	Hydraulic modeling:	()
<u>1.</u>	Hydraune modernig;	<u> </u>

- <u>ii.</u> <u>Usage data and flow calculations;</u> (
- iii. Declining balance reports that demonstrate the system has the capacity to supply the service area of

	T OF ENVIRONMENTAL QUALITY or Public Drinking Water Systems	Docket No. 58-0108-0801 Proposed Rulemaking
the system serve	ed by the extension; or	()
<u>iv.</u>	Other documentation acceptable to the Department.	()
facility plan. In pursuant to Sul	Submittal to the Department. When required, review and approval prior to the submission of plans the case of water main extensions reviewed by a quesction 504.03.b., an updated facility plan shall be the reviewing authority already has a Department approximate the province of the provi	and specifications for a project related to the ualified Idaho licensed professional engineer submitted to the Department for review and
facility plan sha present criteria financing metho conclusion with the project. If the IDAPA 58.01.20 Administration guidance, con form_i_report_con part or in whole Required. Faci	Facility Plan Contents. The facility plan must ine t meets applicable criteria. The facility plan generall ll identify and evaluate problems related to the drinking and assumptions; examine alternative solutions with plats; set forth anticipated charges for users; review organ proposed project for client consideration; and outling the project is funded by the state revolving fund or a set of Planning Grants for Public Drinking Water Loan of Planning Grants for Public Drinking Water Factor be found at http://www.deg.idaho.go.hecklist.pdf. The guidance document is for Department as a guide to assist in the development of a facility plans submitted to the Department shall bear that is both signed and dated by the engineer.	y addresses the overall system-wide plan. The ng water system; assemble basic information; reliminary layouts and cost estimates; describe ganizational and staffing requirements; offer a see official actions and procedures to implement grant, other requirements may also apply. See Program," and IDAPA 58.01.22, "Rules for cilities." A checklist, which can be used as poy/water/permits_forms/forms/drinking_water/nt grant and loan projects, but may be used in lan for any proposed project. Engineer's Seal
The facility plar layouts and cos system deficience	Engineer's Seal Required. Facility plans submitted professional engineer's seal that is both signed and do shall include basic information, criteria and assumption testimates as applicable. The facility plan is intended being, and to lay out a plan for system upgrades and exposure public water system facility plan. The minimum tem are listed in Subsections 502.04.a.i. through 502.04.	ated by the engineer. Facility Plan Contents. ons, and alternative solutions with preliminary do to address system wide growth, to identify ansion.  (3-30-07)()  and requirements for a facility plan for a new
in the facility p	gh 502.04.a.viii. are not applicable to a particular system and state the reason why the requirement is not a to support applicable requirements of Sections 501 thr	pplicable. The facility plan must also include
<u>i.</u>	Location. A general description and location of the s	ystem. ()
ii. and the number	Population. The estimated design population of the of EDUs proposed.	system including the number of connections ()
<u>iii.</u> description of th	Sources of Water. Adequacy, quality, and availabile non-potable irrigation system.	ity of sources of water for potable use and a
<u>iv.</u>	Treatment. Identify and describe any anticipated treatment.	<u>ttment.</u>
uses, including 1	Water Quantity. Design data for domestic, irrigation beak hour, maximum day, and average day demands.	, fire fighting, commercial, or industrial water ()
<u>vi.</u>	Storage. Include the size and location of any anticipa	ated storage structures. ()
<u>vii.</u>	Operating Pressure. Pressure ranges for all flow cond	ditions prescribed by these rules. ()
viii. their relationshi	Sewage. Describe the sewage collection system and to existing or proposed water works structures which	

	IT OF ENVIRONMENTAL QUALITY for Public Drinking Water Systems	Docket No. 58-0108-0801 Proposed Rulemaking
system, or which	ch may affect the quality of the supply.	()
502.04.a.i. thre Subsections 50 engineer shall	Existing public water system facility plan. The minimum requirer water system must include Subsections 502.04.b.i. through 502.04 ough 502.04.a.viii. If specific items listed in Subsections 502.04 ough 2.04.a.i. through 502.04.a.viii. are not applicable to a particular fact state this in the facility plan and state the reason why the requirement include sufficient detail to support applicable requirements of Sections	4.b.vii. as well as Subsections 4.b.i. through 502.04.b.vii. or cility plan, then the submitting t is not applicable. The facility
the Department sophistication of	Hydraulic analysis. A computer analysis of the hydraulics of the dist; any analysis of an existing distribution system shall be proposed analysis shall be dependent on the type of system.	
<u>ii.</u>	Identify and evaluate problems related to the drinking water system	<u>.</u> ()
<u>iii.</u>	Describe financing methods.	()
<u>iv.</u>	Set forth anticipated charges for users.	()
<u>V.</u>	Review organizational and staffing requirements.	()
<u>vi.</u>	Offer a project(s) recommendation for client consideration.	()
<u>vii.</u>	Outline official actions and procedures to implement the project.	()
502.04.b., and	Public Water System Facility Plan funded by the State Revolving fund or a state grant, the facility plan must meet the requirement other requirements that may also apply. See IDAPA 58.01.20, "Rules for Administration of Planning Gram," and IDAPA 58.01.22, "Rules for Administration of Planning Gram".	nts of Subsections 502.04.a. and for Administration of Drinking
document is fo	Facility Plan Guidance. A checklist, which can be used as guingov/water/permits forms/forms/drinking water/form i report check r Department grant and loan projects, but may be used in part or in water facility plan.	dist.pdf. The guidance
See the defini modifications to review and appeared and specification of the reutine distrib. Preliminary en systems that rengineering registation, pressur	LITY AND DESIGN STANDARDS: PRELIMINARY ENGINEED tion of Preliminary Engineering Report in Section 003. For all no existing water systems, a preliminary engineering report shall be stroval, or other reviewing authority in the case of water main extension. One as required in Subsection 504.03. Preliminary engineering report aution system projects designed under a facility plan. This report gineering reports are required for all new water systems or material require plan and specification review and approval pursuant to Suborts must be completed for all major water system projects including, le control, storage, and treatment projects. Preliminary engineering reports are approved in accordance with Subsections 502.01 a. or	ew water systems or material ubmitted to the Department for s, prior to the submittal of plans is are not required for minor or shall provide the following: modifications to existing water ubsection 504.03. Preliminary but not limited to, source, pumperorts are not required for simple

O1. Submittal to Reviewing Authority. Preliminary engineering reports shall be submitted to the Department for review and must be approved by the Department prior to the submission of plans and specifications.

The Department may allow well construction plans and specifications to be submitted concurrently with a preliminary engineering report for these projects.

**Off.** Engineer's Seal Required. Preliminary engineering reports submitted to the <u>AD</u>epartment shall bear the imprint of an Idaho licensed professional engineer's seal that is both signed and dated by the engineer. <u>The Department will accept the seal of an Idaho licensed professional geologist on preliminary reports for well source, spring source, or infiltration gallery site reports, and for well construction.

(3-30-07)(\_\_\_\_)</u>

<del>02.</del>	<b>Location</b> . A general description and location of the project.	<del>(3-30-07)</del>
	Population. The estimated design population of the project. Preliminary Engineer preliminary engineering report must include sufficient detail to demonstrate the proportion	osed project
	criteria. The items included in Subsections 503.03.a. through 503.03.p., and all applicable	
	y required in Sections 500 through 552, shall be addressed in detail. As applicable, a	
	ort shall also identify and evaluate drinking water related problems, assemble basic i	
	and assumptions, examine alternative solutions with preliminary layouts and cost estimate	
	a proposed project, and outline official actions and procedures to implement the project	
	ions 503.03.a. through 503.03.p. are not applicable to a particular design, then the designe	
<u>this in the prelim</u>	ninary engineering report and state the reason why it is not applicable. Items adequately a	<u>ıddressed in</u>
the facility plan	under which the project is being designed may be addressed by reference for purp	oses of the
<u>preliminary engi</u>	neering report. (3-3)	<del>0-07)</del> ()
<u>a.</u>	Existing System. A general description of the existing system.	()
<u>b.</u>	Location. A general description and location of the project.	()
c.	Size. The estimated system size based on number of persons, number of connections, or	r number of
	impacted by the project.	( )
		<u>, , , , , , , , , , , , , , , , , , , </u>
<b>04<u>d</u>.</b> uses, including p	Water Quantity. Design data for domestic, irrigation, fire fighting, commercial and induseak hour ly, peak daily maximum day, and average day demands.	ıstrial water <del>0-07)</del> ()
<i>05</i> <u>e</u> .	Storage. Storage requirements.	(3-30-07)
<del>06</del> f. rules.	Operating Pressure. Pressure ranges for <i>normal and peak</i> <u>all</u> flow conditions <u>prescrib</u> (3-30)	ed by these 0 07)( )
	Hydraulic Analysis. A computer analysis of the hydraulics of the distribution system ent; any analysis of an existing distribution system shall be properly calibrated. The analysis shall be dependent on the type of system.	
demonstrate the	Sources of Water. Adequacy, quality and availability of sources of water. A water system separate non-potable irrigation system must provide documentation of legal water rigactual availability of water in sufficient quantity to ensure that the irrigation system will ray diminish the source of water for the potable water system.	<del>ghts and</del> to
	Sewage. Describe the sewage collection system and sewage treatment works, we relationship to existing or proposed water works structures which may affect the oper tem, or which may affect the quality of the supply.	
system, verify th	Treatment Wastes. Characterize the various wastes from the water treatment process volumes, constituents, and proposed treatment and disposal. If discharging to a sanitate the system is capable of handling the flow to the treatment works and that the treatment to accept the additional loading.	tary sewage
	Monitoring Results. Unless unobtainable, as in the case of a ground water source for a politoring results shall be included for any project that adds capacity, treatment, or has the quality of the existing system.	
	<b>Monitoring Results</b> — Community Systems. Results of analysis for total coliform ninants, organic chemicals, and radionuclide contaminants set forth in Subsections 050. 100.03, 100.04, 100.05, and 100.06, unless analysis is waived pursuant to Subsection 100. (3.3)	.01, 050.02

- 12ii. Monitoring Results Nontransient noncommunity systems. Results of analysis for total coliform and inorganic and organic chemical contaminants listed in Subsections 050.01, 050.02, 100.01, 100.03, 100.04, unless analysis is waived pursuant to Subsection 100.07.
- 13ii. Monitoring Results Transient noncommunity systems. Results of a total coliform, nitrite, and nitrate analysis listed in Subsections 050.01, 100.01 and 100.03.
- **44**<u>iv.</u> Turbidity. For any system supplied by surface water or groundwater under the direct influence of surface water, results of turbidity analysis listed in Subsection 100.02. (3-30-07)
- 15. Evaluation of Surface Water Influence. For all new ground water sources, including but not limited to wells, springs, and infiltration galleries, systems shall supply information as required by the Department to determine if these sources are under the direct influence of surface water. This requirement shall also apply to any existing ground water source that is found to be at risk of surface water influence during a field survey conducted by the Department.
- **161.** Potential contamination. Identify sources of contamination near proposed sources of water and describe how the sources will be protected. (3-30-07)
  - **17**<u>m</u>. Flooding. Mechanisms for protection of the system from flooding.
- **18n.** Additional information Surface water. In addition to the items listed in Subsections 503.0+3.a. through 503.4703.m., the following information must be provided for proposed surface water sources and ground water sources under the direct influence of surface water: (3-30-07)
  - **a**i. Hydrological and historical stream flow data. (3-30-07)
- **b**<u>ii</u>. A copy of the <u>water right(s)</u> appropriate permit(s) or application(s) from the Idaho Department of Water Resources <u>regarding authorization to appropriate public waters of the state of Idaho in sufficient quantity to meet the design requirements of the system.

  (3-30-07)(</u>
  - eiii. Anticipated turbidity ranges, high and low. (3-30-07)
  - $\underline{\mathbf{div}}$ . Treatment selection process and alternative evaluations. (3-30-07)
  - **e**<u>v</u>. Assessment of the degree of control the water system will be able to exercise over the watershed. (3-30-07)
  - $f_{\underline{vi}}$ . Projected future uses of impoundments or reservoirs within the watershed. (3-30-07)
- **g**<u>vii</u>. Assess degree of hazard to the supply by agricultural, industrial, recreational, and residential activities in the watershed, and by accidental spillage of materials that may be toxic, harmful or detrimental to treatment processes. (3-30-07)
- **A** Assess all waste discharges and activities that could impact the water supply. The location of each waste discharge shall be shown on a scale map. (3-30-07)
- <u>Fix.</u> Obtain source water samples over a sufficient period of time to assess the microbiological, physical, chemical and radiological characteristics of the water. (3-30-07)
  - $j\underline{x}$ . Consideration of currents, wind and ice conditions, and the effect of confluent streams. (3-30-07)
  - 490. Additional Information Ground Water. (3 30 07)
- **a.** In addition to the items listed in Subsections 503.043.a. through 503.4703.m., the following information must be provided for a proposed ground water source: (3 30 07)( )

Docket No. 58-0108-0801 Proposed Rulemaking

- i. A site evaluation report as required in Section 510 for wells and Section 514 for springs. (3-30-07)
- ii. Dimensions of the well lot and location of source. Include geographical coordinates of the source location. (3-30-07)
  - iii. Underground geological data and existing well logs. (3-30-07)
- **b**<u>iv</u>. If the water is to be treated, summarize the adequacy of proposed processes and unit parameters for the treatment of the specific water. Bench scale testing, pilot studies, or demonstrations of treatment adequacy may be required.

  (3-30-07)
- **e**<u>v</u>. A copy of the *water right(s)* appropriate permit(s) or application(s) from the Idaho Department of Water Resources regarding authorization to appropriate public waters of the state of Idaho in sufficient quantity to meet the design requirements of the system. (3-30-07)
- <u>vi.</u> Evaluation of surface water influence. For all new ground water sources, including but not limited to wells, springs, and infiltration galleries, systems shall supply information as required by the Department to determine if these sources are under the direct influence of surface water. This requirement shall also apply to any existing ground water source that is found to be at risk of surface water influence during a field survey conducted by the Department.
- **20p.** Soils and ground water levels. Generally discuss soil, ground water conditions, and potential building foundation problems, including a description of: (3-30-07)
  - **e**i. The character of the soil through which water mains are to be laid. (3-30-07)
- **b**<u>ii.</u> Characteristics of the soil, water table, and geological substrate that may affect the design and construction of the foundations of proposed structures. (3-30-07)
  - eiii. The approximate elevation of ground water in relation to subsurface structures. (3-30-07)

### 504. FACILITY AND DESIGN STANDARDS: REVIEW OF PLANS AND SPECIFICATIONS.

The facility and design standards set forth in these rules shall be applied in the review of plans and specifications for public water system facilities. If design issues are not addressed by the facility and design standards set out in these rules, then guidance documents, some of which are listed in Subsection 002.02., shall be used as guidance in the design and review of plans and specifications for public drinking water facilities. See also Section 013. (3-30-07)

- ownership. Documentation of the ownership and responsibility for operating the proposed system shall be made available to the Department prior to or concurrent with the submittal of plans and specifications as required in Subsection 504.03. The documentation must show organization and financial arrangements adequate to assure construction, operation and maintenance of the system according to these rules. Documentation shall also include the name of the water system, the name, address, and phone number of the supplier of water, the system size, and the name, address, and phone number of the system operator. (3-30-07)
- **O2.** Connection to an Existing System. If the proposed project is to be connected to an existing public water system, a letter from the purveyor must be submitted to the Department stating that the purveyor will be able to provide services to the proposed project. The Department may require documentation supporting the ability of the purveyor to provide service to the new system without diminishing quality of service to existing customers. This letter must be submitted prior to or concurrent with the submittal of plans and specifications as required in Subsection 504.03.

### 03. Plans and Specifications Required.

(3-30-07)

**a.** Prior to construction of new public drinking water systems, new drinking water systems designed to serve ten (10) or more service connections, or material modifications of existing public water systems, plans and specifications must be submitted to the Department for review and approval. If construction does not commence within twelve (12) months of the Department's final approval, the Department may require re-submittal of all or part

Docket No. 58-0108-0801 Proposed Rulemaking

of the plans and specifications. (3-30-07)Plans and specifications for simple water main extensions shall not require pre-construction approval by the Department when such extensions will be owned and operated by a city, county, quasi-municipal corporation or regulated public utilitity, provided that such plans and specifications are reviewed and approved by a qualified Idaho licensed professional engineer QLPE who was not involved in the preparation of the plans and specifications being reviewed to verify compliance with the requirements of these rules prior to initiation of construction. Any plans and specifications approved pursuant to Subsection 504.03.b. shall be transmitted to the Department at the time construction is authorized along with a statement that the plans comply with the requirements of these rules and that construction has been authorized by the city, county, quasi-municipal corporation or regulated public utility that will own and operate the system and shall be marked or stamped as "Approved for Construction." Along with the plans and specifications, the transmittal must include the items listed in Subsections 504.03.b.i. through 504.03.b.vii. The plans and specifications must be sealed, signed, and dated by the professional engineer in responsible charge of their preparation, and the approval or transmittal letter must be sealed, signed, and dated by the <del>(3-30-07)</del>( QLPE that is approving the plans and specifications. A statement that the author of the transmittal letter is the QLPE representing the city, county, quasimunicipal corporation or regulated public entity. A statement that the extension project complies with the current facility plan or preliminary engineering report, or a statement that the water system has adequate capacity. Please see Subsection 502.01.a. for further information. A statement from the city, county, quasi-municipal corporation or regulated public entity or its authorized agent that the water system purveyor will serve the project. A statement from the city, county, quasi-municipal corporation or regulated public entity or its <u>iv.</u> authorized agent that the water system purveyor will own and operate the project after construction is complete. A statement by the QLPE that the plans and specifications are approved for construction. <u>v.</u> A statement by the QLPE that the plans and specifications comply with the facility standards within vi. these rules. A statement recommending whether sanitary restrictions can be released or should remain in force. vii. Subsections 504.03.c.i. through 504.03.c.vi. outline the projects which QLPEs may approve and which QLPEs may not approve.

<u>iii.</u> A QLPE may not approve plans and specifications which include mechanical systems such as booster stations.

water system, but are unable to connect to the system at the time the extension is approved for construction by the

connect to an existing water system owned by a city, county, quasi-municipal corporation, or regulated public utility

at the time the extension is approved for construction by the QLPE.

OLPE, provided sanitary restrictions remain in force for the proposed extension.

A QLPE may approve plans and specifications for simple water main extensions that are able to

A QLPE may approve plans for simple water main extensions which will connect to an existing

<u>iv.</u> <u>A QLPE may not approve plans and specifications for projects which the QLPE was the design engineer or otherwise involved in the design. (\_\_\_\_\_\_)</u>

v. A QLPE employed by a city, county, quasi-municipal corporation, or regulated public utility may approve a design that was prepared by a subordinate engineer or an engineer from a separate design group within the

Docket No. 58-0108-0801 Proposed Rulemaking

idano Ruies i	or Public Drinking water Systems	Proposea Ruiemaking
city, county, qua	si-municipal corporation, or regulated public utility.	(
vi. utility, but is reta and specification	A QLPE who is not employed by a city, county, quasi-municipal corpained by a city, county, quasi-municipal corporation, or regulated public un review may not approve projects designed by the company with which	tility for the purpose of plan
ed. plans addressed of construction.	At the discretion of the city, county, quasi-municipal corporation or by Subsection 504.03.b. may be referred to the Department for review and	
de. shall be submitt system.	New or updated operation and maintenance manual or manuals, as req ed to the Department for review and approval prior to start-up of the ne	
and engineering	<b>Criteria for Review.</b> The Department shall review plans and so these rules and engineering standards of care. If the plans and specificati standards of care, the Department shall not substitute its judgment for ning the manner of compliance with the rule.	ions comply with these rules
Department and thereafter, the a demand, the Dej explaining any	Schedule for Review. The Department shall review plans and species within forty-two (42) calendar days of submittal such that appraisant have not resolved design issues within forty-two (42) calendar may file a written demand to the Department for a decision. Upartment shall deliver a written decision to the applicant within no more treasons for disapproval. The Department shall maintain records of all w to Subsection 504.05 with such records including the final decision records.	oval can be granted. If the endar days or at any time pon receipt of such written than seven (7) calendar days written demands for decision
	<b>Engineer's Seal Required</b> . Plans and specifications submitted to the aho licensed professional engineer's seal; except that the Department will ional geologist on the following:	
<b>a.</b> 510 and 514.	Well source, spring source, or infiltration gallery site evaluation reports	, as specified in Subsections (3-30-07)
<b>b.</b> specified in Second	Plans and specifications for well construction and results of field tion 510.	inspection and testing, as (3-30-07)
<b>07.</b> following:	Contents of Plans and Specifications. Plans and specifications shall,	where pertinent, provide the (3-30-07)
a.	General layout, including:	(3-30-07)
i.	Suitable title.	(3-30-07)
ii.	Name of municipality or other entity or person responsible for the water	er supply. (3-30-07)
iii.	Area or institution to be served.	(3-30-07)
iv.	Scale of drawings.	(3-30-07)
v.	North arrow.	(3-30-07)
vi	Datum used	(3-30-07)

vii.

General boundaries of municipality or area to be served.

- viii. Date, name, and address of the designing engineer. (3-30-07)
- ix. Legible prints suitable for reproduction. (3-30-07)
- x. Location and size of existing water mains, if applicable. (3-30-07)
- xi. For systems undergoing material modification, location and nature of existing water works structures and appurtenances affecting the proposed improvements. (3-30-07)
  - **b.** Detailed plans, including: (3-30-07)
- i. Stream crossings, providing profiles with elevations of the stream bed and the estimated normal and extreme high and, where appropriate, low water levels. (3-30-07)
- ii. Location and size of the property to be used for the development with respect to known references such as roads, streams, section lines, or streets. (3-30-07)
  - iii. Topography and arrangement of present or planned wells or structures. (3-30-07)
- iv. Elevations of the one hundred (100) year flood level in relation to the floor of structures, upper termination of protective casings, and grade surrounding facilities. (3-30-07)
- v. Details of well construction, including diameter and depth of drill holes, casing and liner diameters and depths, grouting depths, elevations, and designation of geological formations, water levels and other data as specified in Section 510. (3-30-07)
- vi. Location of all known existing and potential sources of pollution within five hundred (500) feet of water sources or underground treated storage facilities. (3-30-07)
  - vii. Size, length, and materials of proposed water mains. (3-30-07)
- viii. Location of existing or proposed streets; water sources, ponds, lakes, and drains; storm sanitary, combined and house sewers; septic tanks, disposal fields and cesspools. (3-30-07)
  - ix. Schematic flow diagrams and hydraulic profiles showing the flow through various plant units. (3-30-07)
  - x. Piping in sufficient detail to show flow through the plant including waste lines. (3-30-07)
- xi. Locations of all chemical storage areas, chemical feeding equipment, and points of chemical application. (3-30-07)
- xii. All appurtenances, specific structures, equipment, water treatment plant waste disposal units and points of discharge having any relationship to the plans for water mains or water works structures. (3-30-07)
- xiii. Locations of sanitary or other facilities, such as lavatories, showers, toilets, and lockers, when applicable or required by the Department. (3-30-07)
  - xiv. Locations, dimensions, and elevations of all proposed plant facilities. (3-30-07)
  - xv. Locations of all sampling taps owned by the water system. (3-30-07)
- xvi. Adequate description of any significant features not otherwise covered by the specifications that may impact public safety or welfare. (3-30-07)
  - **c.** Complete, detailed technical specifications shall be supplied for the proposed project, including:

- i. A program for keeping existing water works facilities in operation during construction of additional facilities so as to minimize interruption of service. (3-30-07)
  - ii. Laboratory facilities and equipment. (3-30-07)
  - iii. Description of chemical feeding equipment. (3-30-07)
- iv. Procedures for flushing, disinfection and testing, as needed, prior to placing the project in service. All wells, pipes, tanks, and equipment which can convey or store potable water shall be disinfected in accordance with AWWA Standards, incorporated into these rules at Subsection 002.01. Plans or specifications shall outline the procedure and include the disinfectant dosage, contact time, and method of testing the results of this procedure.

  (3-30-07)
- v. Materials or proprietary equipment for sanitary or other facilities, including any necessary backflow or back-siphonage protection. (3-30-07)
  - **d.** Complete design criteria, as set forth in these rules. (3-30-07)
- **e.** The Department may require additional information which is not part of the construction drawings, including, but not limited to, head loss calculations, proprietary technical data, and copies of contracts. (3-30-07)
- **08. Notification of Material Deviations**. As set forth in Subsection 504.03, during construction or modification, the reviewing authority must be notified of any material deviation from the approved plans. The reviewing authority's prior written approval is required before any material deviation is allowed. (3-30-07)

### 09. Record Plans and Specifications Required.

- **a.** Within thirty (30) calendar days of the completion of construction of facilities for which plans are required to be reviewed pursuant to Subsection 504.03, record plans and specifications based on information provided by the construction contractor and field observations made by the engineer or the engineer's designee depicting the actual construction of facilities performed, must be submitted to the Department by the engineer representing the city, county, quasi-municipal corporation or regulated public utility that owns the project, or by the design engineer or owner-designated substitute engineer if the facilities will not be owned and operated by a city, county, quasi-municipal corporation or regulated public utility. Such submittal by the professional engineer must confirm material compliance with the approved plans and specifications or disclose any material deviations therefrom. If the construction does not materially deviate from the approved plans and specifications, the owner may have a statement to that effect prepared by an Idaho licensed professional engineer and filed with the Department in lieu of submitting a complete and accurate set of record drawings. (3-30-07)
- **b.** Record plans and specifications, or a statement submitted in lieu of record plans and specifications, must be sealed, signed, and dated by the professional engineer in responsible charge of their preparation.
- <u>c.</u> The Department will accept the seal of an Idaho licensed professional geologist on record plans and specifications, or a statement bearing the seal of an Idaho licensed professional geologist in lieu of record plans and specifications, for record plans and specifications for well construction and results of field inspection and testing, as specified in Section 510.
- **10. Exception**. The Department may waive the plan and specification approval required of any particular facility or category of facilities when doing so will have no significant impact on public health or the environment. (3-30-07)
- 11. Requirement to Have Approved Plans and Specifications and Approval Letter On-Site During Construction. It is the responsibility of the owner to maintain one (1) copy of the approved plans and specifications and the approval letter from the reviewing authority on-site during construction at all times. (3-30-07)

12. Construction. Except as provided in Subsection 504.03.b., no construction shall commence until all of the necessary approvals have been received from the Department. The owner shall provide for the inspection of the construction of a public drinking water system facility by an Idaho licensed professional engineer to the extent required to confirm material compliance with the approved plans and to produce accurate record documents as required by Subsection 504.09. (3-30-07)

### 505. -- 509. (RESERVED).

### 510. FACILITY AND DESIGN STANDARDS: SITING AND CONSTRUCTION OF WELLS.

Written approval by the Department is required before water from any new or reconstructed well may be served to the public. Any supplier of water for a public water system served by one (1) or more wells shall ensure that the following requirements are met: (3-30-07)

- **01. Site Approval.** Prior to drilling, the site of a public water system well must be approved in writing by the Department. The Department shall require the supplier of water to submit a well site evaluation report that takes into account the proposed size, depth, and location of the well. The evaluation may include, but is not limited to the following types of information: (3-30-07)
  - **a.** An evaluation of the potability and quality of anticipated groundwater. (5-3-03)
- **b.** Identification of the known aquifers and the extent of each aquifer, based on the stratigraphy, sedimentation, and geologic structure beneath the proposed well site. (5-3-03)
  - **c.** An estimate of hydrologic and geologic properties of each aquifer and confining layers. (5-3-03)
- **d.** Prediction of the sources of water to be extracted by the well and the drawdown of existing wells, springs, and surface water bodies that may be caused by pumping the proposed well. This prediction may be based on analytical or numerical models as determined by the Idaho Department of Water Resources permitting process.
  - (3-30-07)
- **e.** Demonstration of the extent of the capture zone of the well, based on the well's design discharge and on aquifer geology, using estimates of hydraulic conductivity and storativity. (5-3-03)
  - **f.** Description of potential sources of contamination within five hundred (500) feet of the well site. (5-3-03)
- **O2. Location**. Each well shall be staked by the design engineer or licensed professional geologist prior to drilling, be located a minimum of fifty (50) feet from the nearest property line, be located a minimum of fifty (50) feet from any potential source of contamination, and be no closer to specified sources of contamination than set forth in Subsection 900.01. In vulnerable settings, the Department may require engineering or hydrologic analysis to determine if the required setback distance is adequate to prevent contamination.

  (3 30 07)(\_\_\_\_)
- **O3. Construction Standards.** In addition to meeting the requirements of these rules, all wells shall be constructed in accordance with IDAPA 37.03.09, "Well Construction Standards Rules," and related rules and laws administered by the Idaho Department of Water Resources. All wells shall comply with the drilling permit requirements of Section 42-235, Idaho Code. (5-3-03)
- a. Casing that meets the requirements set forth in Subsection 900.032 (Table 32). The use of plastic well casing for public water system wells may be considered on a case-by-case basis. Plastic casing shall meet or exceed ASTM Standard F480-02 and ANSI/NSF Standard 61.
- **b.** Public water system wells shall have no less than fifty-eight (58) feet of annular seal of not less than one and one-half (1½) inches thickness as measured from land surface to the bottom of the seal unless:
  - (3-30-07)
- i. It can be demonstrated to the Department's satisfaction that there is a confining layer at lesser depth that is capable of preventing unwanted water from reaching the intake zone of the well; or (5-3-03)

- ii. The best and most practical aquifer at a particular site is less than fifty-eight (58) feet deep; or; (5-3-03)
- iii. The Department specifies a different annular seal depth based on local hydrologic conditions. (5-3-03)
- iv. More stringent standards are required by applicable Rules of the Idaho Water Resources Board, referenced in Subsection 002.02. (3-30-07)
- **c.** Specifications shall include allowable tolerances for plumbness and alignment in accordance with AWWA Standards, incorporated by reference into these rules at Subsection 002.01, or as otherwise approved by the Department. If the well fails to meet these requirements, it may be accepted by the Department if it does not interfere with the installation or operation of the pump or uniform placement of grout. (3-30-07)
- **d.** Geological data shall be collected at each pronounced change in formation and shall be recorded in the driller's log. Supplemental data includes, but is not limited to, accurate geographical location such as latitude and longitude or GIS coordinates, and other information on accurate records of drillhole diameters and depths, assembled order of size and length of casing, screens and liners, grouting depths, formations penetrated, and water levels.

  (3-30-07)
- **e.** The owner of each well shall retain all records pertaining to each well until the well has been properly abandoned. (3-30-07)
  - **f.** Wells with intake screens shall: (3-30-07)
- i. Be constructed of materials resistant to damage by chemical action of ground water or cleaning operations. (3-30-07)
  - ii. Have openings based on sieve analysis of formation and/or gravel pack materials. (3-30-07)(\_\_\_\_\_)
- iii. Have sufficient length and diameter to provide adequate specific capacity and aperture entrance velocity not to exceed point three (0.3) feet per second, or as otherwise approved by the Department. (3-30-07)
- iv. Be installed so that the pumping water level remains above the screen under all operating conditions, or otherwise approved by the Department. Where a bottom plate or sump is utilized, it shall be of the same material as the screen, or as otherwise approved by the Department. Where a washdown assembly, tailpipe or sump is used below the screen, it may be made of a different material than the screen. (3-30-07)
- g. Permanent well casing shall be surrounded by a minimum of one and one-half (1 ½) inches of grout to the depth required by Subsection 510.03. $\alpha$ b. of these rules, or by the Rules of the Idaho Water Resources Board referenced in Subsection 002.02, whichever is *more stringent* greater. All casing identified in plans and specifications as temporary casing shall be removed prior to well completion.
- i. Neat cement grout consisting of cement that conforms to AWWA Standard A-100, and water, with not more than six (6) gallons of water per ninety-four (94) pounds of cement, shall be used for one and one-half (1 ½) inch openings. Additives may be used to enhance effectiveness and are subject to approval by the reviewing authority and the Idaho Department of Water Resources on a case-by-case basis. (3-30-07)
- ii. Bentonite grout shall have a solids content not less than twenty-five (25) percent by weight when mixed with water and be specifically manufactured for use in sealing of well casing. Bentonite grout shall not contain weighting agents to increase solids content. Bentonite grout shall not be used above the water table. All bentonite grout shall be installed by positive displacement from the bottom up through a tremmie or float shoe. (3-30-07)
- iii. Where a dry annular space is to be sealed, a minimum of two (2) inches on all sides of the casing shall be required to place bentonite to depths not greater than one hundred (100) feet, using #8 mesh granular bentonite. All dry pour granular bentonite shall be tagged at appropriate intervals to verify placement. If a bridge

occurs, a tremmie pipe shall be washed or jetted through the bridge to allow for pumping of grout. Bentonite chips shall be of sufficient size to accommodate proper placement for the existing subsurface conditions. (3-30-07)

- iv. Dry granular bentonite used in wells where a dry annular space is to be sealed with depths greater than one hundred (100) feet shall require an annulus of at least three (3) inches on all sides of the casing, or as approved by the reviewing authority and the Idaho Department of Water Resources. If a bridge occurs, a tremmie pipe shall be washed or jetted through the bridge to allow for pumping of grout. Bentonite chips shall be of sufficient size to accommodate proper placement for the existing subsurface conditions. (3-30-07)
- v. All chip bentonite seals installed through water shall only be used in annular spaces of at least four (4) inches on all sides of the casing. If a bridge occurs, a tremmie pipe shall be washed or jetted through the bridge to allow for pumping of grout. Bentonite chips shall be of sufficient size to accommodate proper placement for the existing subsurface conditions. Chip bentonite seals installed through water shall be: (3-30-07)
  - (1) Installed in accordance with manufacturer's specifications; or (3-30-07)
- (2) Installed by pouring chips over a one-quarter (1/4) inch mesh screen for three-eighths (3/8) inch chips to remove fines to prevent bridging at the water table; or (3-30-07)
- (3) Installed using coated pellets to retard hydration if approved by the reviewing authority and the Idaho Department of Water Resources. (3-30-07)
- vi. Concrete may be approved on a case-by-case basis by the reviewing authority and the Idaho Department of Water Resources. Upon such approval, the approved method shall use a six (6) sack minus one-half (1/2) inch Portland cement concrete and shall be installed by positive displacement from the bottom up through a tremmie pipe. (3-30-07)
- **O4. Disinfection.** All tools, bits, pipe, and other materials to be inserted in the borehole shall be cleaned and disinfected in accordance with the Well Construction Standards and permitting requirements of the Idaho Water Resources Board, referenced in Subsection 002.02 This applies to new well construction and repair of existing wells. (3-30-07)
- **05. Information Required.** Upon completion of a groundwater source, and prior to its use as drinking water, the following information and data must be submitted by the water system to the Department: (3-30-07)
  - **a.** A copy of all well logs; (12-10-92)
  - **b.** Results of test pumping, as specified in Section 510; (3-30-07)
  - **c.** As constructed plans showing at least the following: (12-10-92)
  - i. Annular seal, including depth and sealant material used and method of application; (5-3-03)
- ii. Casing perforations, results of sieve analysis used in designing screens installed in sand or gravel aquifers, gravel packs; and (5-3-03)
  - iii. Pump location; and (12-10-92)
- iv. For community water systems, a permanent means for measuring water level. All equipment required for conducting water level measurements shall be purchased and made available to the water system operator at the time well construction is completed. Where pneumatic or electronic water level measuring equipment is used, it shall be made using corrosion resistant materials attached firmly to the drop pipe or pump column and in such a manner as to prevent entrance of foreign materials. (3-30-07)
  - **d.** Other information as may be specified by the Department. (12-10-92)
  - e. Sampling results for iron, manganese, corrosivity, and other secondary contaminants specified by

Docket No. 58-0108-0801 Proposed Rulemaking

the Department. Other monitoring requirements are specified in Subsections 503 510.05.e.i. through 510.05.e.iii.

- i. Community Systems. Results of analysis for total coliform, inorganic chemical contaminants, organic chemicals, and radionuclide contaminants set forth in Subsections 050.01, 050.02, 050.05, 100.01, 100.03, 100.04, 100.05, and 100.06, unless analysis is waived pursuant to Subsection 100.07.
- ii. Nontransient Noncommunity Systems. Results of analysis for total coliform and inorganic and organic chemical contaminants listed in Subsections 050.01, 050.02, 100.01, 100.03, 100.04, unless analysis is waived pursuant to Subsection 100.07.
- iii. Transient Noncommunity Systems. Results of a total coliform, nitrite, and nitrate analysis listed in Subsections 050.01, 100.01 and 100.03.
- **06. Test Pumping**. Upon completion of a ground water source, test pumping shall be conducted in accordance with the following procedures to meet the specified requirements: (12-10-92)
- a. The well shall be test pumped at the desired yield (design capacity) of the well for at least twenty-four (24) consecutive hours after the drawdown trend has stabilized, as determined by the supervising engineer or geologist. Alternatively, the well may be pumped at a rate of one hundred fifty percent (150%) of the desired yield for at least six (6) continuous hours after the drawdown trend has stabilized, as determined by the supervising engineer or geologist. The field pumping equipment must be capable of maintaining a constant rate of discharge during the test. Discharge water must be piped an adequate distance to prevent recharge of the well during the test. If the well fails the test protocol, design of the water system shall be re-evaluated and submitted to the Department for approval.

- **b.** Upon completion of well development, the well shall be tested for sand production. Fifteen (15) minutes after the start of the test pumping (at or above the design production rate), the sand content of a new well shall not be more than five (5) parts per million. Sand production shall be measured by a centrifugal sand sampler or other means acceptable to the Department. If sand production exceeds five (5) ppm, the well shall be screened gravel packed, or re-developed. (3-30-07)
  - **c.** The following data shall be provided: (5-3-03)
  - i. Static water level in the well prior to test pumping; (5-3-03)
- ii. Well yield in gpm and duration of the pump test, including a discussion of any discrepancy between the desired yield and the yield observed during the test; (5-3-03)
  - iii. Water level in the well recorded at regular intervals during pumping; (5-3-03)
  - iv. Profile of water level recovery from the pumping level projected to the original static water level. (5-3-03)
  - v. Depth at which the test pump was positioned in the well; (5-3-03)
  - vi. Test pump capacity and head characteristics; (5-3-03)
  - vii. Sand production data. (5-3-03)
- viii. Any available results of analysis based on the drawdown and recovery test pertaining to aquifer properties, sustained yield, and boundary conditions affecting drawdown. (5-3-03)
- **d.** The Department may allow the use of other pump test protocols that are generally accepted by engineering firms with specialized experience in well construction, by the well drilling industry, or as described in national standards (such as ANSI/AWWA A100-97), as long as the minimum data specified in Subsection 510.06.c. are provided. The Department welcomes more extensive data about the well, such as step-drawdown evaluations used

in determining well capacity for test pumping purposes, zone of influence calculations, and any other information that may be of use in source protection activities or in routine water system operations. (3-30-07)

- **e.** Where aquifer yield, sustainability, or water quality are questionable, the Department, at its discretion, may require additional site specific investigations that could include test well construction, long-term pumping tests, or other means to demonstrate that the aquifer is sufficient to meet the long-term water requirements of the project. (4-11-06)
- **O7.** Conversion of *Irrigation* Non-Public Water System Wells for Public Water System Use. Any *irrigation* existing well constructed for use other than as a public water system source may be considered for use as a public water system source on a case-by-case basis. The owner of such a well must demonstrate to the Department's satisfaction that the well site conforms to the requirements of Subsections 510.01, 510.02, and Section 512, the well is constructed in a manner that is protective of public health and that both the quantity and quality of water produced by the well meet public water system standards set forth in these rules.
- **Observation Wells.** If observation wells are used and are intended to remain in service after completion of the water supply well, the observation wells shall be constructed in accordance with the requirements for permanent wells and be protected at the upper terminal to preclude entrance of foreign materials. See Rules of the Idaho Water Resources Board referenced in Subsection 002.02. (3-30-07)
- **8.9. Well Abandonment.** Any water supply well that will no longer be used must be abandoned by sealing the borehole carefully to prevent pollution of the ground water, eliminate any physical hazard, conserve aquifer yield, maintain confined head conditions in artesian wells, and prevent mixing of waters from different aquifers. The objective of proper well abandonment procedures is to restore, as far as possible, the original hydrogeologic conditions. The services of a licensed well driller are required. Instructions for abandoning various types of wells may be obtained from the Idaho Department of Water Resources. See Rules of the Idaho Water Resources Board referenced in Subsection 002.02. (3-30-07)

# 511. FACILITY AND DESIGN STANDARDS: WELL PUMPS, DISCHARGE PIPING, AND APPURTENANCES.

- **O2. Discharge Piping.** The discharge line shall be equipped with the necessary valves and appurtenances to allow a well to be pumped to waste at the design capacity of the well via an approved air gap at a location prior to the first service connection, and shall meet the following requirements: (3-30-07)
  - **a.** Be designed to minimize friction loss. (3-30-07)
- **b.** Have control valves and appurtenances located above the pump house floor when an above-ground discharge is provided. (3-30-07)
  - **c.** Be protected against contamination. (3-30-07)
- **d.** Vertical turbine pumps shall be equipped with an air release-vacuum relief valve, or equivalent, located upstream from the check valve, with exhaust/relief piping terminating in a down-turned position at least eighteen (18) inches above the floor and covered with a twenty-four (24) mesh corrosion resistant screen. (3-30-07)
  - e. Have all exposed piping, valves and appurtenances protected against physical damage and freezing. (3-30-07)

- **f.** Be properly anchored to prevent movement, and protected against surge or water hammer.
  - (3-30-07)
- **O3. Pressure Gauge Required.** A pressure gauge shall be provided at all installations. (3-30-07)
- **104. Flow Meter and Check Valve.** Unless otherwise approved by the Department, an instantaneous and totalizing flow meter equipped with nonvolatile memory shall be installed on the discharge line of each well. An accessible check valve, which is not located in the pump column, shall be installed in the discharge line of each well between the pump and the shut-off valve.

  (3-30-07)(\_\_\_\_)
- **05. Well Vent.** All wells shall be vented, unless it can be demonstrated that the drawdown under maximum pumping conditions will not exceed ten (10) feet, with the open end of the vent screened and terminated downward at least eighteen (18) inches above the final ground surface. (3-30-07)
- **Casings and Sanitary Well Caps**. The following requirements apply to well casings and sanitary caps: (3-30-07)
- a. Casings shall extend a minimum of eighteen (18) inches above the final ground surface and, if the well is located within a pump house, twelve (12) inches above the pump house floor. If local hydrological conditions require that a well be located in an area subject to flooding, the Department may require extension of the casing to extend above the one hundred (100) year or highest known flood level. (3-30-07)
- **b.** Wells shall be cased and provided with a sanitary cap in such a manner that surface water cannot enter the well. (3-30-07)
- **07. Well Houses.** For regulatory purposes, a well house is considered a pump house as defined in Section 003. Well houses must meet the requirements for pump houses as set forth in Section 541. (3-30-07)
  - **08.** Pitless Adapters and Units. Pitless adapters or pitless units: (3-30-07)
- **a.** Shall be of the type marked approved by the National Sanitation Foundation or Pitless Adapter Division of the Water Systems Council. (12-10-92)
- **b.** Shall be designed, constructed and installed to be watertight including the cap, cover, casing extension and other attachments. (12-10-92)
- **c.** Shall be field tested for leaks before being put into service. The procedure outlined in "Manual of Individual and Non-Public Water Supply Systems," referenced in Subsection 002.02, or other procedure approved by the Department shall be followed. (3-30-07)
- **d.** Pitless adapters with a two (2) inch or smaller discharge line shall be provided with a swing joint outside the pitless adapter unit to reduce strain, deformation, and possible leakage of the pitless seal caused by settling soils in the trench. The orientation of swing joints shall be such that any settling that occurs will tighten the threads. The hole in the casing shall be cut with a saw rather than a torch with an opening large enough to allow seating of gaskets. (3-30-07)
  - **e.** Shall be provided with a contamination-proof entrance connection for electrical cable. (3-30-07)
  - **f.** In the case of pitless adapters: (3-30-07)
- i. Threaded adapters shall be installed by drilling a hole not more than one quarter (1/4) inch larger than the outer diameter of the pitless shank. No torch-cut holes shall be accepted. The orientation of swing joints shall be such that any settling that occurs will tighten the threads. (3-30-07)
  - ii. The only field welding permitted will be that needed to connect a pitless adapter to the casing. (3-30-07)

**g.** In the case of pitless units:

- (3-30-07)
- i. Shall be shop-fabricated from the point of connection with the well casing to the unit cap or cover. (3-30-07)
- ii. Shall be constructed of materials and weight at least equivalent to and compatible with the well casing. (3-30-07)
- iii. Shall be threaded or welded to the well casing. Threaded units shall be installed by drilling a hole not more than one quarter (1/4) inch larger than the outer diameter of the pitless shank. No torch-cut holes shall be accepted. If the connection to the casing is by field weld, the shop-assembled unit must be designed specifically for field welding to the casing.

  (3-30-07)
- iv. Shall terminate at least eighteen (18) inches above final ground elevation or three (3) feet above the 100-year flood level or the highest known flood elevation, whichever is higher, or as otherwise approved by the Department. (3-30-07)
  - v. Shall be provided with access to disinfect the well.

- (3-30-07)
- vi. Shall have field connection to the lateral discharge from the pitless unit of threaded, flanged, or mechanical joint connection. (3-30-07)
- **09. Wells Not Allowed in Pits.** Wells shall not be located in pits. Exceptions to this requirement will be granted by the Department if the well was constructed prior to November 5, 1964, and the installation is constructed or reconstructed in accordance with the requirements of the Department to provide watertight construction of pit walls and floors, floor drains and acceptable pit covers. (3-30-07)
  - **10. Discharge Pumps.** Discharge pumps shall be subject to the following requirements: (3-30-07)
  - **a.** Line shaft pumps shall.

- (3-30-07)
- i. Have the casing firmly connected to the pump structure or have the casing inserted into a recess extending at least one-half (1/2) inch into the pump base. (3-30-07)
- ii. Have the pump foundation and base designed to prevent water from coming into contact with the joint. (3-30-07)
  - iii. Use lubricants that meet ANSI/NSF Standard 61.

(3-30-07)

**b.** When a submersible pump is used:

- (3-30-07)
- i. The top of the casing shall be effectively sealed against the entrance of water under all conditions of vibration or movement of conductors or cables. (3-30-07)
- ii. The electrical cable shall be firmly attached to the drop pipe at twenty-one (21) foot intervals or less, or at each coupling or joint. (3-30-07)

### 512. FACILITY AND DESIGN STANDARDS: WELL LOT.

A well lot shall be provided for wells constructed after November 1, 1977. The well lot shall be owned in fee simple by the supplier of water or controlled by lease or easement with a term of not less than the useful life of the well and be large enough to provide a minimum distance of fifty (50) feet between the well and the nearest property line.

- **01. Use of Chemicals on the Well Lot.** No pesticides, herbicides, or fertilizers shall be applied to a well lot without prior approval from the Department. (3-30-07)
  - **O2.** Storage of Hazardous Materials on the Well Lot. No pesticides, herbicides, fertilizers, portable

containers of petroleum products, or other materials known to be toxic or hazardous shall be stored on a well lot, except that: (3-30-07)

- **a.** An internal combustion engine to drive either a generator for emergency standby power or a pump to provide fire flows, and an associated fuel tank, may be placed on the well lot. (5-3-03)
  - **b.** A propane or natural gas powered generator is preferable to reduce risk of fuel spillage. (5-3-03)
- c. If a diesel or gasoline-fueled engine is used, the fuel tank and connecting piping must be approved by the Underwriter's Laboratory, Inc., double-walled, meet the requirements of the local fire jurisdiction, and include both spill prevention and overfill protection features. The tank must be above ground and may be contained within the structural base of the generator unit. A licensed water system operator shall be present during filling of the tank following a period of usage, or during periodic extraction and replacement of outdated fuel. (4-6-05)
- **d.** Should the internal combustion engine be located within the pump house, the floor of the pump house shall be constructed so as to contain all petroleum drips and spills so that they will not be able to reach the floor drain(s). Engine exhaust shall be directly discharged outside the pump house. (3-30-07)
- e. A spill containment structure shall surround all fuel tanks and be sized to contain at least one hundred ten percent (110%) of the fuel tank volume. The Department may require additional containment capacity in settings where accumulation of snow, ice, or rain water could be expected to diminish the usable capacity of the structure.

  (4-6-05)
- **O3. Location of Hydrants.** Hydrants of the frost free type shall be placed in the buried piping system at a minimum of five (5) feet away from the well casing to prevent drain water from accumulating and for compromising the grout seal surrounding the well casing.

  (3 30 07)( )

# 513. FACILITY AND DESIGN STANDARDS: NUMBER OF GROUND WATER SOURCES REQUIRED $\underline{-}$ EXISTING SYSTEMS.

New Existing community water systems served by ground water and constructed after July 1, 1985, or existing community water systems served by ground water that are substantially modified after July, 2002, shall have a minimum of two (2) sources if they are intended intending to serve more than twenty-five (25) homes connections or equivalent dwelling units are subject to the following requirements for the number of ground water sources required. Under normal operating conditions, with any source out of service, the remaining source or sources shall be capable of providing either the peak hour demand of the system or maximum day demand plus equalization storage. See Subsection 501.17 for general design requirements concerning fire flow capacity. For the purpose of Section 513 only, the Department shall consider a system to be "substantially modified" when there is a combined increase of twenty five percent (25%) or more above the system's existing configuration in the following factors:

<del>(3-30-07)</del>( \_\_\_\_)

- 01. Population Served or Number of Service Connections Existing System with All Sources Constructed Prior to July 1, 1985. A community water system served by ground water and with all existing sources constructed prior to July 1, 1985 will be required to comply with Subsection 501.17 upon substantially modifying the system after July 2002.
- 02. Length of Water Mains Existing System with Any Sources Constructed After July 1, 1985. A community water system served by ground water with any sources constructed after July 1, 1985 is required to comply with Subsection 501.17 when a modification is made to the system which increases the population served or number of service connections, increases the length of transmission and distribution water mains, or increases the peak or average water demand.

  (3 30 07)(\_\_\_\_\_)
  - 03. Peak or Average Water Demand Per Connection.

(3-30-07)

### 514. FACILITY AND DESIGN STANDARDS: SPRING SOURCES.

Written approval by the Department is required before water from any new or reconstructed spring source may be served to the public. For new spring sources, the Department may require a site evaluation report as set forth for wells in Section 510. Any supplier of water for a public water system served by one (1) or more springs shall ensure that the

following requirements are met:

(3-30-07)

- **01. Protection of the Spring**. Springs shall be housed in a permanent structure and protected from contamination including the entry of surface water, animals, and dust. The spring box shall be equipped with a screened overflow. The inlet shall be screened and located above the floor of the collection chamber. (3-30-07)
- **O2.** Access to Spring Box. A watertight and locking access port shall be provided. The Each spring box access port shall be elevated at least twenty-four (24) inches above the top of the box or covering sod, whichever is higher. Each access shall be fitted with a solid water tight cover which overlaps a framed opening and extends down around the frame at least two (2) inches. The frame shall be at least four (4) inches high and shall have a locking device.

  (3 30 07)(\_\_\_\_)
- - **604. Flow Measurement.** A flow meter or other flow measuring device shall be provided. (3-30-07)
- **05. Protected Area.** The entire area within a one hundred (100) foot radius of the spring box shall be owned by the supplier of water or controlled by a long term lease, fenced to prevent trespass of livestock and void of buildings, dwellings and sources of contamination. Surface water shall be diverted from this area. (3-30-07)

### (BREAK IN CONTINUITY OF SECTIONS)

# 518. FACILITY AND DESIGN STANDARDS: ADDITIONAL DESIGN CRITERIA FOR SURFACE WATER TREATMENT.

Performance criteria for surface water treatment facilities are specified in National Primary Drinking Water Regulations, as set forth in Sections 300, 301, and 310 of these rules. Surface water treatment systems must comply with applicable general design requirements in Section 503. In addition, the following design requirements apply specifically to surface water treatment facilities:

(3-30-07)

- **01. Engineering Design Requirements**. The system shall ensure that filtration and disinfection facilities for surface water or groundwater directly influenced by surface water sources are designed, constructed and operated in accordance with all applicable engineering practices designated by the Department. The design of the water treatment plant must consider the worst raw water quality conditions that are likely to occur during the life of the facility. (3-30-07)
- **Removal of Pathogens.** Filtration facilities (excluding disinfection) shall be designed, constructed and operated to achieve at least two (2) log removal of Giardia lamblia cysts, two (2) log removal of Cryptosporidium oocysts, and one (1) log removal of viruses, except as allowed under Subsection 518.09.b. (3-30-07)
- **O3. Disinfection**. Disinfection facilities shall be designed, constructed and operated so as to achieve at least point five zero (0.50) log inactivation of Giardia lamblia cysts; and (3-30-07)
  - **a.** Two (2) log inactivation of viruses if using conventional and slow sand filtration technology; or (12-10-92)
  - **b.** Three (3) log inactivation of viruses if using direct and diatomaceous earth filtration technology; or (12-10-92)
  - **c.** Four (4) log inactivation of viruses if using alternate filtration technology. (12-10-92)

**d.** Four (4) log inactivation of viruses if filtration treatment is not used. (10-1-93)

**04. Enhanced Disinfection**. Higher levels of disinfection than specified under Subsection 5168.03 may be required by the Department in order to provide adequate protection against giardia and viruses.

<del>(3-30-07)</del>( )

- **05. Filter to Waste**. For plants constructed after December 31, 1992, each filter unit must be capable of filter to waste. For plants constructed prior to December 31, 1992, each filter unit must be capable of filter to waste unless the system demonstrates through continuous turbidity monitoring or other means acceptable to the Department that water quality is not adversely affected following filter backwashing, cleaning or media replacement. (3-30-07)
- **06. Continuous Turbidity Monitoring.** For conventional, direct, membrane, and diatomaceous earth filtration technology, equipment must be provided to continuously measure the turbidity of each filter unit. (3-30-07)
- **07. Continuous Monitoring of Disinfectant.** Equipment must be provided and operated for continuous measurement of disinfectant residual prior to entry to the distribution system, unless the system serves fewer than three thousand three hundred (3,300) people. (3-30-07)
- **08. Continuous Operation Required**. Diatomaceous earth filtration facilities shall include an alternate power source with automatic startup and alarm, or be designed in a manner to ensure continuous operation. (3-30-07)
- **O9.** Acceptable Technology. The purveyor shall select a filtration technology acceptable to the Department. (3-30-07)
- **a.** Conventional, direct, membrane, slow sand and diatomaceous earth filtration technologies are generally acceptable to the Department on a case-by-case basis. (5-3-03)
- **b.** Alternate filtration technologies may be acceptable if the purveyor demonstrates all of the following to the satisfaction of the Department: (12-10-92)
  - i. That the filtration technology: (12-10-92)
- (1) Is certified and listed by the National Sanitation Foundation (NSF) under Standard 53, Drinking Water Treatment Units Health Effects, as achieving the NSF criteria for cyst reduction; or (12-10-92)
- (2) Removes at least ninety-nine percent (99%) (two (2) logs) of Cryptosporidium oocysts or surrogate particles and removes or inactivates at least ninety-nine percent (99%) (two (2) logs) of Giardia lamblia cysts or Giardia lamblia cyst surrogate particles in a challenge study acceptable to the Department. (3-30-07)
- ii. Based on field studies or other means acceptable to the Department, it must be demonstrated that the filtration technology has the following capabilities: (3-30-07)
- (1) In combination with disinfection treatment, consistently achieves at least ninety-nine percent (99%) (two (2) logs) removal of Cryptosporidium oocysts or surrogate particles and at least ninety-nine and nine tenths percent (99.9%) (three (3) logs) removal or inactivation of Giardia lamblia cysts and ninety-nine and ninety-nine hundredths percent (99.99%) (four (4) logs) removal or inactivation of viruses; and (3-30-07)
  - (2) Meets the turbidity performance requirements of 40 CFR 141.73 (b). (12-10-92)
- **10. Pilot Studies**. The system shall conduct pilot studies in accordance with the following requirements for all proposed filtration facilities and structural modifications to existing filtration facilities, unless the Department modifies the requirements in writing:

  (12-10-92)
- **a.** The system shall obtain the Department's approval of the pilot study plan before the pilot filter is constructed and before the pilot study is undertaken. (12-10-92)

<b>b.</b> engineer.	The design and operation of the pilot study shall be overseen by an Idah	o licensed professional (3-30-07)
	The existence milest study plan shall identify at a minimum.	(12, 10, 02)

c.	The system's pilot study plan shall identify at a minimum:	(12-10-92)
----	--	------------

	FD1 1	(12.10	1001
1	The chiectives of the nilot stud	v: (12-10	1071
1.	The objectives of the pilot stud	V. (12-10	ノーフムト

- iii. Water quality and operational parameters to monitor; (12-10-92)
- iv. Amount of data to collect; and (12-10-92)
- v. Qualifications of the pilot plant operator. (10-1-93)
- **d.** The system shall ensure that the pilot study is: (12-10-92)
- i. Conducted to simulate conditions of the proposed full-scale design; (12-10-92)
- ii. Conducted for at least twelve (12) consecutive months or for a shorter period upon approval by the Department; (5-3-03)
- iii. Conducted to evaluate the reliability of the treatment system to achieve applicable water quality treatment criteria specified for filtration systems in 40 CFR 141.72 and 40 CFR 141.73; and (12-10-92)
- iv. Designed and operated in accordance with good engineering practices documented in references acceptable to the Department. (12-10-92)
- 11. Redundant Disinfection. Surface water systems constructed after July 1, 1985, are required to install redundant disinfection components or maintain a backup unit on site as required to maintain constant application of disinfectant whenever water is being delivered to the distribution system. (3-30-07)

### (BREAK IN CONTINUITY OF SECTIONS)

### 520. FACILITY AND DESIGN STANDARDS: SURFACE WATER TREATMENT: CLARIFICATION PROCESSES.

Treatment facilities designed to include clarification for processing surface water shall meet the following requirements: (3-30-07)

- **01. Two Units Required**. A minimum of two (2) units shall be provided for flocculation and sedimentation. (3-30-07)
- **O2. Parallel or Serial Operation**. The units shall be capable of being operated either in series or parallel where softening is performed. (3-30-07)
- **03. Independent Units**. The units shall be constructed in such a way that each can be taken out of service without disrupting operation, and with drains or pumps sized to allow dewatering in a reasonable period of time. (3-30-07)
  - **04. Manual Start-Up.** The units shall be started manually following shutdown. (3-30-07)
- **05. Pre-Treatment.** Waters exhibiting high turbidity may require pretreatment, usually sedimentation with or without the addition of coagulation chemicals. When presedimentation is provided, the following

requirements must be met:

(3-30-07)

- **a.** Incoming water shall be dispersed across the full width of the line of travel as quickly as possible. Short circuiting must be prevented. (3-30-07)
  - **b.** Provisions for bypassing pre-sedimentation basins shall be included. (3-30-07)
- **Rapid Mix.** Rapid mix shall mean the rapid dispersion of chemicals throughout the water to be treated, usually by violent agitation. The engineer shall submit the design basis for the velocity gradient (G value) selected, considering the chemicals to be added and water temperature, color and other related water quality parameters. Basins or mixing chambers shall be equipped with devices capable of providing adequate mixing for all treatment flow rates.

  (3-30-07)
- **O7. Flocculation**. Flocculation shall mean the gathering together of fine particles in water by gentle mixing after the addition of coagulant chemicals to form larger particles. (3-30-07)
- **a.** Basin inlet and outlet design shall minimize short-circuiting and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction of both drain and destruction of floc. A drain, pumps, or a combination of both drain and destruction and destruction of both drain and destruction are destructed by the destruction of both drain and destruction are destructed by the destruction of both drain and destruction are destructed by the destruction of both drain and destructed by the destruction of both drain and destructed by the destruction are destructed by the destruction and destructed by the destruction are destructed by the destruction are destructed by the destruction and destructed by the destruction are destructed by the destruction and destructed by the destruction are destructed by the destruction are
- **b.** The flow-through velocity shall not be less than one-half (0.5) nor greater than one and one-half (1.5) feet per minute with a detention time for floc formation of at least thirty (30) minutes unless otherwise approved by the Department. (3-30-07)
  - **c.** Agitators shall be driven by variable speed drives.

- **d.** Flocculation and sedimentation basins shall be as close together as possible. The velocity of flocculated water through pipes or conduits to settling basins shall be not less than one-half (0.5) nor greater than one and one-half (1.5) feet per second. Allowances must be made to minimize turbulence at bends and changes in direction. (3-30-07)
- **08. Small Systems May Use Baffling**. Baffling may be used to provide for flocculation in small plants upon approval by the Department. (3-30-07)
  - **O9. Sedimentation Units.** The following criteria apply to conventional sedimentation units: (3-30-07)
- **a.** A minimum of two (2) hours of settling time shall be provided following flocculation unless adequate settling in less time can be demonstrated. (3-30-07)
  - b. Inlets shall be designed to distribute the water equally and at uniform velocities. (3-30-07)
- c. Outlet weirs or submerged orifices shall maintain velocities suitable for settling in the basin and minimize short-circuiting. Outlet weirs shall be designed so that the rate of flow over the outlet weirs or through the submerged orifices shall not exceed twenty-thousand (20,000) gallons per day per foot of the outlet launder. The entrance velocity through the submerged orifices shall not exceed one-half (0.5) feet per second. (3-30-07)
- **d.** The velocity through settling basins shall not exceed one-half (0.5) feet per minute. The basins must be designed to minimize short-circuiting. Fixed or adjustable baffles must be provided as necessary to achieve the maximum potential for clarification. (3-30-07)
- **e.** When an overflow weir or pipe is provided the overflow shall discharge by gravity with a free fall at a location where the discharge will be noted. (3-30-07)
- **f.** Adequate sludge collection equipment that ensures proper basin coverage shall be provided and basins must be provided with a means for dewatering. (3-30-07)
  - g. Flushing lines or hydrants shall be provided and must be equipped with backflow prevention

devices acceptable to the Department.

- h. Sludge removal design shall provide that sludge pipes are not less than three (3) inches in diameter and arranged so as to facilitate cleaning. Entrance to sludge withdrawal piping shall be designed to prevent clogging. Provision shall be made for the operator to observe and sample sludge being withdrawn from the unit. (3-30-07)
  - i. Sludge shall be disposed of in accordance with applicable regulations, as set forth in Section 540.
- 10. Solids Contact Clarifiers. Solids contact clarifiers are generally acceptable for combined softening and clarification where water characteristics, especially temperature, do not fluctuate rapidly, flow rates are uniform and operation is continuous. A minimum of two (2) units are required for surface water treatment. (3-30-07)
- **a.** Chemicals shall be applied at such points and by such means as to ensure satisfactory mixing of the chemicals with the water. (3-30-07)
- **b.** Unless otherwise approved by the Department, a rapid mix device or chamber ahead of the solids contact clarifier is required to assure proper mixing of the chemicals applied. Mixing devices employed shall be constructed so as to provide good mixing of the raw water with previously formed sludge particles and prevent deposition of solids in the mixing zone. (3-30-07)
- c. Flocculation equipment shall be adjustable as to speed, <u>pitch</u>, <u>or a combination of speed</u> and <del>/or</del> pitch and must provide for coagulation in a separate chamber or baffled zone within the unit. (3 30 07)(\_\_\_\_\_)
- **d.** Sludge removal design shall provide that sludge pipes are not less than three (3) inches in diameter and arranged so as to facilitate cleaning. Entrance to sludge withdrawal piping shall be designed to prevent clogging. Provision shall be made for the operator to observe and sample sludge being withdrawn from the unit. (3-30-07)
- **e.** Blow-off outlets and drains must terminate and discharge at places acceptable to the Department in regard to control of potential cross connections. Cross connection control must be included for the potable water lines used to backflush sludge lines. (3-30-07)
- f. The detention time shall be established on the basis of the raw water characteristics and other local conditions that affect the operation of the unit. The Department may request data to support decisions made with respect to detention times. The Department may alter detention time requirements. (3-30-07)
  - g. Controls for sludge withdrawl which minimize water losses shall be provided. (3-30-07)
- h. Unless otherwise approved by the Department, weirs shall be adjustable and at least equivalent in length to the perimeter of the tank. Weir loading shall not exceed ten (10) gallons per minute per foot of weir length for units used as clarifiers or twenty (20) gallons per minute per foot of weir length for units used for softening. Where orifices are used, the loading rates per foot of launder rates shall be equivalent to weir loadings. Either shall produce uniform rising rates over the entire area of the tank. (3-30-07)
- i. Upflow rates shall not exceed one (1) gallon per minute per square foot of area at the sludge separation line for units used as clarifiers or one and three-quarters (1.75) gallons per minute per foot of area at the slurry separation line for units used as softeners. The Department may consider higher rates if supporting data is provided.

  (3-30-07)
- 11. Settler Units. Settler units consisting of variously shaped tubes or plates installed in multiple layers and at an angle to the flow may be used for sedimentation following flocculation. (3-30-07)
- **a.** Inlets and outlets shall be designed to maintain velocities suitable for settling in the basin and to minimize short-circuiting. Plate units shall be designed to minimize unequal distribution across the units. (3-30-07)
- **b.** Drain piping from the settler units must be sized to facilitate a quick flush of the settler units and to prevent flooding other portions of the plant. (3-30-07)

- **c.** Although most units will be located within a plant, outdoor installations must provide sufficient freeboard above the top of settlers to prevent freezing in the units. (3-30-07)
- **d.** Water shall be applied to tube settlers at a maximum rate of two (2) gallons per minute per square foot of cross-sectional area for tube settlers, unless higher rates are justified through pilot plant or in-plant demonstration studies. (3-30-07)
- **e.** Water shall be applied to plate settlers at a maximum plate loading rate of one-half (0.5) gallons per minute per square foot, based on eighty (80) percent of the projected horizontal plate area. (3-30-07)
- **f.** Flushing lines shall be provided to facilitate maintenance and must be properly protected against backflow or back siphonage. (3-30-07)
- 12. High Rate Clarification. High rate clarification processes may be approved upon demonstrating satisfactory performance under on-site pilot plant conditions or documentation of full scale plant operation with similar raw water quality conditions. Reductions in detention times and/or increases in weir loading rates shall be justified. Examples of such processes include dissolved air flotation, ballasted flocculation, contact flocculation/clarification, and helical upflow. (3-30-07)

### (BREAK IN CONTINUITY OF SECTIONS)

# 522. FACILITY AND DESIGN STANDARDS: SURFACE WATER TREATMENT: FILTRATION USING DIATOMACEOUS EARTH.

The use of these filters may be considered for application to surface waters with low turbidity and low bacterial contamination, and may be used for iron removal for ground waters providing the removal is effective and the water is of satisfactory sanitary quality before treatment. (3-30-07)

- **01. Conditions of Use**. Diatomaceous earth filters are expressly excluded from consideration for the following conditions: (3-30-07)
  - a. Bacteria removal; (3-30-07)
  - **b.** Color removal; (3-30-07)
- **c.** Turbidity removal where either the gross quantity of turbidity is high or the turbidity exhibits poor filterability characteristics; or (3-30-07)
  - **d.** Filtration of waters with high algae counts. (3-30-07)
- **O2. Treated Water Storage**. Treated water storage capacity in excess of normal requirements shall be provided to allow operation of the filters at a uniform rate during all conditions of system demand at or below the approved filtration rate, and guarantee continuity of service during adverse raw water conditions without by-passing the system. (3-30-07)
- Number of Units. The requirements of Subsection  $5\frac{1821}{0.03}$  shall apply to diatomaceous earth  $\frac{(3-30-07)(}{}$
- **04. Precoat**. A uniform precoat shall be applied hydraulically to each septum by introducing a slurry to the tank influent line and employing a filter-to-waste recirculation system. (3-30-07)
- **05. Body Feed.** A body feed system to apply additional amounts of diatomaceous earth slurry during the filter run is required to avoid short filter runs or excessive head losses. (3-30-07)

- The rate of body feed is dependent on raw water quality and characteristics and must be determined in the pilot plant study. (3-30-07)
  - b. Continuous mixing of the body feed slurry is required. (3-30-07)
  - 06. **Filtration Requirements.** (3-30-07)
  - a. Rate of filtration shall be controlled by a positive means. (3-30-07)
- Head loss shall not exceed thirty (30) psi for pressure diatomaceous earth filters, or a vacuum of fifteen (15) inches of mercury for a vacuum system.
- A recirculation or holding pump shall be employed to maintain differential pressure across the filter when the unit is not in operation in order to prevent the filter cake from dropping off the filter elements. A minimum recirculation rate of one-tenth (0.1) gallon per minute per square foot of filter area shall be provided. (3-30-07)
- The septum or filter elements shall be structurally capable of withstanding maximum pressure and d. velocity variations during filtration and backwash cycles, and shall be spaced such that no less than one (1) inch is provided between elements or between any element and a wall. (3-30-07)
- The filter influent shall be designed to prevent scour of the diatomaceous earth from the filter e. element. (3-30-07)
- **07.** Backwash. A satisfactory method to thoroughly remove and dispose of spent filter cake shall be provided. (3-30-07)
  - 08. **Appurtenances**. The following shall be provided for every filter: (3-30-07)
  - a. Sampling taps for raw and filtered water. (3-30-07)
  - h. Loss of head or differential pressure gauge. (3-30-07)
  - c. Rate-of-flow indicator. (3-30-07)
  - d. A throttling valve used to reduce rates below normal during adverse raw water conditions.
    - (3-30-07)
  - f.
- **Monitoring.** A continuous monitoring turbidimeter with recorder is required on each filter effluent

Provisions for filtering to waste with appropriate measures for backflow prevention.

Evaluation of the need for body feed, recirculation, and any other pumps.

### for plants treating surface water. (3-30-07)

### FACILITY AND DESIGN STANDARDS: SURFACE WATER TREATMENT: SLOW SAND FILTRATION.

The use of these filters shall require prior engineering studies to demonstrate the adequacy and suitability of this method of filtration for the specific water supply. Slow Sand Filtration and Diatomaceous Earth Filtration for Small Water Systems, Manual on Slow Sand Filtration, and Slow Sand Filtration referenced in Subsection 002.02, may be used as guidance in design of slow sand filtration facilities. (3-30-07)

- Quality of Raw Water. Slow rate gravity filtration shall be limited to waters having maximum turbidities of ten (10) nephelometric units and maximum color of fifteen (15) units; such turbidity must not be attributable to colloidal clay. Raw water quality data must include examinations for algae. (3-30-07)
- Number of Units. At least two (2) units shall be provided. Where only two (2) units are provided, each shall be capable of meeting the plant design capacity (normally the projected maximum daily demand) at the

e.

(3-30-07)

approved filtration rate. Where more than two (2) filter units are provided, the filters shall be capable of meeting the plant design capacity at the approved filtration rate with one filter removed from service. (3-30-07)

- **03. Structural Details and Hydraulics.** Slow rate gravity filters shall be so designed as to provide a cover, unless otherwise approved by the Department, headroom to permit normal movement by operating personnel for scraping and sand removal operations, adequate access hatches and access ports for handling of sand and for ventilation, filtration to waste, an overflow at the maximum filter water level, and protection from freezing.(3-30-07)
- **04. Underdrains**. Each filter unit shall be equipped with a main drain and an adequate number of lateral underdrains to collect the filtered water. The underdrains shall be so spaced that the maximum velocity of the water flow in the underdrain will not exceed three-fourths (0.75) feet per second. The maximum spacing of laterals shall not exceed three (3) feet if pipe laterals are used. (3-30-07)
  - **05. Filter Material**. The following requirements apply: (3-30-07)
- a. Graded gravel layers beneath filter sand shall have a minimum depth of thirty (30) inches. A minimum depth of thirty (30) inches of filter sand shall be placed on graded gravel layers.
- **b.** The effective size shall be between fifteen hundredths (0.15) of a millimeter and thirty-five hundredths (0.35) of a millimeter. Larger sizes may be considered by the Department based on the results of pilot testing. (3-30-07)
  - **c.** The uniformity coefficient shall not exceed three point zero (3.0). (3-30-07)
  - **d.** The sand shall be cleaned and washed free from foreign matter. (3-30-07)
- e. The sand shall be rebedded to the original minimum depth of thirty (30) inches when scraping has reduced the bed depth to no less than twenty-four (24) inches. Where sand is to be reused in order to provide biological seeding and shortening of the ripening process, rebedding shall utilize a "throw over" technique whereby new sand is placed on the support gravel and existing sand is replaced on top of the new sand. The maximum filtration rate shall not exceed zero point one (0.1) gallon per minute per square foot.

### 06. Filter Sand Support.

- a. A three (3)-inch layer of sand shall be used as a supporting media for filter sand. The supporting sand shall have an effective size of zero point eight (0.8) millimeters to two point zero (2.0) millimeters and a uniformity coefficient not greater than one point seven (1.7).
- **b.** Gravel shall consist of cleaned and washed, hard, durable, rounded rock particles and shall not include flat or elongated particles. The coarsest gravel shall be two and one-half (2.5) inches in size when the gravel rests directly on a lateral system and must extend above the top of the perforated laterals. Not less than four (4) layers of gravel shall be provided in accordance with the size and depth distribution specified in the table below. Reduction of gravel depths and other size gradations may be considered upon justification to the Department.

Size of Gravel	<u>Depth</u>
2 1/2 to 1 1/2 inches	5 to 8 inches
1 <sup>1</sup> / <sub>2</sub> to <sup>3</sup> / <sub>4</sub> inches	3 to 5 inches
3/4 to 1/2 inches	3 to 5 inches
<sup>1</sup> / <sub>2</sub> to <sup>3</sup> / <sub>16</sub> inches	2 to 3 inches
<sup>3</sup> / <sub>16</sub> to <sup>3</sup> / <sub>32</sub> inches	2 to 3 inches

Docket No. 58-0108-0801 Proposed Rulemaking

- **067. Depth of Water Over Filter Beds**. The design shall provide a depth of at least three (3) to six (6) feet of water over the sand. Influent water shall not scour the sand surface. (3-30-07)
- **078. Control Appurtenances.** Each filter shall be equipped with a loss of head gauge, an orifice, Venturi meter, or other suitable means of discharge measurement installed on each filter to control the rate of filtration, and an effluent pipe designed to maintain the water level above the top of the filter sand. (3-30-07)
- **082. Ripening.** Slow sand filters shall be operated to waste after scraping or rebedding during a ripening period until the filter effluent turbidity falls to consistently below the regulated drinking water standard established for the system. (3-30-07)
- **6910. Supernatant Drain Required.** Filter beds shall be equipped with a supernatant drain to allow for quick removal of water standing over sand that has become impermeable because it requires scraping or rebedding. (3-30-07)

### (BREAK IN CONTINUITY OF SECTIONS)

### 530. FACILITY AND DESIGN STANDARDS: DISINFECTION OF DRINKING WATER.

Disinfection may be accomplished with gas and liquid chlorine, calcium or sodium hypochlorites, chlorine dioxide, ozone, or ultraviolet light. Other disinfecting agents will be considered, providing reliable application equipment is available and testing procedures for a residual are recognized in "Standard Methods for the Examination of Water and Wastewater," referenced in Subsection 002.02, or an equivalent means of measuring effectiveness exists. The required amount of primary disinfection needed shall be specified by the Department. Consideration must be given to the formation of disinfection by-products (DBP) when selecting the disinfectant. See Section 531, Facility Design Standards - Design Standards for Chemical Application. (3-30-07)

01.	Chlorination.	(3-30-07)
-----	---------------	-----------

- a. Chlorination equipment shall meet the following requirements:
- i. Solution-feed gas chlorinators or hypochlorite feeders of the positive displacement type must be provided. (3-30-07)
- ii. Standby or backup equipment of sufficient capacity shall be available to replace the largest unit. Spare parts shall be *made available* on hand to replace parts subject to wear and breakage. (3 30 07)(\_\_\_\_\_)
- iii. Automatic proportioning chlorinators will be required where the rate of flow or chlorine demand is not reasonably constant. (3-30-07)
- iv. Each eductor (submerged jet pump) must be selected for the point of application with particular attention given to the quantity of chlorine to be added, the maximum injector waterflow, the total discharge back pressure, the injector operating pressure, and the size of the chlorine solution line. (3-30-07)
- v. The chlorine solution injector/diffuser must be compatible with the point of application to provide a rapid and thorough mix with all the water being treated. (3-30-07)
- vi. Automatic switch-over of chlorination treatment units shall be provided, where necessary, to assure continuous disinfection.
  - **b.** Contact time and point of application requirements are as follows: (3-30-07)
- i. Contact time sufficient to achieve the inactivation of target pathogens under the expected range of raw water pH and temperature variation must be demonstrated through tracer studies or other evaluations acceptable to the Department. Appendix E of EPA Guidance Manual for Compliance with the Filtration and Disinfection

will not continue when the flow of water stops.

Requirements for Public Water Systems Using Surface Water Sources, referenced in Section 002.02, contains tables that may be used as guidance to develop contact time requirements for specific target organisms and disinfectants. Additional baffling can be added to new or existing basins to minimize short circuiting and increase contact time.

ii. At plants treating surface water, except slow sand filtration systems, provisions shall be made for applying the disinfectant to the raw water, settled water, filtered water, and water entering the distribution system. Disinfectant application equipment shall be controlled by a flow sensing device so that injection of the disinfectant

- iii. At a minimum, at plants treating ground water, provisions shall be made for applying the disinfectant to the detention basin contact chamber inlet and water entering the distribution system. (3-30-07)(\_\_\_\_\_\_)
- c. Chlorine residual test equipment recognized in the "Standard Methods for the Examination of Water and Wastewater," referenced in Subsection 002.02, shall be provided for use by the operator. All surface water treatment plants that serve a population greater that three thousand three hundred (3,300) must have equipment to measure chlorine residuals continuously entering the distribution system. A sample tap shall be provided to measure chlorine residual and shall be located at a point after receiving the required contact time and at or prior to the first service connection.

  (3-30-07)(\_\_\_\_\_)

### **d.** Chlorinator piping requirements:

(3-30-07)

- i. Cross connection protection: The chlorinator water supply piping shall be designed to prevent contamination of the treated water supply by sources of questionable quality. At all facilities treating surface water, pre- and post-chlorination systems must be independent to prevent possible siphoning of partially treated water into the clear well. The water supply to each eductor shall have a separate shut-off valve. No master shut-off valve will be allowed.

  (3-30-07)
- ii. The pipes carrying elemental liquid or dry gaseous chlorine under pressure must be Schedule 80 seamless steel tubing or other materials recommended by the Chlorine Institute (never use PVC). Rubber, PVC, polyethylene, or other materials recommended by the Chlorine Institute must be used for chlorine solution piping and fittings. Nylon products are not acceptable for any part of the chlorine solution piping system. (3-30-07)
- **02. Disinfection with Ozone**. Systems that are required to maintain a disinfectant residual in the distribution system shall supplement ozone disinfection with a chemical disinfectant. (3-30-07)
  - **a.** The following are requirements for feed gas preparation:

(3-30-07)

i. Feed gas can be air, oxygen enriched air, or high purity oxygen. Sources of high purity oxygen include purchased liquid oxygen conforming with AWWA Standard B-304; on site generation using cryogenic air separation; or temperature, pressure or vacuum swing (adsorptive separation) technology. In all cases, the design engineer must ensure that the maximum dew point of  $-76^{\circ}$ F ( $-60^{\circ}$ C) will not be exceeded at any time. (3-30-07)

### ii. Air compression:

- (1) Air compressors shall be of the liquid-ring or rotary lobe, oil-less, positive displacement type for smaller systems or dry rotary screw compressors for larger systems. (3-30-07)
- (2) The air compressors shall have the capacity to simultaneously provide for maximum ozone demand, provide the air flow required for purging the desiccant dryers (where required) and allow for standby capacity. (3-30-07)
- (3) Air feed for the compressor shall be drawn from a point protected from rain, condensation, mist, fog and contaminated air sources to minimize moisture and hydrocarbon content of the air supply. (3-30-07)
- (4) A compressed air after-cooler, *and/or* entrainment separator, or a combination of the two (2) with automatic drain shall be provided prior to the dryers to reduce the water vapor. (3-30-07)(\_\_\_\_\_)

(5) A back-up air compressor must be provided so that ozone generation is not interrupted in the event of a break-down. (3-30-07)

iii. Air drying: (3-30-07)

- (1) Dry, dust-free and oil-free feed gas must be provided to the ozone generator. Dry gas is essential to prevent formation of nitric acid, to increase the efficiency of ozone generation and to prevent damage to the generator dielectrics. Sufficient drying to a maximum dew point of -76°F (-60°C) must be provided at the end of the drying cycle.

  (3-30-07)
- (2) Drying for high pressure systems may be accomplished using heatless desiccant dryers only. For low pressure systems, a refrigeration air dryer in series with heat-reactivated desiccant dryers shall be used.(3-30-07)
- (3) A refrigeration dryer capable of reducing inlet air temperature to  $40^{\circ}F$  ( $4^{\circ}C$ ) shall be provided for low pressure air preparation systems. The dryer can be of the compressed refrigerant type or chilled water type.

  (3-30-07)
- (4) For heat-reactivated desiccant dryers, the unit shall contain two (2) desiccant filled towers complete with pressure relief valves, two (2) four-way valves and a heater. In addition, external type dryers shall have a cooler unit and blowers. The size of the unit shall be such that the specified dew point will be achieved during a minimum adsorption cycle time of sixteen (16) hours while operating at the maximum expected moisture loading conditions.

  (3-30-07)
- (5) Multiple air dryers shall be provided so that the ozone generation is not interrupted in the event of dryer breakdown. (3-30-07)
- (6) Each dryer shall be capable of venting "dry" gas to the atmosphere, prior to the ozone generator, to allow start-up when other dryers are "on-line." (3-30-07)

iv. Air filters: (3-30-07)

- (1) Air filters shall be provided on the suction side of the air compressors, between the air compressors and the dryers and between the dryers and the ozone generators. (3-30-07)
- (2) The filter before the desiccant dryers shall be of the coalescing type and be capable of removing aerosol and particulates larger than 0.3 microns in diameter. The filter after the desiccant dryer shall be of the particulate type and be capable of removing all particulates greater than 0.1 microns in diameter, or smaller if specified by the generator manufacturer. (3-30-07)
- v. Piping in the air preparation system can be common grade steel, seamless copper, stainless steel or galvanized steel. The piping must be designed to withstand the maximum pressures in the air preparation system.

  (3-30-07)
  - **b.** The following requirements apply to the ozone generator:
  - i. Capacity. (3-30-07)
- (1) The production rating of the ozone generators shall be stated in pounds per day and kWhr per pound at a maximum cooling water temperature and maximum ozone concentration. (3-30-07)
- (2) The design shall ensure that the minimum concentration of ozone in the generator exit gas will not be less than one (1) percent (by weight). (3-30-07)
- (3) Generators shall be sized to have sufficient reserve capacity so that the system does not operate at peak capacity for extended periods of time resulting in premature breakdown of the dielectrics. (3-30-07)

- (4) The production rate of ozone generators will decrease as the temperature of the coolant increases. If there is to be a variation in the supply temperature of the coolant throughout the year, then pertinent data shall be used to determine production changes due to the temperature change of the supplied coolant. The design shall ensure that the generators can produce the required ozone at maximum coolant temperature. (3-30-07)
  - (5) Appropriate ozone generator backup equipment must be provided.
- ii. Electrical. The generators can be low, medium or high frequency type. Specifications shall require that the transformers, electronic circuitry and other electrical hardware be proven, high quality components designed for ozone service. (3-30-07)
- iii. Cooling. Adequate cooling shall be provided. The cooling water must be properly treated to minimize corrosion, scaling and microbiological fouling of the water side of the tubes. Where cooling water is treated, cross connection control shall be provided to prevent contamination of the potable water supply. (3-30-07)
- iv. Materials. To prevent corrosion, the ozone generator shell and tubes shall be constructed of Type 316L stainless steel. (3-30-07)
  - c. The following requirements apply to ozone contactors: (3-30-07)
  - i. Bubble diffusers. (3-30-07)
- (1) Where disinfection is the primary application, a minimum of two (2) contact chambers each equipped with baffles to prevent short circuiting and induce countercurrent flow shall be provided. Ozone shall be applied using porous-tube or dome diffusers. (3-30-07)
- (2) The minimum contact time shall be ten (10) minutes. A shorter contact time (CT) may be approved by the Department if justified by appropriate design and "CT" considerations. (3-30-07)
- (3) Where taste and odor control is of concern, multiple application points and contactors shall be considered. (3-30-07)
- (4) Contactors shall be separate closed vessels that have no common walls with adjacent rooms. The contactor must be kept under negative pressure and sufficient ozone monitors shall be provided to protect worker safety. (3-30-07)
- (5) Contact vessels can be made of reinforced concrete, stainless steel, fiberglass or other material which will be stable in the presence of residual ozone and ozone in the gas phase above the water level. If contact vessels are made of reinforced concrete, all reinforcement bars shall be covered with a minimum of one and one-half (1.5) inches of concrete. (3-30-07)
- (6) Where necessary, a system shall be provided between the contactor and the off-gas destruct unit to remove froth from the air and return the other to the contactor or other location acceptable to the reviewing authority. If foaming is expected to be excessive, then a potable water spray system shall be placed in the contactor head space.

  (3-30-07)
- (7) All openings into the contactor for pipe connections, hatchways, etc. shall be properly sealed using welds or ozone resistant gaskets such as Teflon or Hypalon. (3-30-07)
- (8) Multiple sampling ports shall be provided to enable sampling of each compartment's effluent water and to confirm "CT" calculations. (3-30-07)
- (9) A pressure/vacuum relief valve shall be provided in the contactor and piped to a location where there will be no damage to the destruction unit. (3-30-07)
- (10) The depth of water in bubble diffuser contactors shall be a minimum of eighteen (18) feet. The contactor shall also have a minimum of three (3) feet of freeboard to allow for foaming. (3-30-07)

- (11) All contactors shall have provisions for cleaning, maintenance and drainage of the contactor. Each contactor compartment shall also be equipped with an access hatchway. (3-30-07)
  - (12) Aeration diffusers shall be fully serviceable by either cleaning or replacement. (3-30-07)
- ii. Other contactors, such as the venturi or aspirating turbine mixer contactor, may be approved by the Department provided adequate ozone transfer is achieved and the required contact times and residuals can be met and verified. (3-30-07)
  - **d.** The following requirements apply to ozone destruction units: (3-30-07)
- i. A system for treating the final off-gas from each contactor must be provided in order to meet safety and air quality standards. Acceptable systems include thermal destruction and thermal/catalytic destruction units.

  (3-30-07)
  - ii. The maximum allowable ozone concentration in the discharge is 0.1 ppm (by volume). (3-30-07)
  - iii. At least two (2) units shall be provided which are each capable of handling the entire gas flow.
    (3-30-07)
  - iv. Exhaust blowers shall be provided in order to draw off-gas from the contactor into the destruct unit. (3-30-07)
  - v. Catalysts must be protected from froth, moisture and other impurities which may harm the catalyst. (3-30-07)
- vi. The catalyst and heating elements shall be located where they can easily be reached for maintenance. (3-30-07)
- **e.** Piping materials: Only low carbon 304L and 316L stainless steels shall be used for ozone service with 316L preferred. (3-30-07)
  - **f.** The following requirements apply to joints and connections: (3-30-07)
  - i. Connections on piping used for ozone service are to be welded where possible. (3-30-07)
- ii. Connections with meters, valves or other equipment are to be made with flanged joints with ozone resistant gaskets, such as Teflon or Hypalon. Screwed fittings shall not be used because of their tendency to leak.

  (3-30-07)
- iii. A positive closing plug or butterfly valve plus a leak-proof check valve shall be provided in the piping between the generator and the contactor to prevent moisture reaching the generator. (3-30-07)
  - **g.** The following requirements apply to instrumentation: (3-30-07)
- i. Pressure gauges shall be provided at the discharge from the air compressor, at the inlet to the refrigeration dryers, at the inlet and outlet of the desiccant dryers, at the inlet to the ozone generators and contactors, and at the inlet to the ozone destruction unit. (3-30-07)
- ii. Each generator shall have a trip which shuts down the generator when the wattage exceeds a certain preset level. (3-30-07)
- iii. Dew point monitors shall be provided for measuring the moisture of the feed gas from the desiccant dryers. Where there is potential for moisture entering the ozone generator from downstream of the unit or where moisture accumulation can occur in the generator during shutdown, post-generator dew point monitors shall be used.

  (3-30-07)

- iv. Air flow meters shall be provided for measuring air flow from the desiccant dryers to each of the other ozone generators, air flow to each contactor, and purge air flow to the desiccant dryers. (3-30-07)
- v. Temperature gauges shall be provided for the inlet and outlet of the ozone cooling water and the inlet and outlet of the ozone generator feed gas and, if necessary, for the inlet and outlet of the ozone power supply cooling water. (3-30-07)
- vi. Water flow meters shall be installed to monitor the flow of cooling water to the ozone generators and, if necessary, to the ozone power supply. (3-30-07)
- vii. Ozone monitors shall be installed to measure zone concentration in both the feed-gas and off-gas from the contactor and in the off-gas from the destruct unit. For disinfection systems, monitors shall also be provided for monitoring ozone residuals in the water. The number and location of ozone residual monitors shall be such that the amount of time that the water is in contact with the ozone residual can be determined. (3-30-07)
- viii. A minimum of one ambient ozone monitor shall be installed in the vicinity of the contactor and a minimum of one shall be installed in the vicinity of the generator. Ozone monitors shall also be installed in any areas where ozone gas may accumulate. (3-30-07)
  - **h.** Safety requirements are as follows:

- i. The maximum allowable ozone concentration in the air to which workers may be exposed must not exceed one-tenth part per million (0.1 ppm) by volume. (3-30-07)
- ii. Noise levels resulting from the operating equipment of the ozonation system shall be controlled to within acceptable limits by special room construction and equipment isolation. (3-30-07)
- iii. Emergency exhaust fans must be provided in the rooms containing the ozone generators to remove ozone gas if leakage occurs. (3-30-07)
- iv. A sign shall be posted indicating "No smoking, oxygen in use" at all entrances to the treatment plant. In addition, no flammable or combustible materials shall be stored within the oxygen generator areas.

(3-30-07)

- **03. Disinfection with Chlorine Dioxide**. Chlorine dioxide may be considered as a primary and residual disinfectant, a pre-oxidant to control tastes and odors, to oxidize iron and manganese, and to control hydrogen sulfide and phenolic compounds. When choosing chlorine dioxide, consideration must be given to formation of the regulated by-products, chlorite and chlorate. (3-30-07)
- **a.** Chlorine dioxide generation equipment shall be factory assembled pre-engineered units with a minimum efficiency of ninety-five (95) percent. The excess free chlorine shall not exceed three (3) percent of the theoretical stoichiometric concentration required. (3-30-07)
  - **b.** Other design requirements include:

- i. The design shall comply with all applicable portions of Subsections 530.01.a. through 530.01.d. (3-30-07)
- ii. The maximum residual disinfectant level allowed shall be zero point eight (0.8) milligrams per liter (mg/l), even for short term exposures. (3-30-07)
- iii. Notification of a change in disinfection practices and the schedule for the changes shall be made known to the public; particularly to hospitals, kidney dialysis facilities and fish breeders, as chlorine dioxide and its by-products may have effects similar to chloramines. (3-30-07)
  - **Other Disinfecting Agents.** Proposals for use of disinfecting agents other than those listed shall be

submitted to the Department for approval prior to preparation of final plans and specifications. (3-30-07)

### 531. FACILITY DESIGN STANDARDS: DESIGN STANDARDS FOR CHEMICAL APPLICATION.

- **01. General Equipment Design.** General equipment design shall be such that: (3-30-07)
- **a.** Feeders will be able to supply, at all times, the necessary amounts of chemicals at an accurate rate, throughout the range of feed. (3-30-07)
- **b.** Chemical-contact materials and surfaces are resistant to the aggressiveness of the chemical solution. (3-30-07)
  - **c.** Corrosive chemicals are introduced in such a manner as to minimize potential for corrosion. (3-30-07)
- **d.** Chemicals that are incompatible are not stored or handled together. At facilities where more than one (1) chemical is stored or handled, tanks and pipelines shall be clearly labeled to identify the chemical they contain. (3-30-07)
  - **e.** All chemicals are conducted from the feeder to the point of application in separate conduits. (3-30-07)
  - **f.** Chemical feeders are as near as practical to the feed point. (3-30-07)
- g. Chemical feeders and pumps shall operate at no lower than twenty percent (20%) of the feed range unless two fully independent adjustment mechanisms such as pump pulse rate and stroke length are fitted when the pump shall operate at no lower than ten percent (10%) of the rated maximum. (3-30-07)
  - <u>h.</u> Spare parts shall be on hand for parts of feeders that are subject to frequent wear and damage.
- <u>i.</u> Redundant chemical feeders with automatic switchover shall be provided when necessary to ensure adequate treatment.

### **02.** Facility Design. (3-30-07)

- **a.** Where chemical feed is necessary for the protection of the supply, such as disinfection, coagulation or other essential processes, a minimum of two feeders shall be provided and a separate feeder shall be used for each chemical applied. (3-30-07)
  - **b.** Chemical application control systems shall meet the following requirements: (3-30-07)
- i. Feeders may be manually or automatically controlled, with automatic controls being designed so as to allow override by manual controls. (3-30-07)
- ii. Chemical feeders shall be controlled by a flow sensing device so that injection of the chemicals will not continue when the flow of water stops. (3-30-07)
  - iii. Chemical feed rates shall be proportional to flow. (3-30-07)
  - iv. A means to measure water flow must be provided in order to determine chemical feed rates.
    (3-30-07)
  - v. Provisions shall be made for measuring the quantities of chemicals used. (3-30-07)
- vi. Weighing scales shall be provided for weighing cylinders at all plants utilizing chlorine gas, fluoride solution feed. (3-30-07)

- vii. Weighing scales  $\underline{Ss}$  hall be capable of providing reasonable precision in relation to average daily dose.
- viii. Where conditions warrant, for example with rapidly fluctuating intake turbidity, coagulant and coagulant aid addition may be made according to turbidity, streaming current or other sensed parameter. (3-30-07)
- c. Dry chemical feeders shall measure chemicals volumetrically or gravimetrically, provide adequate solution water and agitation of the chemical in the solution pot, and completely enclose chemicals to prevent emission of dust to the operating room. (3-30-07)
- **d.** Positive displacement type solution feed pumps must be capable of operating at the required maximum head conditions found at the point of injection. (3-30-07)
- **e.** Liquid chemical feeders shall be such that chemical solutions cannot be siphoned or overfed into the water supply, by assuring discharge at a point of positive pressure, or providing vacuum relief, or providing a suitable air gap, or providing other suitable means or combinations as necessary. (3-30-07)
  - **f.** Cross connection control must be provided to assure that the following requirements are satisfied. (3-30-07)
- i. The service water lines discharging to solution tanks shall be properly protected from backflow-as required in Subsection 900.02 (Table 2).
- ii. No direct connection exists between any sewer and a drain or overflow from the feeder, solution chamber or tank by providing that all drains terminate at least six (6) inches or two pipe diameters, whichever is greater, above the overflow rim of a receiving sump, conduit or waste receptacle. (3-30-07)
- **g.** Chemical feed equipment shall be readily accessible for servicing, repair, and observation of operation. (3-30-07)
  - h. In-plant water supply for chemical mixing shall be:
  - i. Ample in quantity and adequate in pressure. (3-30-07)
  - ii. Provided with means for measurement when preparing specific solution concentrations by dilution. (3-30-07)
  - iii. Properly treated for hardness, when necessary. (3-30-07)
  - iv. Properly protected against backflow. (3-30-07)
- v. Obtained from a location sufficiently downstream of any chemical feed point to assure adequate mixing. (3-30-07)
  - i. Chemical storage facilities shall satisfy the following requirements: (3-30-07)
- i. Storage tanks and pipelines for liquid chemicals shall be specified for use with individual chemicals and not used for different chemicals. Off-loading areas must be clearly labeled to prevent accidental cross-contamination. (3-30-07)
- ii. Chemicals shall be stored in covered or unopened shipping containers, unless the chemical is transferred into an approved storage unit. (3-30-07)
- iii. Liquid chemical storage tanks must have a liquid level indicator and have an overflow and a receiving basin capable of receiving accidental spills or overflows without uncontrolled discharge; a common receiving basin may be provided for each group of compatible chemicals, that provides sufficient containment volume

Docket No. 58-0108-0801 Proposed Rulemaking

to prevent	accide	ntal discharge in the event of failure of the largest tank.	<del>(3-30-07)</del>
j.		Solution Bulk liquid storage tanks shall comply with the following requirements:	(3-30-07)()
i. tank to m suspension	aintain	A means which is consistent with the nature of the chemical solution shall be provia uniform strength of solution. Continuous agitation shall be provided to mai	
ii		Means shall be provided to measure the liquid level in the tank.	(3-30-07)
ii with acces		Chemical solutions Bulk liquid storage tanks shall be kept covered. Large Bulk liquings shall have such openings curbed and fitted with overhanging covers.	uid storage tanks <del>(3-30-07)</del> ()
iv contamina		Subsurface locations for solution bulk liquid storage tanks shall be free from sound assure positive drainage for ground waters, accumulated water, chemical spills at	
V. Acid stora		Bulk liquid storage tanks shall be vented, but shall not vent through vents common as must be vented to the outside atmosphere, but not through vents in common with	
	i. <i>e with</i>	Each <u>bulk liquid storage</u> tank shall be provided with a valved drain, protected aga Subsection 900.02 (Table 2).	ainst backflow- <i>in</i> (3-30-07)()
<del>failure, sp</del> i	ıks sha	Solution tanks shall be located and protective curbings provided so that chemicals or accidental drainage shall not enter the water in conduits, treatment or storage ball have an overflow that is turned downward with the end screened, has a free fall ticeable.	<del>ısins.</del> <u>Bulk liquid</u>
equipment provided f shall provi	or each	Bulk liquid storage tanks shall be provided with secondary containment so that e, spillage, or accidental drainage shall be fully contained. A common receiving group of compatible chemicals. The bulk liquid storage tank basin or the common econdary containment volume sufficient to hold the volume of the largest storage to inimize or contain chemical spills in the event of pipe ruptures.	ng basin may be n receiving basin
	<u>«.</u> supply	Where chemical feed is necessary for the protection of the supply, a means to assimile servicing a bulk liquid storage tank shall be provided.	ure continuity of ()
purposes of chemical s	of Sect	Day tanks are subject to the requirements in Subsections 531.02.k.i. through 531 ion 531, day tanks are defined as liquid chemical tanks holding no more than a	.02.k.iv. For the thirty (30) hour
<u>i.</u> may allow	chemi	Day tanks shall be provided where bulk storage of liquid chemicals are provided. cals to be fed directly from shipping containers no larger than fifty-five (55) gallons	
	iii. Shi	Day tanks shall meet all the requirements of Subsection 531.02.j., with the exceptioning containers do not require overflow pipes or drains as required by Subsection requirements of Subsection 531.02.j.viii.	
each group sufficient located an	r accide p of co to hold d prote	Where feasible, secondary containment shall be provided so that chemicals from edental drainage of day tanks shall be fully contained. A common receiving basin may empatible chemicals. The common receiving basin shall provide a secondary contained the volume of the largest storage tank. If secondary containment is not feasible, decrive curbings provided so that chemicals from equipment failure, spillage, or accident enter the water in conduits, treatment, or storage basins.	y be provided for tainment volume ay tanks shall be
<u>iv</u>	/ <u>.</u>	Day tanks and the tank refilling line entry points shall be clearly labeled with	the name of the

<u>iv.</u>

chemical contained.

- **k].** Provisions shall be made for measuring quantities of chemicals used to prepare feed solutions. (3-30-07)
- **Im.** Vents from feeders, storage facilities and equipment exhaust shall discharge to the outside atmosphere above grade and remote from air intakes. (3-30-07)
- **03.** Chemicals. Chemical shipping containers shall be fully labeled to include chemical name, purity and concentration, supplier name and address, and evidence of ANSI/NSF certification where applicable. (3-30-07)
  - **04.** Safety Requirements for Chemical Facilities. (3-30-07)
  - **a.** The following requirements apply to chlorine gas feed and storage rooms: (3-30-07)
- i. Each storage room shall be enclosed and separated from other operating areas. They shall be constructed in such a manner that all openings between the chlorine room and the remainder of the plant are sealed, and provided with doors equipped with panic hardware, assuring ready means of exit and opening outward only to the building exterior.

  (3-30-07)
  - ii. Each room shall be provided with a shatter resistant inspection window installed in an interior wall. (3-30-07)
- iii. Each room shall have a ventilating fan with a capacity which provides one (1) complete air change per minute when the room is occupied. Where this is not appropriate due to the size of the room, a lesser rate may be allowed by the Department on a site specific basis. (3-30-07)
- iv. The ventilating fan shall take suction near the floor as far as practical from the door and air inlet, with the point of discharge so located as not to contaminate air inlets to any rooms or structures. Air inlets shall be through louvers near the ceiling. (3-30-07)
  - v. Louvers for chlorine room air intake and exhaust shall facilitate airtight closure. (3-30-07)
- vi. Separate switches for the fan and lights shall be located outside of the chlorine room and at the inspection window. Outside switches shall be protected from vandalism. A signal light indicating fan operation shall be provided at each entrance when the fan can be controlled from more than one (1) point. (3-30-07)
  - vii. Vents from feeders and storage shall discharge to the outside atmosphere, above grade. (3-30-07)
- viii. Where provided, floor drains shall discharge to the outside of the building and shall not be connected to other internal or external drainage systems. (3-30-07)
- ix. Chlorinator rooms shall be heated to sixty degrees farenheit (60°F) and be protected from excessive heat. Cylinders and gas lines shall be protected from temperatures above that of the feed equipment. (3-30-07)
  - x. Pressurized chlorine feed lines shall not carry chlorine gas beyond the chlorinator room. (3-30-07)
  - xi. Critical isolation valves shall be conspicuously marked and access kept unobstructed. (3-30-07)
- xii. All chlorine rooms, buildings, and areas shall be posted with a prominent danger sign warning of the presence of chlorine. (3-30-07)
- xiii. Full and empty cylinders of chlorine gas shall be isolated from operating areas and stored in definitely assigned places away from elevators, stairs, or gangways. They shall be restrained in position to prevent being knocked over or damaged by passing or falling objects. In addition, they shall be stored in rooms separate from ammonia storage, out of direct sunlight, and at least twenty (20) feet from highly combustible materials. Cylinders shall not be kept in unventilated enclosures such as lockers and cupboards. (3-30-07)

- b. Where acids and caustics are used, they shall be kept in closed corrosion-resistant shipping containers or storage units. Acids and caustics shall not be handled in open vessels, but shall be pumped in undiluted form from original containers through suitable hose to the point of treatment or to a covered day tank.
- Sodium chlorite for chlorine dioxide generation. Proposals for the storage and use of sodium chlorite shall be approved by the Department prior to the preparation of final plans and specifications. Provisions shall be made for proper storage and handling of sodium chlorite to eliminate any danger of fire or explosion associated with its oxidizing nature.
- Chlorite (sodium chlorite) shall be stored by itself in a separate room. It must be stored away from organic materials. The storage structure shall be constructed of noncombustible materials. If the storage structure must be located in an area where a fire may occur, water must be available to keep the sodium chlorite area cool enough to prevent heat-induced explosive decomposition of the chlorite. (3-30-07)
- Care shall be taken to prevent spillage. An emergency plan of operation shall be available for the clean up of any spillage. Storage drums shall be thoroughly flushed prior to recycling or disposal.
- Where ammonium hydroxide is used, an exhaust fan shall be installed to withdraw air from high points in the room and makeup air shall be allowed to enter at a low point. The feed pump, regulators, and lines shall be fitted with pressure relief vents discharging outside the building away from any air intake and with water purge lines leading back to the headspace of the bulk storage tank.
- Where anhydrous ammonia is used, the storage and feed systems (including heaters where required) shall be enclosed and separated from other work areas and constructed of corrosion resistant materials. (3-30-07)

- i. Pressurized ammonia feed lines shall be restricted to the ammonia room.
- An emergency air exhaust system, as described in Subsection 531.04.a., but with an elevated intake, shall be provided in the ammonia storage room. (3-30-07)
  - Leak detection systems shall be fitted in all areas through which ammonia is piped. (3-30-07)iii.
- Special vacuum breaker/regulator provisions must be made to avoid potentially violent results of iv. backflow of water into cylinders or storage tanks. (3-30-07)
- Consideration shall be given to the provision of an emergency gas scrubber capable of absorbing the entire contents of the largest ammonia storage unit whenever there is a risk to the public as a result of potential ammonia leaks. (3-30-07)
- Operator Safety. The Idaho General Safety and Health Standards, referenced in Subsection 002.02, may be used as guidance in designing facilities to ensure the safety of operators. The following requirements are in addition to the requirements of Subsection 501.12. (3-30-07)
- Respiratory protection equipment, meeting the requirements of the National Institute for Occupational Safety and Health (NIOSH) shall be available where chlorine gas is handled, and shall be stored at a convenient heated location, but not inside any room where chlorine is used or stored. The units shall use compressed air, have at least a thirty (30) minute capacity, and be compatible with or exactly the same as units used by the fire department responsible for the plant. (3-30-07)
- Chlorine leak detection. A bottle of concentrated ammonium hydroxide (fifty-six (56) per cent ammonia solution) shall be available for chlorine leak detection. Where ton containers are used, a leak repair kit approved by the Chlorine Institute shall be provided. (3-30-07)
  - Protective equipment.

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

## Docket No. 58-0108-0801 Proposed Rulemaking

- i. At least one pair of rubber gloves, a dust respirator of a type certified by NIOSH for toxic dusts, an apron or other protective clothing, and goggles or face mask shall be provided for each operator. (3-30-07)
- ii. A deluge shower and eyewashing device shall be installed where strong acids and alkalis are used or stored. A water holding tank that will allow water to come to room temperature shall be installed in the water line feeding the deluge shower and eyewashing device. Other methods of water tempering will be considered on an individual basis.

  (3-30-07)(\_\_\_\_\_)
- iii. A water holding tank that will allow water to come to room temperature shall be installed in the water line feeding the deluge shower and eyewashing device. Other methods of water tempering will be considered on an individual basis. For chemicals other than strong acids and alkalis, an appropriate eye washing device or station shall be provided.

  (3-30-07)(\_\_\_\_\_\_)
  - iv. Other protective equipment shall be provided as necessary. (3-30-07)
- **06. Design Requirements for Specific Applications.** <u>In addition to Subsection 531.01 through 531.03, the following design requirements apply for the specific applications within Subsection 531.06 of this rule. (3-30-07)(\_\_\_\_\_\_)</u>
- a. Sodium chlorite for chlorine dioxide generation. Positive displacement feeders shall be provided. Tubing for conveying sodium chlorite or chlorine dioxide solutions shall be Type 1 PVC, polyethylene or materials recommended by the manufacturer. Chemical feeders may be installed in chlorine rooms if sufficient space is provided. Otherwise, facilities meeting the requirements of chlorine rooms shall be provided. Feed lines shall be installed in a manner to prevent formation of gas pockets and shall terminate at a point of positive pressure. Check valves shall be provided to prevent the backflow of chlorine into the sodium chlorite line. (3-30-07)
  - **b.** Sodium hHypochlorite facilities shall meet the following requirements: (3-30-07)(
- i. <u>Sodium hHy</u>pochlorite shall be stored in the original shipping containers or in sodium hypochlorite compatible containers. Storage containers or tanks shall be sited out of the sunlight in a cool and ventilated area.

  (3-30-07)(
- ii. Stored hypochlorite shall be pumped undiluted to the point of addition. Where dilution is unavoidable, deionized or softened water shall be used. (3-30-07)
- iii. Storage areas, tanks, and pipe work shall be designed to avoid the possibility of uncontrolled discharges and a sufficient amount of appropriately selected spill absorbent shall be stored on-site. (3-30-07)
- iv. Sodium h $\underline{H}$ ypochlorite feeders shall be positive displacement pumps with compatible materials for wetted surfaces. (3-30-07)(
- v. To avoid air locking in smaller installations, small diameter suction lines shall be used with foot valves and degassing pump heads. In larger installations flooded suction shall be used with pipe work arranged to ease escape of gas bubbles. Calibration tubes or mass flow monitors which allow for direct physical checking of actual feed rates shall be fitted.

  (3-30-07)
  - vi. Injectors shall be made removable for regular cleaning where hard water is to be treated. (3-30-07)
- **c.** When ammonium sulfate is used, the tank and dosing equipment contact surfaces shall be made of corrosion resistant non-metallic materials. Provision shall be made for removal of the agitator after dissolving the solid. The tank shall be fitted with a lid and vented outdoors. Injection of the solution should take place in the center of treated water flow at a location where there is high velocity movement. (3-30-07)
- **d.** When aqua ammonia (ammonium hydroxide) is used, the feed pumps and storage shall be enclosed and separated from other operating areas. The aqua ammonia room shall be equipped as required for chlorinator rooms with the following changes: (3-30-07)

- i. A corrosion resistant, closed, unpressurized tank shall be used for bulk storage, vented through an inert liquid trap to a high point outside and an incompatible connector, or lockout provisions shall be made to prevent accidental addition of other chemicals to the storage tank. (3-30-07)
- ii. The storage tank shall be *fitted either with cooling/refrigeration and/or with provision without* opening the system to dilute and mix the contents with water designed to avoid conditions where temperature increases cause the ammonia vapor pressure over the aqua ammonia to exceed atmospheric pressure. This capability can be provided by cooling/refrigeration or diluting or mixing the contents with water without opening the system.

  (3-30-07)(
- iii. The aqua ammonia shall be conveyed direct from storage to the treated water stream injector without the use of a carrier water stream unless the carrier stream is softened. (3-30-07)
  - iv. The point of delivery to the main water stream shall be placed in a region of turbulent water flow.
    (3-30-07)
  - v. Provisions shall be made for easy access for removal of calcium scale deposits from the injector.
    (3-30-07)

# (BREAK IN CONTINUITY OF SECTIONS)

# 533. FACILITY AND DESIGN STANDARDS: DESIGN STANDARDS FOR TASTE AND ODOR CONTROL.

Provision shall be made for the control of taste and odor. Chemicals shall be added sufficiently ahead of other treatment processes to assure adequate contact time for an effective and economical use of the chemicals. Where severe taste and odor problems are encountered, in-plant and pilot plant studies, or both in-plant and pilot plant studies may be required.

(3-30-07)(\_\_\_\_)

- **01. Chlorination**. When using chlorination as a method of taste and odor control adequate contact time must be provided to complete the chemical reactions involved. (3-30-07)
- **02. Chlorine Dioxide**. Provisions shall be made for proper storing and handling of the sodium chlorite, so as to eliminate any danger of explosion. (3-30-07)

#### **03.** Powdered Activated Carbon. (3-30-07)

- **a.** The carbon can be added as a pre-mixed slurry or by means of a dry-feed machine as long as the carbon is properly wetted. (3-30-07)
- **b.** Continuous agitation or resuspension equipment is necessary to keep the carbon from depositing in the slurry storage tank. (3-30-07)
  - **c.** Provision shall be made for adequate dust control. (3-30-07)
  - **d.** Powdered activated carbon shall be handled as a potentially combustible material. (3-30-07)
- **04. Granular Activated Carbon**. Replacement of anthracite with GAC may be considered as a control measure for geosmin and methyl isoborneol (MIB) taste and odors from algae blooms in surface water applications. Demonstration studies are required by the Department. (3-30-07)
- **05. Copper Sulfate and Other Copper Compounds**. Continuous or periodic treatment of surface water with copper compounds to kill algae or other growths shall be controlled to prevent copper in excess of one point zero (1.0) milligrams per liter as copper in the plant effluent or distribution system. Care shall be taken to assure an even distribution of the chemical within the treatment area. (3-30-07)

- **96. Potassium Permanganate**. Application of potassium permanganate may be considered, providing the treatment shall be designed so that the products of the reaction are not visible in the finished water. (3-30-07)
- **07. Ozone**. Ozonation may be used as a means of taste and odor control. Adequate contact time must be provided to complete the chemical reactions involved. (3-30-07)
- **08. Other Methods**. Other methods of taste and odor control shall be made only after pilot plant tests and approval of the Department. (3-30-07)

#### 534. FACILITY AND DESIGN STANDARDS: AERATION PROCESSES.

Public water systems that install aeration treatment are subject to the Rules of the Department of Environmental Quality, IDAPA 58.01.01, "Rules for the Control of Air Pollution in Idaho." The system owner or the design engineer shall contact one of the Department's regional offices for information on obtaining a permit or an exemption for the emissions resulting from the aeration process. General information may be found at http://www.deq.idaho.gov/air/prog\_issues/toxics/overview.cfm#tap. (3-30-07)

- **01.** Natural Draft Aeration. Design shall provide: (3-30-07)
- a. Perforations in the distribution pan three sixteenths to one-half  $(3/16 \frac{1}{2})$  inches in diameter, spaced one to three (1-3) inches on centers to maintain a six (6) inch water depth. (3-30-07)
  - **b.** For distribution of water uniformly over the top tray. (3-30-07)
- c. Discharge through a series of three (3) or more trays with separation of trays not less than twelve (3-30-07)
  - **d.** Loading at a rate of one to five (1-5) gallons per minute for each square foot of total tray area. (3-30-07)
  - e. Trays with slotted, heavy wire (1/2 inch openings) mesh or perforated bottoms. (3-30-07)
  - **f.** Construction of durable material resistant to aggressiveness of the water and dissolved gases. (3-30-07)
  - g. Protection from insects by twenty-four (24) mesh screen. (3-30-07)
  - **02. Forced or Induced Draft Aeration**. Devices shall be designed to: (3-30-07)
  - **a.** Include a blower with a weatherproof motor in a tight housing and screened enclosure. (3-30-07)
  - **b.** Ensure adequate counter current of air through the enclosed aerator column. (3-30-07)
  - **c.** Exhaust air directly to the outside atmosphere. (3-30-07)
  - **d.** Include a down-turned and twenty-four (24) mesh screened air outlet and inlet. (3-30-07)
- e. Be such that air introduced in the column shall be as free from obnoxious fumes, dust, and dirt as possible. (3-30-07)
- **f.** Be such that sections of the aerator can be easily reached or removed for maintenance of the interior or installed in a separate aerator room. (3-30-07)
- **g.** Provide loading at a rate of one to five (1-5) gallons per minute for each square foot of total tray area. (3-30-07)
  - **h.** Ensure that the water outlet is adequately sealed to prevent unwarranted loss of air. (3-30-07)

- i. Discharge through a series of five (5) or more trays with separation of trays not less than six (6) inches or as approved by the Department. (3-30-07)
  - **j.** Provide distribution of water uniformly over the top tray. (3-30-07)
  - **k.** Be of durable material resistant to the aggressiveness of the water and dissolved gases. (3-30-07)
  - **O3.** Spray Aeration. Design shall provide: (3-30-07)
  - a. A hydraulic head of between five (5) and twenty-five (25) feet. (3-30-07)
- **b.** Nozzles, with the size, number, and spacing of the nozzles being dependent on the flowrate, space, and the amount of head available. (3-30-07)
  - **c.** Nozzle diameters in the range of one (1) to one and one-half (1.5) inches to minimize clogging. (3-30-07)
- **d.** An enclosed basin to contain the spray. Any openings for ventilation must be protected with a twenty-four (24) mesh screen. (3-30-07)
- **04. Pressure Aeration**. Pressure aeration may be used for oxidation purposes only if the pilot plant study indicates the method is applicable; it is not acceptable for removal of dissolved gases. Filters following pressure aeration must have adequate exhaust devices for release of air. Pressure aeration devices shall be designed to give thorough mixing of compressed air with water being treated and provide screened and filtered air, free of obnoxious fumes, dust, dirt and other contaminants. (3-30-07)
- **05. Packed Tower Aeration**. Packed tower aeration may be used for the removal of volatile organic chemicals, trihalomethanes, carbon dioxide, and radon. Final design shall be based on the results of pilot studies and be approved by the Department. (3-30-07)
  - a. Process design criteria. (3-30-07)
- i. Justification for the design parameters selected (i.e., height and diameter of unit, air to water ratio, packing depth, surface loading rate, etc.) shall be provided to the Department for review. The pilot study shall evaluate a variety of loading rates and air to water ratios at the peak contaminant concentration. Special consideration shall be given to removal efficiencies when multiple contaminations occur. Where there is considerable past performance data on the contaminant to be treated and there is a concentration level similar to previous projects, the Department may approve the process design based on use of appropriate calculations without pilot testing. (3-30-07)
- ii. The tower shall be designed to reduce contaminants to below the maximum contaminant level and to the lowest practical level. (3-30-07)
- iii. The type and size of the packing used in the full scale unit shall be the same as that used in the pilot study. (3-30-07)
  - iv. The maximum air to water ratio for which credit will be given is 80:1. (3-30-07)
- v. The design shall consider potential fouling problems from calcium carbonate and iron precipitation and from bacterial growth. It may be necessary to provide pretreatment. Disinfection capability shall be provided prior to and after packed tower aeration. (3-30-07)
  - vi. The effects of temperature shall be considered. (3-30-07)
  - vii. Redundant packed tower aeration capacity at the design flowrate shall be provided. (3-30-07)
  - **b.** The tower may be constructed of stainless steel, concrete, aluminum, fiberglass or plastic.

Uncoated carbon steel is not allowed. Towers constructed of light-weight materials shall be provided with adequate support to prevent damage from wind. Packing materials shall be resistant to the aggressiveness of the water, dissolved gases and cleaning materials and shall be suitable for contact with potable water. (3-30-07)

- **c.** Water flow system. (3-30-07)
- i. Water shall be distributed uniformly at the top of the tower using spray nozzles or orifice-type distributor trays that prevent short circuiting. (3-30-07)
  - ii. A mist eliminator shall be provided above the water distributor system. (3-30-07)
- iii. A side wiper redistribution ring shall be provided at least every ten (10) feet in order to prevent water channeling along the tower wall and short circuiting. (3-30-07)
- iv. Sample taps shall be provided in the influent and effluent piping. The sample taps shall satisfy the requirements of Subsection 501.09.
- v. The effluent sump, if provided, shall have easy access for cleaning purposes and be equipped with a drain valve. The drain shall not be connected directly to any storm or sanitary sewer. (3-30-07)
- vi. The design shall prevent freezing of the influent riser and effluent piping when the unit is not operating. (3-30-07)
  - vii. The water flow to each tower shall be metered. (3-30-07)
- viii. An overflow line shall be provided which discharges twelve (12) to fourteen (14) inches above a splash pad or drainage inlet. Proper drainage shall be provided to prevent flooding of the area. (3-30-07)
  - ix. Means shall be provided to prevent flooding of the air blower. (3-30-07)
  - **d.** Air flow system. (3-30-07)
- i. The air inlet to the blower and the tower discharge vent shall be down-turned and protected with a non-corrodible twenty-four (24) mesh screen to prevent contamination from extraneous matter. (3-30-07)
  - ii. The air inlet shall be in a protected location. (3-30-07)
- iii. An air flow meter shall be provided on the influent air line or an alternative method to determine the air flow shall be provided. (3-30-07)
- iv. A positive air flow sensing device and a pressure gauge must be installed on the air influent line. The positive air flow sensing device must be a part of an automatic control system which will turn off the influent water if positive air flow is not detected. The pressure gauge will serve as an indicator of fouling buildup. (3-30-07)
  - v. A backup motor for the air blower must be readily available. (3-30-07)
  - e. Other features that shall be provided: (3-30-07)
- i. A sufficient number of access ports with a minimum diameter of twenty-four (24) inches to facilitate inspection, media replacement, media cleaning and maintenance of the interior. (3-30-07)
- ii. A method of cleaning the packing material when iron, manganese, or calcium carbonate fouling may occur. (3-30-07)
  - iii. Tower effluent collection and pumping wells constructed to clearwell standards. (3-30-07)
  - iv. Provisions for extending the tower height without major reconstruction. (3-30-07)

- v. No bypass shall be provided unless specifically approved by the Department. (3-30-07)
- vi. Disinfection and adequate contact time after the water has passed through the tower and prior to the distribution system. (3-30-07)
- vii. Adequate packing support to allow free flow of water and to prevent deformation with deep packing heights. (3-30-07)
  - viii. Operation of the blower and disinfectant feeder equipment during power failures. (3-30-07)
- ix. Adequate foundation to support the tower and lateral support to prevent overturning due to wind loading. (3-30-07)
  - x. Fencing and locking gate to prevent vandalism. (3-30-07)
- xi. An access ladder with safety cage for inspection of the aerator including the exhaust port and demister. (3-30-07)
  - xii. Electrical interconnection between blower, disinfectant feeder and supply pump. (3-30-07)
- **06. Other Methods of Aeration.** Other methods of aeration may be used if applicable to the treatment needs. Such methods include but are not restricted to spraying, diffused air, cascades and mechanical aeration. The treatment processes are subject to the approval of the Department. (3-30-07)
- **07. Protection of Aerators**. All aerators except those discharging to lime softening or clarification plants shall be protected from contamination by birds, insects, wind borne debris, rainfall and water draining off the exterior of the aerator. (3-30-07)
- **08. Disinfection**. Ground water supplies exposed to the atmosphere by aeration must receive disinfection as the minimum additional treatment. (3-30-07)

# 535. FACILITY AND DESIGN STANDARDS: DESIGN STANDARDS FOR IRON AND MANGANESE CONTROL SYSTEMS.

Iron and manganese control, as used herein, refers solely to treatment processes designed specifically for this purpose. The treatment process used will depend upon the character of the raw water. The selection of one (1) or more treatment processes must meet specific local conditions as determined by engineering investigations, including chemical analyses of representative samples of water to be treated, and receive the approval of the Department. The Department may require a pilot plant study in order to gather all information pertinent to the design. (3-30-07)

#### 01. Removal by Oxidation, Detention and Filtration.

(3-30-07)

**a.** Oxidation may be by aeration or by chemical oxidation with chlorine, potassium permanganate, ozone or chlorine dioxide. (3-30-07)

#### **b.** Detention time: (3-30-07)

- i. A minimum detention time of thirty (30) minutes shall be provided following aeration to ensure that the oxidation reactions are as complete as possible. This minimum detention may be omitted only where a pilot plant study indicates no need for detention. The detention basin may be designed as a holding tank without provisions for sludge collection but with sufficient baffling to prevent short circuiting. (3-30-07)
- ii. Sedimentation basins shall be provided when treating water with high iron *and/*or manganese content, or where chemical coagulation is used to reduce the load on the filters. Provisions for sludge removal shall be made.

  (3-30-07)(
  - **c.** Filtration. Rapid rate pressure filters are normally used for iron and manganese removal. Pressure

filters shall not be used in the filtration of surface or other polluted waters or following lime-soda softening.

(3-30-07)

- i. The rate of filtration shall not exceed three (3) gallons per minute per square foot of filter area except where in-plant testing as approved by the Department has demonstrated satisfactory results at higher rates.

  (3-30-07)
  - ii. The filters shall be designed to provide for: (3-30-07)
  - (1) Loss of head gauges on the inlet and outlet pipes of each battery of filters. (3-30-07)
  - (2) An easily readable meter or flow indicator on each battery of filters. (3-30-07)
- (3) Filtration and backwashing of each filter individually with an arrangement of piping as simple as possible to accomplish these purposes. (3-30-07)
- (4) Minimum side wall shell height of five (5) feet. A corresponding reduction in side wall height is acceptable where proprietary bottoms permit reduction of the gravel depth. (3-30-07)
- (5) The top of the wash water collectors to be at least eighteen (18) inches above the surface of the media, (3-30-07)
- (6) The underdrain system to efficiently collect the filtered water and to uniformly distribute the backwash water at a rate not less than fifteen (15) gallons per minute per square foot of filter area. (3-30-07)
  - (7) Backwash flow indicators and controls that are easily readable while operating the control valves. (3-30-07)
  - (8) An air release valve on the highest point of each filter. (3-30-07)
- (9) An accessible manhole to facilitate inspection and repairs for filters thirty-six (36) inches or more in diameter. Sufficient handholds shall be provided for filters less than thirty-six (36) inches in diameter. (3-30-07)
- (10) A means to observe the wastewater during backwashing and construction to prevent cross connection. (3-30-07)
- **02. Removal by Manganese Coated Media Filtration**. This process consists of a continuous or batch feed of potassium permanganate to the influent of a manganese coated media filter. (3-30-07)
- **a.** Other oxidizing agents or processes such as chlorination or aeration may be used prior to the permanganate feed to reduce the cost of the chemical. (3-30-07)
- **b.** An anthracite media cap of at least six (6) inches or more as required by the Department shall be provided over manganese coated media. (3-30-07)
  - **c.** Normal filtration rate shall be three (3) gallons per minute per square foot. (3-30-07)
- **d.** Normal wash rate shall be eight (8) to ten (10) gallons per minute per square foot with manganese greensand and fifteen (15) to twenty (20) gallons per minute with manganese coated media. (3-30-07)
- e. Sample taps shall be provided prior to application of permanganate, immediately ahead of filtration, at points between the anthracite media, and at the filter effluent. The sample taps shall satisfy the requirements of Subsection 501.09.
- **03. Removal by Ion Exchange**. This process is not acceptable where either the raw water or wash water contains dissolved oxygen or other oxidants. (3-30-07)

- **04. Biological Removal.** Biofiltration to remove manganese, <u>and/or</u> iron, <u>or a combination of manganese and iron</u> requires on-site piloting testing to establish effectiveness. The final filter design shall be based on the on-site pilot plant studies.

  (3-30-07)(\_\_\_\_\_)
- **05. Sequestration by Polyphosphates.** This process shall not be used when iron, manganese or a combination thereof exceeds one point zero (1.0) mg/l. The total phosphate applied shall not exceed ten (10) mg/l as PO<sub>4</sub>. Where phosphate treatment is used, satisfactory chlorine residuals shall be maintained in the distribution system. Possible adverse affects on corrosion must be addressed when phosphate addition is proposed for iron sequestering. (3-30-07)
- **a.** Stock phosphate solution must be kept covered and disinfected by carrying approximately ten (10) mg/l free chlorine residual unless the phosphate is not able to support bacterial growth and the phosphate is being fed from the covered shipping container. Phosphate solutions having a pH of two point zero (2.0) or less may also be exempted from this requirement by the Department. (3-30-07)
- **b.** Polyphosphates shall not be applied ahead of iron and manganese removal treatment. The point of application shall be prior to any aeration, oxidation or disinfection if no iron or manganese removal treatment is provided. (3-30-07)
- **06. Sequestration by Sodium Silicates.** Sodium silicate sequestration of iron and manganese is allowed only for ground water supplies prior to air contact. On-site pilot tests are required to determine the suitability of sodium silicate for the particular water and the minimum feed needed. Rapid oxidation of the metal ions such as by chlorine or chlorine dioxide must accompany or closely precede the sodium silicate addition. (3-30-07)
- **a.** Sodium silicate addition is applicable to waters containing up to two (2) mg/l of iron, manganese or combination thereof. (3-30-07)
- **b.** Chlorine residuals shall be maintained throughout the distribution system to prevent biological breakdown of the sequestered iron. (3-30-07)
- c. The amount of silicate added shall be limited to twenty (20) mg/l as  $SiO_2$ , but the amount of added and naturally occurring silicate shall not exceed sixty (60) mg/l as  $SiO_2$ . (3-30-07)
  - **d.** Sodium silicate shall not be applied ahead of iron or manganese removal treatment. (3-30-07)
- **O7. Sampling Taps**. Smooth-nosed sampling taps shall be provided for control purposes. Taps shall be located on each raw water source, each treatment unit influent and each treatment unit effluent. The sample taps shall satisfy the requirements of Subsection 501.09.

# (BREAK IN CONTINUITY OF SECTIONS)

#### 537. FACILITY AND DESIGN STANDARDS: DESIGN STANDARDS FOR STABILIZATION.

Water that is unstable due either to natural causes or to subsequent treatment shall be stabilized. The expected treated water quality shall be evaluated to determine what, if any, treatment is necessary. (3-30-07)

01.	Carbon Dioxide Addition.	(3-30-07)
a.	Recarbonation basin design shall provide the following:	(3-30-07)
i.	A total detention time of twenty (20) minutes.	(3-30-07)
ii.	A mixing compartment having a detention time of at least three (3) minutes.	(3-30-07)
iii.	A reaction compartment.	(3-30-07)

- iv. The mixing and reaction compartments shall have a depth sufficient to provide a diffuser submergence of not less than seven and one half (7.5) feet and no greater than the manufacturer's recommendation.

  (3-30-07)
- **b.** Where liquid carbon dioxide is used, adequate precautions must be taken to prevent carbon dioxide from entering the plant from the recarbonation process. (3-30-07)
- **c.** Recarbonation tanks shall be located outside or be sealed and vented to the outside with adequate seals and adequate purge flow of air to ensure workers safety. (3-30-07)
  - **d.** Provisions shall be made for draining the recarbonation basin and removing sludge. (3-30-07)
- **O2. Phosphates.** The feeding of phosphates may be used for sequestering calcium, for corrosion control, and in conjunction with alkali feed following ion exchange softening. (3-30-07)
- **a.** Stock phosphate solution must be kept covered and disinfected by carrying approximately ten (10) mg/l free chlorine residual unless the phosphate is not able to support bacterial growth and the phosphate is being fed from the covered shipping container. Phosphate solutions having a pH of two point zero (2.0) or less are exempted from this requirement. (3-30-07)
- **b.** Satisfactory chlorine residuals shall be maintained in the distribution system when phosphates are used. (3-30-07)
- **O3. Split Treatment**. Raw water may be blended with lime-softened water to partially stabilize the water prior to secondary clarification and filtration. Treatment plants designed to utilize split treatment shall also contain facilities for further stabilization by other methods. (3-30-07)
- **04. Water Unstable Due to Biochemical Action in Distribution System.** Unstable water resulting from the bacterial decomposition of organic matter in water (especially in dead end mains), the biochemical action within tubercles, and the reduction of sulfates to sulfides shall be prevented by the maintenance of a free and/or combined chlorine residual throughout the distribution system.

### 538. – 539. (RESERVED).

# 540. FACILITY AND DESIGN STANDARDS: DESIGN STANDARDS FOR TREATMENT AND DISPOSAL OF WASTE RESIDUALS.

Provisions must be made for proper disposal of water treatment plant waste such as sanitary, laboratory, clarification sludge, softening sludge, iron sludge, filter backwash water, and liquid concentrates. In locating waste disposal facilities, due consideration shall be given to preventing potential contamination of the water supply. (3-30-07)

**01. Sanitary Waste**. The sanitary waste from water treatment plants, pumping stations, and other waterworks installations must receive treatment. Waste from these facilities shall be discharged directly to a sanitary sewer system, when available and feasible, or to an adequate on-site waste treatment facility approved under the provisions of IDAPA 58.01.03, "Individual/Subsurface Sewage Disposal Rules." (3-30-07)

# **02.** Liquid Concentrates.

- **a.** Waste from ion exchange plants, demineralization plants, reverse osmosis, or other plants which produce liquid concentrates may be disposed of by the following methods: (3-30-07)
- i. Liquid concentrates that contain radionuclides must be further treated to remove the radioactive constituents as sludge. See Subsection 540.03.e. for disposal requirements for sludge that contains radionuclides. The residual liquids from which radionuclides have been removed may be disposed of in accordance with Subsections 540.02.a.ii. through 540.02.a.v. (3-30-07)
  - ii. Controlled discharge to a stream or other receiving water body if adequate dilution is available.

Such discharge will require a National Pollution Elimination System Permit from the U.S. Environmental Protection Agency, Region 10, 1200 Sixth Avenue, Seattle, WA 98101, Telephone (206) 553-1200. (3-30-07)

- iii. Liquid concentrates may be discharged to a sanitary sewer, if available and feasible. Acceptance of such waste must be approved by the sewer authority. (3-30-07)
- iv. Subsurface disposal or land application of liquid concentrates may be permitted, but only if such discharge meets the requirements of the IDAPA 58.01.03, "Individual/Subsurface Sewage Disposal Rules" for subsurface disposal and/or the requirements of IDAPA 58.01.17, "Rules for the Reclamation and Reuse of Municipal and Industrial Wastewater" for land application.

  (3-30-07)(\_\_\_\_)
- v. Liquid concentrates may be discharged to an injection well if in accordance with Rules of the Idaho Water Resources Board, IDAPA 37.03.03 "Rules and Minimum Standards for the Construction and Use of Injection Wells," referenced in Subsection 002.02. (3-30-07)
- **b.** Should the nature of the liquid concentrate cause it to be ineligible for permitted discharge as described in Subsection 540.02.a., further onsite treatment of the liquid concentrate may be required in order to produce sludge and liquid waste that will meet the permit criteria for one (1) or more of the disposal options.

(3-30-07)

- **O3. Sludge Waste.** Sludge is the solid waste resulting from coagulation, precipitation, or passive settling of liquid concentrates. Depending on composition, liquids remaining after sludge removal may be disposed of by methods described in Subsection 540.02, recycled through the treatment plant, or may be pure enough to be unregulated. The following methods of treatment and disposal apply to sludge: (3-30-07)
  - **a.** Precipitative Softening Sludge.

(3-30-07)

- i. At least two (2) temporary storage lagoons must be provided in order to give flexibility in operation. Provisions must be made for convenient cleaning. An acceptable means of final sludge disposal must be provided. (3-30-07)
- ii. Liquid or dewatered precipitative softening sludge may be applied to farm land if heavy metals or other contaminants do not exceed the requirements of IDAPA 58.01.02, "Water Quality Standards." (3-30-07)
- iii. Dewatered precipitative softening sludge may be disposed of in a sanitary landfill in accordance with the requirements of IDAPA 58.01.06, "Solid Waste Management Rules." Acceptance of such waste is at the discretion of the landfill authority. (3-30-07)
  - **b.** Alum or Ferric Sludge.

- i. Temporary storage lagoons must contain at least two (2) compartments to facilitate independent filling and dewatering operations. Mechanical concentration may be considered. If mechanical dewatering is used, it shall be preceded by sludge concentration and chemical pre-treatment. A pilot plant study is required before the design of a mechanical dewatering installation. (3-30-07)
- ii. Alum or ferric sludge may be discharged to a sanitary sewer if available and feasible. Acceptance of such waste must be approved by the sewer authority. (3-30-07)
- iii. Dewatered alum or ferric sludge may be disposed of in a sanitary landfill in accordance with the requirements of IDAPA 58.01.06, "Solid Waste Management Rules." Acceptance of such waste is at the discretion of the landfill authority. (3-30-07)
- iv. Alum or ferric sludge may be disposed of by land application if the permitting requirements of IDAPA 58.01.02, "Water Quality Standards," and IDAPA 58.01.17, "Rules for the Reclamation and Reuse of Municipal and Industrial Wastewater," are met. (3-30-07)
  - v. Water removed from alum or ferric sludge may be disposed of in the same manner as liquid

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

Docket No. 58-0108-0801 Proposed Rulemaking

concentrates, as described in Subsection 540.02.

(3-30-07)

- **c.** Red Water. Red water is the waste filter wash water from iron and manganese removal plants. (3-30-07)
- i. If sand filters are used they shall have the following features:
- (1) Total filter area shall be sufficient to adequately dewater applied solids. Unless the filter is small enough to be cleaned and returned to service in one (1) day, two (2) or more cells are required. (3-30-07)
- (2) The "red water" filter shall have sufficient capacity to contain, above the level of the sand, the entire volume of wash water produced by washing all of the production filters in the plant, unless the production filters are washed on a rotating schedule and the flow through the production filters is regulated by true rate of flow controllers. Then sufficient volume shall be provided to properly dispose of the wash water involved. (3-30-07)
- (3) Where freezing is a problem, provisions should be made for covering the filters during the winter months. (3-30-07)
  - (4) "Red water" filters shall not have common walls with finished water. (3-30-07)
- ii. Subsurface infiltration lagoons may be permitted, but only if such discharge meets the requirements of IDAPA 58.01.03, "Individual/Subsurface Sewage Disposal Rules." (3-30-07)
- iii. "Red water" may be discharged to a sanitary sewer if available and feasible. Acceptance of such waste must be approved by the sewer authority. Design shall prevent cross connections and there shall be no common walls between potable and non-potable water. (3-30-07)
  - **d.** Filter Backwash Water. (3-30-07)
- i. Recycling is permitted if the backwash waters are returned to the head of the treatment plant or another entry point if supported by engineering studies. Backwash water shall be held for a sufficient time prior to recycling to allow solids to settle out. (3-30-07)
- ii. Dewatered sludge from backwash water clarification processes may be disposed of in a sanitary landfill in accordance with the requirements of IDAPA 58.01.06, "Solid Waste Management Rules." Acceptance of such waste must be approved by the landfill authority. (3-30-07)
- e. Radioactive Sludge. Waste residuals containing radioactive substances, including, but not limited to granular activated carbon used for radon removal or ion-exchange regeneration waste from uranium removal, must be disposed of in accordance with IDAPA 58.01.10, "Rules Regulating the Disposal of Radioactive Materials Not Regulated Under The Atomic Energy Act of 1954, As Amended." (3-30-07)
- i. The buildup of radioactive materials such as uranium or radon and its decay products shall be considered and adequate shielding and safeguards shall be provided for operators and visitors. (3-30-07)
- ii. Waste residuals containing naturally occurring radioactive materials that have been concentrated by human activities must be disposed of in an approved hazardous waste landfill (Class D), in accordance with the IDAPA 58.01.10, "Rules Regulating the Disposal of Radioactive Materials not Regulated Under the Atomic Energy Act of 1954, as Amended," and IDAPA 58.01.06, "Solid Waste Management Rules." (3-30-07)
- iii. Waste residuals containing greater than point zero five (.05) percent by weight of uranium are subject to licensing and disposal under the regulations of the U.S. Nuclear Regulatory Commission, Region IV, 611 Ryan Plaza Drive, Suite 400, Arlington, TX 76011, Phone 817-860-8299. (3-30-07)
- **f.** Arsenic Sludge. Solid waste residuals containing arsenic at a concentration less than five (5) mg/l may be disposed of at a sanitary landfill if permitted under IDAPA 58.01.06, "Solid Waste Management Rules." Solid waste containing arsenic at a concentration greater than five (5) mg/l must be disposed of at an approved hazardous

waste landfill. Liquid wastes generated by arsenic treatment processes are subject to the handling and disposal requirements for liquid concentrates, as discussed under Subsection 540.02. (3-30-07)

**O4. Spent Media**. Exhausted ion exchange media, adsorption media, disposable filters, and other components of treatment processes that contain concentrated contaminants shall be disposed of in accordance with IDAPA 58.01.06, "Solid Waste Management Rules," and/or IDAPA 58.01.10, "Rules Regulating the Disposal of Radioactive Materials not Regulated Under the Atomic Energy Act of 1954, as Amended." (3-30-07)

#### 541. FACILITY AND DESIGN STANDARDS - PUMPING FACILITIES.

Pumping facilities shall be designed to maintain the sanitary quality of pumped water.

(3-30-07)

- **O1. Pump Houses.** The following requirements apply to pump houses as defined in Section 003 unless it can be shown that some or all of these requirements are not needed to protect the combination of system components in a given structure: (3-30-07)
- **a.** Pump houses shall be readily accessible for operation, maintenance, and repair at all times and under all weather conditions unless permitted to be out of service for a period of inaccessibility. (3-30-07)
- **b.** Pump houses shall be protected from flooding and shall be adequately drained. The ground surface shall be graded so as to lead surface drainage away from the pump house. The floor surface shall be at least six (6) inches above the final ground surface. (3-30-07)
- **c.** Pump houses shall be of durable construction, fire and weather resistant, and with outward-opening doors. All underground structures shall be waterproofed. (3-30-07)
- **d.** Provisions shall be made for adequate heating for the comfort of the operator and the safe and efficient operation of the equipment. In pump houses not occupied by personnel, only enough heat need be provided to prevent freezing of equipment or treatment processes. (3-30-07)
- **e.** Ventilation shall conform to existing local and/or state codes. Adequate ventilation shall be provided for all pumping stations for operator comfort and dissipation of excess heat and moisture from the equipment. In all cases, measures must be taken to minimize corrosion of metallic and electrical components.

- f. Pump houses shall be provided with a locking door or access to prohibit unauthorized entrance and shall be protected to prevent vandalism and entrance by animals. Plans and specifications for pump houses must provide enough detail to enable the reviewing engineer to determine that the facility is secure, safe, accessible, and that it conforms to electrical and plumbing codes. (3-30-07)
- **g.** Pump houses shall be kept clean and in good repair and shall not be used to store toxic or hazardous materials other than those materials required for treatment processes. (3-30-07)
- **h.** A suitable outlet shall be provided for drainage from pump glands without discharging onto the floor. (3-30-07)
- i. Floor drains shall not be connected to sewers, storm drains, chlorination room drains, or any other source of contamination. Sumps for pump house floor drains shall not be closer than thirty (30) feet from any well.

  (3-30-07)
- **j.** Adequate space shall be provided for the <u>installation of potential additional units and for the</u> safe and efficient servicing of all equipment.

  (3-30-07)(\_\_\_\_)
- **k.** Suction basins shall be watertight, have floors sloped to permit removal of water and settled solids, be covered or otherwise protected against contamination, and have two (2) pumping compartments or other means to allow the suction basin to be taken out of service for inspection maintenance or repair. (3-30-07)
  - **l.** Pump houses shall be designed to allow efficient equipment servicing. Crain-ways, hoist beams,

eyebolts, or other adequate facilities for servicing or removal of pumps, motors or other heavy equipment shall be provided. Openings in floors, roofs or wherever else shall be provided as needed for removal of heavy or bulky equipment.

(3-30-07)

- **m.** All remote controlled stations shall be electrically operated and controlled and shall have signaling apparatus of proven performance. Signaling apparatus shall report automatically when the station is out of service.

  (3-30-07)
- **n.** Any threaded hose bib installed in the pump house must be equipped with an appropriate backflow prevention device. (3-30-07)
- **Pumping Units**. At least two (2) pumping units shall be provided for raw water and surface source pumps. Pumps using seals containing mercury shall not be used in public drinking water system facilities. With any pump out of service, the remaining pump or pumps shall be capable of providing the peak hour demand of the system or <u>a minimum of the</u> maximum day demand plus equalization storage. See Subsection 501.178 for general design requirements concerning fire flow capacity <u>and Subsection 501.07 regarding reliability and emergency operation</u>. The pumping units shall meet the following requirements:

  (3 30 07)(\_\_\_\_)
- **a.** The pumps shall have ample capacity to supply the maximum demand against the required pressure without dangerous overloading. (3-30-07)
- **b.** The pumps shall be driven by prime movers able to meet the maximum horsepower condition of the pumps. (3-30-07)
  - **c.** The pumps shall be provided with readily available spare parts and tools. (3-30-07)
- **d.** The pumps shall be served by control equipment that has proper heater and overload protection for air temperature encountered. (3-30-07)
- **e.** Suction lift shall be avoided if possible. When suction lift is used, it shall be within the limits allowed by the manufacturer of the pumps, and provision shall be made for priming the pumps. (3-30-07)
- **f.** Prime water must not be of lesser sanitary quality than that of the water being pumped. Means shall be provided to prevent either backpressure or backsiphonage backflow. When an air-operated ejector is used, the screened intake shall draw clean air from a point at least ten (10) feet above the ground or other source of possible contamination, unless the air is filtered by an apparatus approved by the reviewing authority. Vacuum priming may be used. (3-30-07)
- **O3. Appurtenances**. The following appurtenances shall be provided for all water pumps with the exception of well pumps. The requirements for well pumps are provided in Section 511. (3-30-07)
- a. Pumps shall be adequately valved to permit satisfactory operation, maintenance and repair of the equipment. If foot valves are necessary, they shall have a net valve area of at least two and one-half (2.5) times the area of the suction pipe and they shall be screened. Each pump shall have *a positive acting* an accessible check valve on the discharge side between the pump and the shut-off valve. Surge relief measures shall be designed to minimize hydraulic transients.
- **b.** In general, piping shall be designed so that it will have watertight joints, be protected against surge or water hammer, be provided with suitable restraints where necessary, be designed so that friction losses will be minimized, and not be subject to contamination. Each pump shall have an individual suction line or the suction lines shall be manifolded such that they will ensure similar hydraulic and operating conditions. (3-30-07)
  - **c.** Each pump station shall have a standard pressure gauge on its discharge line and suction line. (3-30-07)
- **d.** Water seals shall not be supplied with water of a lesser sanitary quality than that of the water being pumped. Where pumps are sealed with potable water and are pumping water of lesser sanitary quality, the seal shall:

(3-30-07)

- i. Be provided with either an approved reduced pressure principle backflow preventer or a break tank open to atmospheric pressure, (3-30-07)
- ii. Where a break tank is provided, have an air gap of at least six (6) inches or two (2) pipe diameters, whichever is greater, between the feeder line and the flood rim of the tank. (3-30-07)
- e. Pumps, their prime movers, and accessories shall be controlled in such a manner that they will operate at rated capacity without dangerous overload. Where two (2) or more pumps are installed, provision shall be made for alternation. Provision shall be made to prevent energizing the motor in the event of a backspin cycle. Equipment shall be provided or other arrangements made to prevent surge pressures from activating controls which switch on pumps or activate other equipment outside the normal design cycle of operation. (3-30-07)
- **04. Booster Pumps**. In addition to other applicable requirements in Section 541, booster pumps must comply with the following: (3-30-07)
- a. In-line booster pumps shall maintain an operating pressure that is consistent with the requirements specified in Subsection 552.01, and shall be supplied with an automatic cutoff when intake pressure is less than or equal to five (5) psi. (3-30-07)
- **b.** Booster pumps with a suction line directly connected to any storage reservoirs shall be protected by an automatic cutoff to prevent pump damage and avoid excessive reservoir drawdown. (3-30-07)
- **c.** Each booster pumping station shall contain not less than two (2) pumps with capacities such that peak hour demand, or <u>a minimum of the</u> maximum day demand plus equalization storage, can be satisfied with *the largest* any pump out of service. See Subsection 501.178 for general design requirements concerning fire flow capacity.

  (3-30-07)(\_\_\_\_\_)

#### 542. FACILITY AND DESIGN STANDARDS - DISTRIBUTION SYSTEM.


- **01. Protection from Contamination**. The distribution system shall be protected from contamination and be designed to prevent contamination by steam condensate or cooling water from engine jackets or other heat exchange devices. (3-30-07)
- **02. Installation of Water Mains**. Division 400 of "Idaho Standards for Public Works Construction," referenced in Subsection 002.02, may be used as guidance for installation of water mains. In addition, the following provisions shall apply: (3-30-07)
- **a.** Installed pipe shall be pressure tested and leakage tested in accordance with the applicable AWWA Standards, incorporated by reference into these rules at Subsection 002.01. (3-30-07)
- **b.** New, cleaned, and repaired water mains shall be disinfected in accordance with AWWA Standard C651, incorporated by reference into these rules at Subsection 002.01. The specifications shall include detailed procedures for the adequate flushing, disinfection, and microbiological testing of all water mains. (3-30-07)
- c. In areas where aggressive soil conditions are suspected or known to exist, analyses shall be performed to determine the actual agressiveness of the soil. If soils are found to be aggressive, action shall be taken to protect metallic joint restraints and the water main, such as encasement in polyethylene, provision of cathodic protection, or use of corrosion resistant materials. (3-30-07)
- **d.** The Department must approve any interconnection between potable water supplies, taking into account differences in water quality between the two systems. (3-30-07)
- **e.** A continuous and uniform bedding shall be provided in the trench for all buried pipe. Backfill material shall be tamped in layers around the pipe and to a sufficient height above the pipe to adequately support and protect the pipe. Stones found in the trench shall be removed for a depth of at least six (6) inches below the bottom of

the pipe. (3-30-07)

- **f.** Water mains shall be covered with sufficient earth or other insulation to prevent freezing. (3-30-07)
- **g.** All tees, bends, plugs and hydrants shall be provided with reaction blocking, tie rods or joints designed to prevent movement. (3-30-07)
- **O3. Pressure Relief Valves**. All pumps connected directly to the distribution system shall be designed in conjunction with a water pressure relief valve of type, size, and material approved by the Department unless the Department approves another method that will prevent excessive pressure development. (3-30-07)
- **94. Flow Meter Required.** All source pumps and booster pumps connected directly to the distribution system shall have an instantaneous and totalizing flow meter, installed in accordance with manufacture's specifications, unless deemed unnecessary by the Department in a particular application. The Department may require larger water systems to provide a means of automatically recording the total water pumped. (3-30-07)
- **05. Pipe and Jointing Materials.** Pipe and jointing materials comply with the standards set forth in Subsection 501.01. Pipe shall be manufactured of materials resistant internally and externally to corrosion and not imparting tastes, odors, color, or any contaminant into the system. Where distribution systems are installed in areas of ground water contaminated by organic compounds:

  (3-30-07)
- **a.** Pipe and joint materials which do not allow permeation of the organic compounds shall be used; and (4-11-06)
- **b.** Non-permeable materials shall be used for all portions of the system including pipe, joint materials, hydrant leads, and service connections. (4-11-06)
- **O6. Size of Water Mains.** When fire hydrants are provided, they shall not be connected to water mains smaller than six (6) inches in diameter, and fire hydrants shall not be installed unless fireflow volumes are available. If fire flow is not provided, water mains shall be no less than three (3) inches in diameter. Any departure from this minimum standard shall be supported by hydraulic analysis and detailed projections of water use. (3-30-07)
- **O7. Separation of Potable and Non-Potable Pipelines.** The relation between potable and non-potable *water* pipelines shall be as *follows:* described in Subsections 542.07.a. through 542.07.c. The Department will use the Memorandum of Understanding with the Plumbing Bureau as guidance in determining the relative responsibilities for reviewing service lines. The conditions of Subsections 542.07.a. and 542.07.b. shall apply to all potable services constructed or reconstructed after April 15, 2007 and where the Department or the QLPE is the reviewing authority.

  (3.30-07)(1.50)
  - a. Non-potable mains in relation to potable mains Parallel installation requirements. (3-30-07)(\_\_\_\_\_)
  - i. Parallel installation requirements: Potable mains in relation to non-potable mains. (4-11-06)(
- (1) Greater than ten (10) feet separation: no *conditions* <u>additional requirements based on separation</u> <u>(4-II-06)(</u>
- (2) Ten (10) feet to six (6) feet separation: separate trenches, with potable main above non-potable main, and non-potable main to be constructed with potable water class pipe.
- (3) Less than six (6) feet separation: design engineer to submit data to the Department for review and approval showing that this installation will protect public health and the environment and non-potable main to be constructed of potable water class pipe. (4-11-06)
  - (4) Non-potable mains are prohibited from being located in the same trench as potable mains. (3-30-07)
  - (5) Pressure sewage mains shall be no closer horizontally than ten (10) feet from potable mains.



non-potable pipeline; and either:

(2a)

service: non potable service or main constructed with potable water class pipe and non potable joint as far as possible from crossing, or sleeve non-potable service or main with potable water class pipe for ten (10) feet either

Less than eighteen (18) inches vertical separation or potable service or main below non-potable

<del>(3 30 07)</del>(

side of crossing. Use of concrete slurry encasement is not allowed as a substitute for sleeving. Non-potable pipeline constructed with potable water class pipe for a minimum of ten (10) feet either side of potable pipeline with a single twenty (20) foot section of potable water class pipe centered on the crossing; or (3-30-07)(\_\_\_\_\_)

- (b) Sleeve non-potable or potable pipeline with potable water class pipe for ten (10) feet either side of crossing. Use of hydraulic cementitious materials such as concrete, controlled density fill, and concrete slurry encasement is not allowed as a substitute for sleeving.
- (2) If potable pipeline is below non-potable pipeline, the non-potable pipeline must also be supported through the crossing to prevent settling.
  - iv. Pressure sewage mains shall be no closer vertically than eighteen (18) inches from potable mains.
- c. Existing potable services in relation to new non-potable mains, and existing non-potable services in relation to new potable mains, and existing potable services in relation to new non-potable services shall meet the requirements of Subsection 542.07.b., where practical, based on cost, construction factors, and public health significance. If the Department determines that there are significant health concerns with these services, such as where a large existing service serves an apartment building or a shopping center, then the design shall conform with Subsection 542.07.b.

  (3 30 07)(
- **08.** Separation from Subsurface Wastewater Systems and Other Sources of Contamination. A minimum horizontal distance of twenty-five (25) feet shall be maintained between any potable water pipe and a septic tank or subsurface wastewater disposal system. Guidance on separation from other potential sources of contamination, such as stormwater facilities, may be found at www.deq.idaho.gov/water/assist\_business/engineers/checklists/guidance\_separation\_distances.pdf. (3-30-07)
- **09. Dead End Mains.** All dead end water mains shall be equipped with a means of flushing and shall be flushed at least semiannually at a water velocity of two and one-half (2.5) feet per second. (3-30-07)
- **a.** Dead ends shall be minimized by making appropriate tie-ins whenever practical in order to provide increased reliability of service and reduce head loss. (4-11-06)
  - **b.** No water main flushing device shall be directly connected to any sewer. (4-11-06)
- **10. Repair of Leaks**. Leaking water mains shall be repaired or replaced upon discovery and disinfected in accordance with American Water Works Association (AWWA) Standards, incorporated by reference into these rules at Subsection 002.01. (3-30-07)
- 11. Separation from Structures. Water mains shall be separated by at least five (5) feet from buildings, industrial facilities, and other permanent structures. (3-30-07)
- 12. Meter Vault Required. All new public water systems shall include a meter vault at each service connection. A lockable shut-off valve shall be installed in the meter vault. This requirement shall also apply to extensions of the distribution system of existing public water systems. (3-30-07)
- 13. Minimum Pressure at Building Sites. *All new public water systems that are constructed* Any public water system constructed or undergoing material modification where topographical relief may affect water pressure at the customers' premises shall provide the Department with an analysis which demonstrates that the pressure at each designated building site will be at least forty (40) psi, based on dynamic pressure in the main, as set forth in Subsections 552.01.b.i. and 552.01.b.ii., plus a static compensation from the elevation of the main to the elevation of each building site.

  (3-30-07)(\_\_\_\_)
- **a.** If forty (40) psi cannot be provided at each designated building site, the Department may require that reasonable effort be made to provide notification to existing and potential customers of the expected pressure.

  (5-3-03)

- **b.** The Department will not authorize a service connection at any designated building site where analysis indicates that pressure will be less than twenty (20) psi static pressure (or twenty-six point five (26.5) psi for two (2) story buildings). (5-3-03)
- **14. Isolation Valves**. A sufficient number of valves shall be provided on water mains to minimize inconvenience and sanitary hazards during repairs. (3-30-07)
- <u>15.</u> Air Relief Valves. At high points in water mains where air can accumulate, provisions shall be made to remove the air by means of combination vacuum relief/air release valves. In lieu of combination vacuum relief/air release valves, vacuum relief and air release functions in the pipeline may be adequately handled by approved appurtenances such as fire hydrants.
- a. The open end of an air relief pipe shall be extended to at least one (1) foot above grade and provided with a screened, downward-facing elbow. When an air vent cannot be practically installed above ground, the vent may be below grade provided that the below grade chamber is rated for appropriate traffic loading in traffic areas and the chamber is drained to daylight.
- **b.** <u>Discharge piping from air relief valves shall not connect directly to any storm drain, storm sewer, or sanitary sewer.</u>
- **156. Backflow Protection.** Automatic air relief valves shall be equipped with a means of backflow protection. (3-30-07)
- 167. Surface Water Crossings. For the purposes of Subsection 542.17, surface water is defined as all surface accumulations of water, natural or artificial, public or private, or parts thereof which are wholly or partially within, which flow through or border upon the state. This includes, but is not limited to, rivers, streams, canals, ditches, lakes, and ponds. Surface water crossings, whether over or under water, shall be constructed as follows:

<del>(3-30-07)</del>(

- **a.** Above water crossings: the pipe shall be adequately supported and anchored, protected from damage and freezing, and shall be accessible for repair or replacement. (4-11-06)
- **b.** Under water crossings: A minimum cover of two (2) feet shall be provided over the pipe. When crossing a water course that is greater than fifteen (15) feet in width, the following shall be provided: (4-11-06)
- i. The pipe shall be of special construction, having flexible, restrained, or welded water-tight joints; and (4-11-06)
- ii. Valves shall be provided at both ends of water crossings so that the section can be isolated for testing or repair; the valves shall be easily accessible and not subject to flooding; and (4-11-06)
- iii. Permanent taps or other provisions to allow insertion of a small meter to determine leakage and obtain water samples shall be made on each side of the valve closest to the supply source. (4-11-06)

## 543. FACILITY AND DESIGN STANDARDS - CROSS CONNECTION CONTROL.

There shall be no connection between the distribution system and any pipes, pumps, hydrants, water loading stations, or tanks whereby unsafe water or other contaminating materials may be discharged or drawn into a public water system. The water purveyor is responsible through its cross connection control program to take reasonable and prudent measures to protect the water system against contamination and pollution from cross connections through premise isolation or containment, internal or in-plant isolation, fixture protection, or some combination of premise isolation, internal isolation, and fixture protection.

(3-30-07)(\_\_\_\_\_)

**O1. Double Cheek Valve Testable Assemblies.** If All double check valve backflow prevention assemblies, and pressure principle backflow prevention assemblies, are spill resistant vacuum breakers, and pressure vacuum breakers used, they must pass a performance test conducted by the University of Southern California Foundation for Cross-Connection Control and Hydraulic Research. In addition, they all double check valve backflow prevention assemblies and reduced pressure principle backflow prevention assemblies used shall meet

American Water Works Association (AWWA) Standards C-510 or C-511, incorporated by reference into these rules at Subsection 002.01, or an equivalent standard approved by the Department.

(3 30 07)(\_\_\_\_)

- **O2.** Atmospheric Vacuum Breakers. If All atmospheric vacuum breakers and/or pressure vacuum breakers are used, they shall be marked approved either by the International Association of Plumbing and Mechanical Officials (IAPMO) or by the American Society of Sanitation Engineers (ASSE). Pressure vacuum breakers must pass a performance test conducted by the University of Southern California Foundation for Cross Connection Control and Hydraulic Research.
- **03. Resilient Seated Shutoff Valves.** Resilient seated shutoff valves shall be used when double check valve backflow prevention assemblies, reduced pressure principle backflow prevention assemblies, and pressure vacuum breakers are installed. (3-30-07)
- **O4.** Reference Assembly Selection-Chart. Reference may be made to a selection chart Appropriate and adequate backflow prevention assemblies for various facilities, fixtures, equipment, and uses of water provided in Subsection 900.02 (Table 2) must be selected either from the Pacific Northwest Cross Connection Control Manual, the Uniform Plumbing Code, the Environmental Protection Agency's Cross Connection Control Manual, the USC Manual of Cross Connection Control or other sources deemed acceptable by the Department. The selected assembly must comply with local ordinances.

  (3-30-07)(\_\_\_\_\_)
- 544. FACILITY AND DESIGN STANDARDS: GENERAL DESIGN OF FINISHED WATER STORAGE. The materials and designs used for finished water storage structures shall provide stability and durability as well as protect the quality of the stored water. <u>Finished water storage structures shall be designed to maintain water circulation and prevent water stagnation.</u> Steel structures <u>and facilities</u> such as steel tanks, standpipes, reservoirs, and elevated tanks shall be designed and constructed in accordance with applicable AWWA Standards, incorporated by reference into these rules at Subsection 002.01. Other materials of construction are acceptable when properly designed to meet the requirements of Section 544.
- **O1. Sizing.** Storage facilities shall have sufficient capacity, as determined from engineering studies that consider peak flows, fire flow capacity, and analysis of the need for various components of finished storage as defined under the term "Components of Finished Water Storage" in Section 003. The requirement for storage may be reduced when the source and treatment facilities have sufficient capacity with standby power to supply peak demands of the system. (3-30-07)
- **02. Location.** Storage facilities shall be located in a manner that protects against contamination, ensures structural stability, *and* protects against flooding, and provides year-round access by vehicles and equipment needed for repair and maintenance.

  (3-30-07)(\_\_\_\_)
- **a.** If the bottom elevation of a storage reservoir must be below normal ground surface, it shall be placed above the seasonal high ground water table. (3-30-07)
- **b.** Sewers, drains Non-potable mains and services, standing water, and similar sources of possible contamination must be kept at least fifty (50) feet from the reservoir any partially buried or below-ground storage structure or facility, except that gravity sewers non-potable mains and services constructed of potable water main quality class pipe are allowed as close as twenty (20) feet from the reservoir a partially buried or below-ground storage structure or facility. Partially buried or below-ground storage structures or facilities shall be located a minimum of fifty (50) feet from the nearest property line.
- **c.** No public water supply storage tank shall be located within five hundred (500) feet of any municipal or industrial wastewater treatment plant or any land which is spray irrigated with wastewater or used for sludge disposal. (3-30-07)
- **d.** The top of a partially buried storage structure shall not be less than two (2) feet above normal ground surface. (3-30-07)
- <u>e.</u> <u>Ground-level or elevated storage structures or facilities shall be located a minimum of twenty (20) feet from the nearest property line and a minimum of twenty (20) feet from any potential source of contamination.</u>

	<del>\</del>
	<b>Protection from Contamination</b> . All finished water storage structures shall have suitable which exclude birds, animals, insects, and excessive dust. The installation of appurtenances, such as e done in a manner that ensures no damage to the tank, coatings or water quality, or corrects any irred. (3-30-07)
<b>04.</b> shall be provided	<b>Protection from Trespassers</b> . Fencing, locks on access manholes, and other necessary precautions to prevent trespassing, vandalism, and sabotage. (3-30-07)
	<b>Drains</b> . No drain on a water storage structure may have a direct connection to a sewer or storm shall allow draining the storage facility for cleaning or maintenance without causing loss of stribution system. (3-30-07)
metal screen inst sufficient diamete inlet structure or	Overflow. Overflow pipes of any storage structure or facility shall discharge to daylight in a way e the possibility of backflow to the reservoir and, where practical, be provided with an expanded alled within the pipe that will exclude rodents and deter vandalism. The overflow pipe shall be of er to permit waste of water in excess of the filling rate. The overflow shall discharge over a drainage a splash plate and, when practical, discharge at an elevation between twelve (12) and twenty-four e the receiving surface.
a. access tube.	When an internal overflow pipe is used on <i>elevated</i> <u>above-ground</u> tanks, it shall be located in the (3 30 07)()
<b>b.</b> structures or faci length and either	The overflow for <i>a</i> ground-level, <i>storage reservoir</i> partially buried, or below-ground storage <u>lities</u> shall <i>open downward and</i> have a vertical section of pipe at least two (2) pipe diameters in ()
<u>i.</u> practical <del>,</del> or an ex	<u>bBe</u> screened with a twenty-four (24) mesh noncorrodible screen installed within the pipe when spanded metal screen installed within the pipe plus a weighted flapper valve <u>or check</u> ; or ()
<u>ii.</u> erosion shall be p	Be an equivalent system acceptable to the Department. A splash pan or similar provision to prevent provided at the base of the overflow.  (3-30-07)()
	The overflow pipe shall be of sufficient diameter to permit waste of water in excess of the filling we shall be brought down to an elevation between twelve (12) and twenty-four (24) inches above and discharge over a drainage inlet structure or a splash plate.
	Access. Finished water storage structures shall be designed with reasonably convenient access to leaning and maintenance. At least two (2) manholes shall be provided above the waterline at each ent where space permits.  (3-30-07)
a.	The following access requirements apply to <i>elevated</i> <u>above-ground</u> storage structures; (3 30 07)()
	At least one (1) of the access manholes shall be framed at least four (4) inches above the surface of ening. The manholes shall be fitted with a solid water tight cover which overlaps the framed opening in around the frame at least two (2) inches, shall be hinged on one side, and shall have a locking (3-30-07)
ii. the reviewing aut	All other manholes or access ways shall be bolted and gasketed according to the requirements of thority, or shall meet the requirements of the Subsection 544.07.a.i. (3-30-07)
<b>b.</b> structures:	The following access requirements apply to ground_level, partially buried, or below-ground storage (3-30-07)()
i.	Each manhole shall be elevated at least twenty-four (24) inches above the top of the tank or

covering sod, whichever is higher.

- ii. Each manhole shall be fitted with a solid water tight cover which overlaps a framed opening and extends down around the frame at least two (2) inches. The frame shall be at least four (4) inches high. Each cover shall be hinged on one side, and shall have a locking device. (3-30-07)
- **Vents.** Finished water storage structures shall be vented. The overflow pipe shall not be considered a vent. Open construction between the sidewall and roof is not permissible. Vents shall: (3-30-07)
  - **a.** Prevent the entrance of surface water and rainwater and extend twelve (12) inches above the roof. (3-30-07)
  - **b.** Exclude birds and animals. (3-30-07)
  - **c.** Exclude insects and dust, as much as this function can be made compatible with effective venting. (3-30-07)
- **d.** On ground-level, <u>partially buried</u>, <u>or below-ground</u> structures, open downward with the opening at least twenty-four (24) inches above the roof or sod and covered with twenty-four (24) mesh non-corrodible screen. The screen shall be installed within the pipe at a location least susceptible to vandalism.
- **e.** On *elevated* <u>above-ground</u> tanks and standpipes, open downward, and be fitted with four (4) mesh non-corrodible screen.
- **Roof and Sidewall**. The roof and sidewalls of all water storage structures must be watertight with no openings except properly constructed vents, manholes, overflows, risers, drains, pump mountings, control ports, or piping for inflow and outflow. Particular attention shall be given to the sealing of roof structures which are not integral to the tank body.

  (3-30-07)
- **a.** Any pipes running through the roof or sidewall of a metal storage structure must be welded, or properly gasketed. In concrete tanks, these pipes shall be connected to standard wall castings which were poured in place during the forming of the concrete. (3-30-07)
- **b.** Openings in the roof of a storage structure designed to accommodate control apparatus or pump columns shall be curbed and sleeved with proper additional shielding to prevent contamination from surface or floor drainage. (3-30-07)
- **c.** The roof of the storage structure shall be sloped to facilitate drainage. Downspout pipes shall not enter or pass through the reservoir. Parapets, or similar construction which would tend to hold water and snow on the roof, will not be approved unless adequate waterproofing and drainage are provided. (3-30-07)
- **d.** Reservoirs with pre-cast concrete roof structures must be made watertight with the use of a waterproof membrane or similar product. (3-30-07)
- **10. Construction Materials.** Materials used in storage facility construction shall meet the requirements for water contact surfaces set forth in Subsection 501.01. Porous materials such as wood or concrete block are not acceptable for use in storage construction. (3-30-07)
- 11. **Protection from Freezing**. Finished water storage structures and their appurtenances, especially the riser pipes, overflows, and vents, shall be designed to prevent freezing which will interfere with proper functioning. (3-30-07)
- **12. Internal Catwalk**. Every catwalk over finished water in a storage structure shall have a solid floor with sealed raised edges, designed to prevent contamination from shoe scrapings and dirt. (3-30-07)
- **13. Silt Stops**. Removable silt stops shall be provided to prevent sediment from entering the reservoir discharge pipe. (3-30-07)

- **14. Grading.** The area surrounding a ground-level, <u>partially buried</u>, <u>or below-ground</u> structures shall be graded in a manner that will prevent surface water from standing within fifty (50) feet of it. (3-30-07)(\_\_\_\_\_)
- **15. Coatings and Cathodic Protection.** Proper protection shall be given to metal surfaces by paints or other protective coatings, by cathodic protective devices, or by both. (3-30-07)
- **16. Disinfection.** Storage facilities shall be disinfected in accordance with AWWA Standard C652, incorporated by reference into these rules at Subsection 002.01. Two (2) or more successive sets of samples, taken at twenty-four (24) hour intervals, shall indicate microbiologically satisfactory water before the facility is placed into operation. (3-30-07)
- **17. Abandonment**. All unused subsurface storage tanks shall be removed and backfilled, or abandoned by extracting residual fluids and filling the structure with sand or fine gravel. (3-30-07)

### (BREAK IN CONTINUITY OF SECTIONS)

#### 546. FACILITY AND DESIGN STANDARDS: DISTRIBUTION SYSTEM STORAGE FACILITIES.

- **01. Design**. The applicable design standards of Section 544 shall be followed for distribution system storage. (3-30-07)
- **O2. Isolation**. Finished water storage structures which provide pressure directly to the distribution system shall be designed so they can be isolated from the distribution system and drained for cleaning or maintenance without causing a loss of pressure in the distribution system. <u>If the finished water storage structure provides fire flow for the water system, the water system owner shall provide the local fire authority advance notification of cleaning or maintenance events which isolate the structure from the distribution system and reduce available fire flow to less than the minimum required by the local fire authority.

  (3-30-07)(\_\_\_\_)</u>
- **O3. Drain.** Drains shall discharge to daylight in a way that will preclude the possibility of backflow to the reservoir and, where practical, be provided with an expanded metal screen installed within the pipe that will exclude rodents and deter vandalism. The drain shall, when practical, discharge at an elevation between twelve (12) and twenty-four (24) inches above the receiving surface, and discharge over a drainage inlet structure or a splash plate.
- **04. Level Controls**. Adequate controls shall be provided to maintain levels in distribution system storage structures. Level indicating devices shall be provided at a central location. (3-30-07)

#### (BREAK IN CONTINUITY OF SECTIONS)

# 552. FACILITY AND DESIGN STANDARDS: OPERATING CRITERIA FOR PUBLIC WATER SYSTEMS.

- 01. Quantity and Pressure Requirements. Design requirements regarding pressure analysis are found in Section 542.13. (12-1-92)(\_\_\_\_\_)
- **a.** Minimum Quantity. The capacity of a public drinking water system shall *in no instance be less than* be at least eight hundred (800) gallons per day per residence, *plus irrigation flows*. (5-3-03)(\_\_\_\_\_)
- i. The minimum capacity of eight hundred (800) gallons per day represents the maximum day demand rate exclusive of irrigation and fire flow requirements.

- ii. The minimum capacity of eight hundred (800) gallons per day is only acceptable if the public drinking water system has equalization storage of finished water in sufficient quantity to compensate for the difference between a water system's maximum pumping capacity and peak hour demand.
- iii. The design capacity of a public drinking water system for material modifications may be less than eight hundred (800) gallons per day per residence if the water system owner provides information that demonstrates to the Department's satisfaction the maximum day demand for the system, exclusive of irrigation and fire flows, is less than eight hundred (800) gallons per day per residence.
- **b.** Pressure. If the Department receives a complaint from a customer or customers of a public drinking water system regarding inadequate or excessive pressure, the Department may, after initial investigation by the water system or the Department, require the public water system to conduct a local pressure monitoring study to diagnose and correct pressure problems. (3-30-07)
- i. Any public water system shall be capable of providing sufficient water during maximum day demand conditions, including fire flow to maintain a minimum pressure of twenty (20) psi throughout the distribution system, at ground level, as measured at the service connection or along the property line adjacent to the consumer's premises.

  (3-30-07)
- ii. Any The following public water systems constructed or significantly modified after July 1, 1985, or service areas of public water systems shall maintain a minimum pressure of forty (40) psi throughout the distribution system, during peak hourly demand conditions, excluding fire flow, measured at the service connection or along the property line adjacent to the consumer's premises.
- (1) Existing water systems that are planning to expand their service area shall meet the criteria in Subsections 552.01.b.i. and 552.01.b.ii. in the new service area. Any public water system constructed or substantially modified after July 1, 1985.

  (4-11-06)(\_\_\_\_\_)
- (2) Compliance with these requirements by water systems that do not have a meter vault or other point of access at the service connection or along the property line adjacent to the consumer's premises where pressure in the distribution system can be reliably measured shall be determined by measurements within the consumer's premises, or at another representative location acceptable to the Department. Any new service areas. (5 3 03)(
- (3) Any public water system that is undergoing material modification where it is feasible to meet the pressure requirements as part of the material modification.
- iii. Any public water system shall keep static pressure within the distribution system below one hundred (100) psi and should ordinarily keep static pressure below eighty (80) psi. Pressures above one hundred (100) psi shall be controlled by pressure reducing devices installed in the distribution main. If system modification will cause pressure to routinely exceed eighty (80) psi, the water system shall notify affected customers. The Department may approve the use of pressure reducing devices at individual service connections on a case by case basis, if it can be demonstrated that higher pressures in portions of the distribution system are required for efficient system operation. If system modification will cause pressure to routinely exceed eighty (80) psi, or if a check valve or an individual pressure reducing device is added to the service line, the water system owner shall notify affected customers.
- iv. The Department may allow the installation of booster pump systems at individual service connections on a case by case basis. However, such an installation may only occur with the full knowledge and agreement of the public water system, including assurance by the water system that the individual booster pump will cause no adverse effects on system operation. (4-11-06)
- v. When pressures within the system are known to have fallen below twenty (20) psi, the water system must provide public notice and disinfect the system. (5-3-03)
- vi. Compliance with these requirements by water systems that do not have a meter vault or other point of access at the service connection or along the property line adjacent to the consumer's premises where pressure in the distribution system can be reliably measured shall be determined by measurements within the consumer's

# DEPARTMENT OF ENVIRONMENTAL QUALITY Idaho Rules for Public Drinking Water Systems

Docket No. 58-0108-0801 Proposed Rulemaking

premises, or at another representative location acceptable to the Department.

**c.** Fire Flows. Any public water system designed to provide fire flows shall ensure that such flows are compatible with the water demand of existing and planned fire fighting equipment and fire fighting practices in the area served by the system. (5-3-03)

**d.** Irrigation Flows. (12-1-92)

- i. Any public water system constructed after November 1, 1977, shall be capable of providing water for uncontrolled, simultaneous foreseeable irrigation demand, which shall include all acreage that the system is designed to irrigate. (5-3-03)
- (1) The Department must concur with assumptions regarding the acreage to be irrigated. In general, an assumption that no outside watering will occur is considered unsound and is unlikely to be approved. (5-3-03)
- (2) An assumption of minimal outside watering, as in recreational subdivisions, may be acceptable if design flows are adequate for maintenance of "green zones" for protection against wildland fire. (5-3-03)
  - ii. The requirement of Subsection 552.01.d.i. may be modified by the Department if: (5-3-03)
  - (1) A separate irrigation system is provided; or (12-10-92)
- (2) The supplier of water can regulate the rate of irrigation through its police powers, and the water system is designed to accommodate a regulated rate of irrigation flow. The Department may require the water system to submit a legal opinion addressing the enforceability of such police powers. (5-3-03)
- iii. If a separate non-potable irrigation system is provided for the consumers, all mains, hydrants and appurtenances shall be easily identified as non-potable. The Department must concur with a plan to ensure that each new potable water service is not cross-connected with the irrigation system. (5-3-03)

**02.** Ground Water. (12-10-92)

- **a.** Public water systems constructed after July 1, 1985, and supplied by ground water, shall treat water within the system by disinfection if the groundwater source is not protected from contamination. (12-10-92)
- **b.** The Department may, in its discretion, require disinfection for any existing public water system supplied by ground water if the system consistently exceeds the MCL for coliform, and if the system does not appear adequately protected from contamination. Adequate protection will be determined based upon at least the following factors:

  (12-10-92)
  - i. Location of possible sources of contamination; (12-10-92)
  - ii. Size of the well lot; (12-10-92)
  - iii. Depth of the source of water; (12-10-92)
  - iv. Bacteriological quality of the aquifer; (12-10-92)
  - v. Geological characteristics of the area; and (12-10-92)
  - vi. Adequacy of development of the source. (12-10-92)
- **03. Operating Criteria.** The operating criteria for systems supplied by surface water or ground water under the direct influence of surface water shall be as follows: (12-10-92)
- **a.** Each system must develop and follow a water treatment operations plan acceptable to the Department, by July 31, 1993, or within six (6) months of installation of filtration treatment, whichever is later. For a

maximum of twelve (12) months, this may be a draft operations plan based on pilot studies or other criteria acceptable to the Department. After twelve (12) months the plan shall be finalized based on full scale operation.

(12-10-92)

- **b.** The purveyor shall ensure that treatment facilities are operated in accordance with good engineering practices such as those found in the Recommended Standards for Water Works, A Report of the Water Supply Committee of the Great Lakes Upper Mississippi River Board of Public Health and Environmental Managers as set forth in Subsection 002.02.c., or other equal standard designated by the Department. (4-6-05)
- shall conduct monitoring specified by the Department for a trial period specified by the Department before serving water to the public in order to protect the health of consumers served by the system. (3-30-07)
- **O4. Chlorination**. Systems that regularly add chlorine to their water are subject to the provisions of Section 320. Systems using surface water or ground water under the direct influence of surface water, are subject to the disinfection requirements of Sections 300 and 518. (3-30-07)
- **a.** Systems using only ground water that add chlorine for the purpose of disinfection, as defined in Section 003, are subject to the following requirements: (4-6-05)
- i. Chlorinator capacity shall be such that the system is able to demonstrate that it is routinely achieving four (4) logs (ninety-nine point ninety-nine percent) (99.99%)) inactivation of viruses. The required contact time will be specified by the Department. This condition must be attainable even when the *maximum* <u>peak</u> hourly demand coincides with anticipated maximum chlorine demands.

  (4-6-05)(\_\_\_\_)
  - ii. A detectable chlorine residual shall be maintained throughout the distribution system. (4-6-05)
- iii. Automatic proportioning chlorinators are required where the rate of flow is not reasonably constant. (12-10-92)
- iv. Analysis for free chlorine residual shall be <u>made</u> <u>conducted at a location at or prior to the first service connection</u> at least daily and records of these analyses shall be kept by the supplier of water for at least one (1) year. A report of all daily chlorine residual measurements for each calendar month shall be submitted to the <u>Department no later than the tenth day of the following month.</u> The frequency of measuring free chlorine residuals shall be sufficient to detect variations in chlorine demand or changes in water flow.

  (4 6 05)
  - v. A separate and ventilated room for gas chlorination equipment shall be provided. (12-10-92)
- vi. The Department may, in its discretion, require a treatment rate higher than that specified in Subsection 552.04.a.i. (3-30-07)
- vii. When chlorine gas is used, chlorine leak detection devices and safety equipment shall be provided in accordance with the 1992 Recommended Standards for Water Works, as set forth in Subsection 002.02.e and equipped with both an audible alarm and a warning light.

  (12 10 92)(\_\_\_\_\_)
- viii. The Department may require redundant chlorine pumping capabilities with automatic switchover for systems with documented source water contamination problems and that lack adequate storage to supply the system during a pump failure.
- **b.** Systems using only ground water that add chlorine for the purpose of maintaining a disinfectant residual in the distribution system, when the source(s) is not at risk of microbial contamination, are subject to the following requirements: (4-6-05)
- i. Automatic proportioning chlorinators are required where the rate of flow is not reasonably constant. (4-6-05)
  - ii. Analysis for free chlorine residual shall be made at a frequency that is sufficient to detect variations

in chlorine demand or changes in water flow.

(4-6-05)

**c.** Systems using only ground water that add chlorine for other purposes, such as oxidation of metals or taste and odor control, when the source(s) is known to be free of microbial contamination, must ensure that chlorine residual entering the distribution system after treatment is less than four (4.0) mg/L. The requirements in Subsection 552.04.b.ii. also apply if the system maintains a chlorine residual in the distribution system. (3-30-07)

**05.** Fluoridation. (12-1-92)

**a.** Commercial sodium fluoride, sodium silico fluoride and hydrofluosilicic acid which conform to the applicable American Water Works Association (AWWA) Standards, incorporated by reference into these rules at Subsection 002.01, are acceptable. Use of other chemicals shall be specifically approved by the Department.

(3-30-07)

- **b.** Fluoride compounds shall be stored in covered or unopened shipping containers. (3-30-07)
- **c.** Provisions shall be made to minimize the quantity of fluoride dust. Empty bags, drums, or barrels shall be disposed of in a manner that will minimize exposure to flouride dusts. (3-30-07)
- **d.** Daily records of flow and amounts of fluoride added shall be kept. An analysis for fluoride in finished water shall be made at least weekly. Records of these analyses shall be kept by the supplier of water for five (5) years. (12-10-92)
- **Of.** Cross Connection Control Program Community Water Systems. The water purveyor is responsible through its cross connection control program to take reasonable and prudent measures to protect the water system against contamination and pollution from cross connections through premise isolation, internal or in-plant isolation, fixture protection, or some combination of premise isolation, internal isolation, and fixture protection. Pursuant to Section 543, all suppliers of water for community water systems shall implement a cross connection control program to prevent the entrance to the system of materials known to be toxic or hazardous. See AWWA "Cross Connection Control Manual," referenced in Subsection 002.02. The water purveyor is responsible to enforce the system's cross connection control program. The program will at a minimum include: (3-30-07)(\_\_\_\_\_\_\_)
- a. An inspection once a year of all facilities listed in Subsection 900.02 (Table 2) program to locate cross connections and determine required suitable protection. For new connections, suitable protection must be installed prior to providing water service.

  (3-30-07)(\_\_\_\_)
- Appropriate and adequate backflow prevention assemblies for various facilities, fixtures, equipment, and uses of water is provided in Subsection 900.02 (Table 2) must be selected from either the Pacific Northwest Cross Connection Control Manual, the Uniform Plumbing Code, the Environmental Protection Agency's Cross Connection Control Manual, the USC Manual of Cross Connection Control, or other sources deemed acceptable by the Department. The assemblies must comply with local ordinances.
- c. Annual inspections and testing of all installed backflow prevention assemblies by a tester licensed by a licensing authority recognized by the Department. Testing shall be done in accordance with the test procedures published by the University of Southern California Foundation for Cross-Connection Control and Hydraulic Research. See the USC Manual of Cross-Connection Control referenced in Subsection 002.02. (3-30-07)
- **d.** Discontinuance of service to any facility where suitable backflow protection has not been provided for a cross connection. (3-30-07)
- **O7.** Cross Connection Control Program Non-Community Water Systems. All suppliers of water for non-community water systems shall ensure that cross connections do not exist or are isolated from the potable water system by an approved backflow prevention assembly. Backflow prevention assemblies shall be inspected and tested annually for functionality on a regular basis by an Idaho licensed tester, as specified in Subsection 552.06.c.

<del>(3 30 07)</del>(\_\_\_\_)

## (BREAK IN CONTINUITY OF SECTIONS)

#### 554. LICENSE REQUIREMENTS.

#### 01. Licensed Operator Required.

(4-6-05)

- a. Owners of all community and nontransient noncommunity public drinking water systems must place the direct supervision of their drinking water system, including each treatment facility and/or distribution system, under the responsible charge of a properly licensed operator.

  (4-6-05)(\_\_\_\_)
- **b.** Owners of all surface water systems must place the direct supervision of their public drinking water system under the responsible charge of a properly licensed operator. (4-6-05)
- **02. Responsible Charge Operator License Requirement**. An operator in responsible charge of a public drinking water system must hold a valid license equal to or greater than the classification of the public water system where the responsible charge operator is in responsible charge. (4-6-05)
- **O3.** Substitute Responsible Charge Operator License Requirement. At such times as the responsible charge operator is not available, a substitute responsible charge operator shall be designated to replace the responsible charge operator. A substitute responsible charge operator of a public water system must hold a valid license equal to or greater than the classification of the public water system where the substitute responsible charge operator is in responsible charge. (4-6-05)
- **O4. Shift Operator Requirement.** Any public drinking water system subject to these requirements with multiple operating shifts must have a designated properly licensed operator available for each operating shift. An on-duty designated shift operator does not replace the requirements in Subsections 554.01 and 554.03 for responsible charge operator coverage during all operating shifts. (4-6-05)
- **05. Water Operator License Requirement**. All operating personnel at public drinking water systems subject to these requirements making process control/ system integrity decisions about water quality or quantity that affect public health must hold a valid and current license. (4-6-05)

### (BREAK IN CONTINUITY OF SECTIONS)

#### 900. TABLES.

# 01. Table 1 -- Minimum Distances From a Public Water System Well.

Minimum Distances from a Public Water System Well					
Gravity sewer line	50 feet				
Any potential source of contamination	50 feet				
Pressure sewer line	100 feet				
Individual home septic tank	100 feet				
Individual home disposal field	100 feet				
Individual home seepage pit	100 feet				
Privies	100 feet				

Minimum Distances from a Public Water System Well						
Livestock	50 feet					
<u>Drainfield - standard subsurface disposal</u> <u>module</u>	100 feet					
Absoprtion module - large soil absorption system	150 - 300 feet, see IDAPA 58.01.03					
Canals, streams, ditches, lakes, ponds and tanks used to store non-potable substances	50 feet					
Storm water facilities disposing storm water originating off the well lot	50 feet					
Municipal or industrial wastewater treatment plant	500 feet					
Reclamation and reuse of municipal and industrial wastewater sites	<u>See IDAPA</u> <u>58.01.17</u>					
Biosolids application site	<u>1,000 feet</u>					

<del>(3-30-07)</del>(\_\_\_\_)

# 02. Table 2 -- Selection Chart for Minimum Backflow Prevention Services.

SELECTION CHART FOR MINIMUM BACKFLOW PREVENTION DEVICES							
FACILITIES, FIXTURES, EQUIPMENT, OR USE OF WATER	ATMOSPHERIC TYPE VACUUM BREAKER	PRESSURE TYPE VACUUM BREAKER	DOUBLE- CHECK VALVE- ASSEMBLY	REDUCED- PRESSURE- BACKFLOW- PREVENTER	AIR GAP		
Animal Watering	X	X		X	X		
Aspirators, harmful substance	X	X		X	X		
Autopsy Equipment	X	X		X			
Autoclaves				X			
Boiler Feeds without harmful chemicals			X				
Boiler Feeds with harmful chemicals				X	X		
Bed Pan Washers	X	X					
Cuspidors, Open Outlet	X	X					
Cuspidors, Valved Outlet		X					
Dairies and Farms				X	X		
Dishwashers	X	X			X		
Domestic Water Booster Pump on service lines			X	X			
Garbage Can Washers		X			X		
Heat Exchangers with transfer fluids			X	X			
High Rise Buildings, 3 stories or more, bldgs. on hill			×	×			

SELECTION CHART FOR MINIMUM BACKFLOW PREVENTION DEVICES						
FACILITIES, FIXTURES, EQUIPMENT, OR USE OF WATER	ATMOSPHERIC TYPE VACUUM BREAKER	PRESSURE- TYPE VACUUM BREAKER	DOUBLE- CHECK VALVE- ASSEMBLY	REDUCED- PRESSURE- BACKFLOW- PREVENTER	AIR GAP	
Irrigation Systems, such as cemeteries, golf courses, playgrounds, parks, estates, ranches, schools, and residential uses with chemicals added				×	×	
Irrigation Systems, such as cemeteries, golf courses, playgrounds, parks, estates, ranches, schools, and residential uses without chemicals added	×	×	×			
Laundries with under rim or bottom-fill inlets, dry cleaning, and dye works	×	×		×	×	
Mobile Home and RV Parks with nonapproved- waste valves		×	×	×		
Mobile Home and RV Parks with below ground level service line termination				×		
Fixing Tees with steam and water used with harmful- substances				×		
Fixing Tees with steam and water used without harmful substances			×			
Private Water Sources which are unmonitored				×		
Radiator-Vats				×	X	
Slaughter Houses				X		
Car Washes using soaps and waxes			X	X		
Chemical Plants				X	X	
Dockside Watering Facilities, Marinas	X		X	X	X	
Film Laboratories				X	X	
Food Processing Plants			X	X	X	
Fertilizer Plants				X	X	
Hospitals handling harmful substances				X		
Lab Sink using toxics (unharmful)	X	X	X	×		
Meat Packing Plants				×		
Medical Bldgs, clinics, laboratories, etc.				×		
Nonpotable Water				×	X	
Oil Refinery and Petroleum Storage Facilities				X		
Sanitariums -	X	X		X		
Sewage Piping or Plants				X	X	
Tank Truck Fill Station				X	X	
Mortuaries -				×		

SELECTION CHART FOR MINIMUM BACKFLOW PREVENTION DEVICES						
FACILITIES, FIXTURES, EQUIPMENT, OR USE OF WATER	ATMOSPHERIC- TYPE VACUUM- BREAKER	PRESSURE TYPE VACUUM BREAKER	DOUBLE- CHECK VALVE- ASSEMBLY	REDUCED- PRESSURE- BACKFLOW- PREVENTER	AIR GAP	
Hoses that could be in contact with animal waste	X	X				
Shampoo Sprays	X	X				
Sterilizers				X		
Steam Cookers using low health risk substance			X			
Steam Cookers using high health risk -substance				×		
Swim Pools, Hot Tubs, private or semiprivate	X	X		X	X	
Swim Pools direct connection	X	X		X	X	
<u>Urinals</u>	X			X		
Water Cooling or Heating Coils		X		X		
Water Closets	X			X		

X -- indicates suitable protection to be required by the public water system. For facilities with multiple options, the public water system will determine the lowest degree of protection that is acceptable. (4-6-05)

032. Table 32 - Well Casing Standards for Public Water System Wells.

STEEL PIPE								
		WEIGHT PER FOOT (pounds)						
DIAMETER (inches) THICKNESS							Plain Ends couplings	With Threads and
SIZE	External	Internal	(inches)	(calculated)	(nominal)			
6 (id) *	6.625	6.065	0.280	18.97	19.18			
8	8.625	7.981	0.322	28.55	29.35			
10	10.750	10.020	0.365	40.48	41.85			
12	12.750	12.000	0.375	49.56	51.15			
14 (od) *	14.000	13.250	0.375	54.57	57.00			
16	16.000	15.250	0.375	62.58				
18	18.000	17.250	0.375	70.59				
20	20.000	19.250	0.375	78.60				
22	22.000	21.000	0.500	114.81				
24	24.000	23.000	0.500	125.49				
26	26.000	25.000	0.500	136.17				

STEEL PIPE								
28	28.000	27.000	0.500	146.85				
30	30.000	29.000	0.500	157.53				
32	32.000	31.000	0.500	168.21				
34	34.000	33.000	0.500	178.89				
36	36.000	35.000	0.500	189.57				

\* id = inside diameter od = outside diameter